


SCIENTIFIC AMERICAN

[Entered at the Post Office of New York, N. Y., as Second Class Matter. Copyright, 1908, by Munn & Co.]


Vol. XCVIII.—No. 20.
ESTABLISHED 1845.

NEW YORK, MAY 16, 1908.

[10 CENTS A COPY
\$3.00 A YEAR.]



The Caterpillar Motor, Showing the Weight-Carrying wheels.



A 35-Horse-Power Caterpillar Motor Crossing a Brook on Its Own Bridge.

A CURIOUS MEANS OF PROPULSION.—[See page 348.]

SCIENTIFIC AMERICAN

ESTABLISHED 1845

MUNN & CO. - Editors and Proprietors

Published Weekly at

No. 361 Broadway, New York

CHARLES ALLEN MUNN, President

361 Broadway, New York

FREDERICK CONVERSE BEACH, Sec'y and Treas.

361 Broadway, New York

TERMS TO SUBSCRIBERS.

One copy, one year, for the United States or Mexico \$3.00
 One copy, one year, for Canada 3.75
 One copy, one year, to any foreign country, postage prepaid, 18s. 6d. 4.50

THE SCIENTIFIC AMERICAN PUBLICATIONS.

Scientific American (established 1845) \$3.00 a year
 Scientific American Supplement (established 1876) 5.00 "
 American Homes and Gardens 3.00 "
 Scientific American Export Edition (established 1878) 3.00 "

The combined subscription rates and rates to foreign countries, including Canada, will be furnished upon application.

Remit by postal or express money order, or by bank draft or check.

MUNN & CO., 361 Broadway, New York.

NEW YORK, SATURDAY, MAY 16, 1908.

The Editor is always glad to receive for examination illustrated articles on subjects of timely interest. If the photographs are sharp, the articles short, and the facts authentic, the contributions will receive special attention. Accepted articles will be paid for at regular space rates.

INVESTIGATIONS FOR THE GATUN DAM.

With a view to ascertaining with absolute certainty the conditions at the site of the Gatun Dam, an elaborate investigation is now being carried on, the purpose of which, as outlined by Mr. Saville, the engineer in charge, is to determine the characteristics of the various soils and rocks which are to be used in the construction of the dam, the nature of the materials underlying the foundations, and the ground beneath the proposed embankments and walls. The most important experiment will be the construction of a section of a dam one-twelfth the size of the actual Gatun structure. This will be built in a water-tight wooden tank, into which the materials will be pumped, under conditions similar to those that will exist when the dam itself is built. The completed section will be subjected to water pressure for a considerable length of time, and records will be kept of the rate at which water percolates into the material. Horizontal pipes will lead from the interior of the dam section out through the side of the tank, where they will connect with glass gages. By this means the "slope of saturation" can be determined, and the slope of the dam can be determined. It has lost all of its pressure. Various materials will be tested in the tank in order to determine which is the best to use in the great dam itself. Another set of experiments consists in placing a layer of material in a tank, 3 feet in diameter and 5 feet high, and exposing it to a constant head of water. By means of glass gages a determination will be made of the amount of water that passes through under various heads, and in this way it will be known what thickness of the particular material under test will be sufficient to make the embankment practically impervious. Studies are also being made of the landslides along the Isthmus, the friction angle and coefficient of friction for various materials being determined by means of large sliding boxes. Upon Gatun Island a huge exploration pit 20 feet square is being carried down to a depth of at least 100 feet. Samples of the material at every 10 feet of depth will be subjected to mechanical and filtration tests to determine its behavior. To ascertain the action of the material under heavy water pressure, cylinders of the soil and rock are placed in strong iron tubes and subjected to water pressures varying from 20 pounds to 80 pounds per square inch. Also tests are being made of the several rocks encountered, to determine their resistance to abrasion and to the eroding action under pressure. Wash-drill and diamond-drill investigations are being carried on upon a more extensive scale than before. In the words of the Canal Record, "The ground is being so thoroughly explored, and to such great depth, that it is felt that no conditions can obtain which will materially change the plans after they have once been decided upon."

TO SECURE BETTER RAILS.

The agitation of last year against the poor quality of rails turned out by the rail mills is bearing good fruit. More than one organization has been investigating the subject of rail manufacture, in the endeavor to frame new specifications designed to secure a rail that will stand up faithfully to its work. Perhaps the most important of these is the committee of the American Railway Association on "Standard Rail and Wheel

Sections," whose report presented at the New York meeting of April last is now before us.

It will be remembered that in the series of articles which we published some twelve months ago, it was shown that the most serious point of controversy between the railways and the rail mills was the question of "discard," or the amount of the ingot which should be rejected, before the latter was passed through the rolls. The railways were in favor of a discard of from 25 to 30 per cent of the top of the ingot. The rail mills, on the other hand, had reduced the discard, until in the current practice, it was not more than 8 or 10 per cent, and sometimes even less. The object of rejecting such a large percentage as 25, was to get rid of the segregated material and of the pipes or cavities which develop with more or less seriousness during the cooling of the ingot. Now, in the investigation of the American Railway Association, the committee decided that it would be preferable to aim at securing perfect rails rather by testing the finished rail than by making any close specifications as to the way in which the rails should be manufactured in the mills. It was decided that the best results would be obtained by abolishing the discard altogether, and basing rejections of the rails upon the results of tests made upon rails rolled from the upper portion of the ingot. To determine the practicability of this method, a trial lot of rails was rolled from the ingot without any discard, and the rails were then tested to destruction and the fracture examined. This test proved to the satisfaction of the committee that if "pipes" or other physical defects were present, they could be detected; and the committee was satisfied that rail manufacture could be so conducted that physical defects of any kind whatsoever would be reduced to a minimum. It will be remembered that the committee of the Pennsylvania Railroad, as was mentioned recently in this journal, following the same idea, drew up a specification which provided that whenever physical defects were discovered, all top rails of the heat should be rejected. This would mean a discard of between 25 and 30 per cent of the entire metal in the heat, should physical defects be found; and it was realized that a requirement of this kind would at once secure the rejection of defective rails, and insure the practice of very careful manufacture on the part of the rail mills.

The question of segregation was carefully considered by the committee, and it was agreed that if all segregated metal must be rejected it would be necessary to discard more than a third of the upper part of the ingot. Furthermore, the analyses of rails that had been many years in service indicated that a wide variation in chemical composition due to segregation may occur without affecting the safety or wearing quality of the rail. None of the experts consulted was ready to say what the limit of this variation might safely be, and the committee state that they will be unable to determine definitely the effect of segregation until after they had opportunity to observe the results obtained with rails rolled under the new specifications eliminating rails containing physical defects.

The committee are convinced that with regard to the question of phosphorus, it will be impossible for the mills to furnish more than a small percentage of the total rails required if they are made under the Bessemer process, with a phosphorus specification of less than 0.10. Railroads desiring to obtain low-phosphorus rails are reminded that they have the option of using open-hearth steel. The specifications lay down very detailed instructions as to the process of manufacture and testing, and, except for the chemical composition, these specifications apply both for the Bessemer and open-hearth process. The chemical composition of open-hearth steel rails, weighing 100 pounds to the yard, calls for the following percentages: Carbon, 0.70 to 0.80; manganese, 0.75 to 1.00; silicon, 0.10 to 0.20; phosphorus, not to exceed 0.04; and sulphur, not to exceed 0.06. For Bessemer-steel rails the chemical composition is: Carbon, 0.46 to 0.56; manganese, 0.90 to 1.20; silicon, 0.10 to 0.20; phosphorus, not to exceed 0.10; and sulphur, not to exceed 0.075. In these specifications the committee consider that the nearest approach to a satisfactory single standard type of rail has been arrived at consistent with present engineering knowledge and opinion. Provision has been made for the rejection of all rails containing dangerous physical defects; and the adoption of new and better balanced sections will enable the manufacturers to roll the rails at lower temperatures, thus insuring a finer grain and better wearing quality, as well as reducing the internal stresses.

A HEAT FLYWHEEL.

A highly successful example of the utilization of the exhaust steam from a reciprocating engine is to be found at the Wisconsin Steel Company's mill at South Chicago, where the exhaust from a large blooming mill engine is used to drive a steam turbine. The average indicated horse-power of the engine is 1,010, with a consumption of steam of 54 pounds per horse-power per hour. The most interesting part of this plant is a regenerator, or accumulator, which absorbs the

energy of the exhaust steam and gives it up to the turbine as it is required. In the course of a paper on this remarkable plant, presented by Henry H. Wait before the American Institute of Electrical Engineers, this accumulator was very aptly described as a heat flywheel.

The exhaust from the engine first passes through a receiver, provided with baffle plates, which deadens the puffs and equalizes the flow. It then passes to the accumulator, through a series of finely-perforated pipes, through which the steam is led into the body of water in the accumulator. More or less of this steam is condensed, and gives up its heat. The steam enters the accumulator, which is operated at about atmospheric pressure, at about 212 deg. Fahr., and tends to heat the water to the same temperature. From the accumulator the steam is led to a turbine of the Rateau type. Should the blooming-mill engine stop running and the flow of exhaust steam be discontinued, there will be present in the accumulator a mass of water at 212 deg. Fahr.; and if the turbine is running under a continuous load, the flow of steam will reduce the pressure. The water will then boil under the lower pressure, and give off steam at about the atmospheric pressure. If the blooming-mill engine starts up again, the exhaust steam will enter the accumulator at a temperature slightly above that to which the water has fallen on account of the cooling due to the evaporation of the steam drawn off for the turbine, and the whole mass of water will again begin to rise in temperature. To provide for any lengthy stoppage of the reciprocating engine, an automatic reducing valve connected to the steam boilers is so set that it will open whenever the pressure falls below the atmosphere, and deliver live steam to the regenerator.

The practical results obtained by this installation are highly gratifying. It became possible for the mill to shut down two 250-kilowatt engine-driven generators which formerly operated the mill, and for a considerable time the turbine plant took care of the entire electrical load of the mill, utilizing only the exhaust of the blooming engine, and using live steam from the boilers only when the blooming engine was shut down for an abnormal length of time. The installation has resulted in saving the amount of coal necessary to generate the steam for the required for running the generator engines, a saving estimated at from \$10,000 to \$20,000 a year. Tests of two hours' duration of the exhaust-steam turbine showed that the average pressure under the controlling valve was 24.85 pounds; the average vacuum at the exhaust casing, 26.40 pounds; the average consumption of steam per brake horse-power per hour at the turbine was 33.7 pounds; and the average brake horse-power at the turbine shaft was 869. Finally, the total cost of the plant, including oil, attendance, maintenance, and fixed charges, was 0.299 cent per kilowatt hour; these figures being based on a delivery of 51 per cent of the total possible kilowatt hours of the turbine, if it had been operated at its rated load during the three months steam plant was running at nearly full capacity.

FORMER CHIEF ENGINEER STEVENS ON THE CANAL.

It will be remembered that Mr. John F. Stevens, former Chief Engineer of the Panama Canal, was reported in the daily press as having a few weeks delivered an address at New Haven, in which he made certain drastic criticisms of this great work. We are glad to note, however, that extracts from a full copy of his paper, recently published in an esteemed contemporary, show that the press reports were entirely unjustified. What he said was confined largely to an account of the difficult work of organization which confronted him, and occupied practically all his attention while he remained on the Isthmus. This work consisted in the reconstruction of the Panama Railroad, which was absolutely essential before the enormous yardage of excavation to be done could possibly be handled, and the gathering together and making provision for the great number of skilled and unskilled laborers and clerical and supervising forces requisite to carry on the work.

Mr. Stevens makes no criticism of the general plans of the canal; and it is well worthy of note that he went to the Isthmus inclined to favor a sea-level canal, but after making a personal study of the conditions, abandoned it in favor of the high-level, lock canal now being built. During his term of office, he recommended the construction of locks at Miraflores and Pedro Miguel, instead of at La Boca—a change which has recently been approved. Two hundred millions of dollars, in addition to the money already paid to the French company and to the Republic of Panama, should complete the work as planned originally, though, because of changes since made in the locks, the cost must now be greater. It is Mr. Stevens's opinion that after allowing proper time for contingencies, the canal should be in active operation in seven years from the present time.

METCHNIKOFF'S THEORY OF LONGEVITY.

A great many endeavors have been made to fix the duration of human life, and of animal life in general, within limits prescribed by a definite law. The fact that large animals live longer than smaller ones has been made the basis of the statement that the total duration of life is proportional to the time required to reach maturity, since the duration of the period of development of an animal usually varies with its size. This relation is not a simple one, however, for the horse, entirely adult at four years, lives to forty years of age in many cases. The sheep, on the other hand, not fully developed until its fifth year, is quite senile at fourteen.

The period of gestation, also, has been taken as the main factor for the computation of length of life. Too many exceptions are present in this case to make the deduced conclusions reliable. The horse, again an instance, passes through a longer period of embryonic life than does man, yet it does not live more than half as long. Sex apparently has nothing to do with the case, for men and women both seem to have about the same extent of life.

Among the invertebrates, great ages are sometimes reached. Sea anemones have frequently been kept in captivity for over sixty years. Some marine bivalves (*Tridacna gigas*) live to sixty or a hundred years.

In spite of the variability of the life periods of insects, some reach truly great ages, comparatively speaking. Our American seventeen-year locust (*Cicada septendecim*) lives in the larval stage alone, as the name implies, seventeen years.

Reptiles like the tortoise and the crocodile are very long-lived also. Crocodiles have been kept in the Paris Museum of Natural History for more than forty years without showing signs of senescence. In the garden of the Governor of Cape Town, a tortoise has lived for eighty years, and is believed to have reached the two-hundred-year mark. Another, a native of the Galapagos Islands, is known to be 175 years old. The natural inference is that in cold-blooded animals the changes of metabolism are so slow that the organism is not as rapidly altered as in the warm-blooded forms. The truth of this statement has yet to be proved.

The commoner life of birds is for from 15 to 20 years. Canaries have lived in captivity for from 19 to 20 years; gold finches, up to 23 years. Parrots often reach 80 years, and not infrequently a hundred. A raven is known to have reached 69 years, and another 50. In the royal park at Schönbrunn, near Vienna, a white-headed vulture died at 118 years, and a golden eagle at 104.

Going up the scale of development, we find that life is still shorter among the mammals. Elephants seldom live over 100 years. The number of years lived by sheep and by horses we have mentioned before.

Upon inquiring into the causes of these variations in duration of life, Metchnikoff finds the key in the digestive system. The organs of respiration, circulation, and of urinary excretion show no great differences in the various forms of creation. When, however, we reach the digestive tract, the whole aspect changes. This is most markedly shown in birds, for in the various species, the greatest differences in length of life and in the composition of the digestive tract are found.

As spoken of before, parrots are very long-lived. They have a very simple alimentary canal, and a very small number of intestinal microbes, owing to the short time that matter remains in the intestine. Atricius and other cursory birds, provided with a well-developed cæcum, show profuse and varied intestinal flora. They approach the short-lived mammals in length of life. If length of life is due to freedom from intestinal microbes, a preventive of bacterial life must be found. This, according to Metchnikoff, seems to exist in lactic acid.

That lactic acid is a preservative is a time-honored fact. Meat is often preserved in sour milk. Milk itself undergoes lactic fermentation, but it decomposes only under the conditions most propitious for decomposition to take place. Sauerkraut is the product of lactic acid fermentation, and owes its keeping qualities to this substance. The races living upon the various preparations of sour milk are usually found to attain remarkable ages. Cases, both individual and collective, of great age in those living on a diet of curdled milk are almost too numerous to mention. A few, however, may prove instructive. Metchnikoff gives an account of one Riley, who was shipwrecked on the western coast of Africa, and was enslaved by Arabs. He says members of the tribes with whom he came in contact were two or three hundred years old. That these figures are too high is only too probable, nor can they be taken as more than indications, yet they are not without interest, since these Arabs lived upon camel's milk, fresh or soured.

In Bulgaria there is a surprising number of cen-

tenarians; the staple food in Bulgaria is *yahourth*, a soured milk. A laborer of Verdun, Ambroise Jaulet by name, died in 1751 at the age of 111 years. He "ate nothing but unleavened bread, and drank nothing but skimmed milk."

Curdled milk and other similar milk products are the result of the action of lactic-acid bacilli, which produce lactic acid at the expense of milk sugar. In most of these soured milks there are too many different kinds of microbes, often pernicious, associated with the bacillus actually causing the desired fermentation. Therefore it is best to procure some form of ferment which is known to be pure. The preparations of the Bulgarian bacillus are the best for this purpose, according to Metchnikoff.

The Bulgarian bacillus was isolated from *yahourth* by M. Massol. It produces lactic acid in large quantities, while very small quantities of other acids, such as acetic and formic, which are somewhat injurious, are formed.

The method of preparing soured milk advocated by M. Metchnikoff is as follows: "After the milk has been boiled and rapidly cooled, pure cultures of the lactic microbes are sown in it in sufficient quantities to prevent the germination of spores already in the milk and not destroyed by the boiling. The fermentation lasts a number of hours, varying according to the temperature, and finally produces a sour curdled milk, pleasant to the taste, and active in preventing intestinal putrefaction. This milk, taken daily in quantities of from 300 to 500 cubic centimeters, controls the action of the intestine, and stimulates the kidneys favorably."

The bacilli may also be taken dry as small pellets, but a goodly quantity of sugar-containing material, such as jam or the like, must be taken with each tablet, to furnish the necessary material from which the microbes can produce the lactic acid. Metchnikoff claims that he has been himself benefited by his treatment.

COPPER-CLAD STEEL.

By a curious anomaly, steel is at once the strongest and the weakest of metals. Its frailty lies in the scant resistance which it is able to offer to corrosion, even when painted. By still another curious anomaly, copper is at once a weak and a strong metal. Its strength lies in its wonderful ability to resist corrosion. If it were possible to cover the corrodible steel with non-corrodible copper, a problem of vast technical importance would be solved.

Perhaps the most obvious way of utilizing the properties of copper is to deposit it on the steel electrolytically. But it has been found that between the two metals a film of moisture is impounded, which in time causes the steel to corrode and the copper to peel off. A French inventor then hit on the idea of drawing a copper tube over the steel. Still the moisture-filled space existed.

The latest solution, and apparently a successful one, is offered by J. Ferreol Monnot. Instead of drawing one metal over the other, he welds the two together. Broadly stated, his process consists in thoroughly cleaning a base or core of the steel; bringing it up to a welding temperature without permitting access of air and consequent oxidation during heating; contacting with it on the cleaned surfaces a highly-heated, or "supermolten," mass of molten copper; segregating from the mass in immediate proximity to the base a layer of the thickness desired in the subsequent compound ingot; allowing the base and coating layer to cool under or during compression; and drawing the compound ingot so formed to produce the drawn wire desired. The steel core or base used may be an ingot, bar, bloom, billet or other commercial form, and may be of any desired cross-section, as round, square, oval, etc., and of any size.

If the billet is to be made into structural steel wire or rods, where resistance to the corrosion of the elements is alone desired, the copper coating can be very light, indeed as low as ten per cent, by volume, of the steel. If, however, the wire is to be used for the transmission of electric current, the coating is made heavier, in order that it may present less resistance to the current. Hence 30 per cent, 40 per cent, and 50 per cent of the conductivity of a copper wire of the same size is produced, with consequent great increase of tensile strength, because of the presence of the steel. When the billet leaves the coating department, it passes through mammoth steel rolls, where the diameter is brought down to a final size of $\frac{3}{8}$ inch and consequent length. These rolls of wire are then sent into the drawing department, where wire as small as a hair can be turned out. Most wonderful of all, the copper remains on the steel in the same proportion originally found in the billet. The same rolling mills and drawing dies that handle steel alone are used.

The next step will naturally be the adaptation of the process on a larger scale, for the covering of the immense steel girders used in our modern office buildings and other structures.

Copper-clad wire can be made into any kind of standard or twisted cable for ship rigging, catenary suspension, and the like.

When steel is drawn or made into springs, necessarily when hot, a resultant scale of iron oxide materially reduces its strength. Copper-clad metal cannot oxidize thus, because the steel does not come into contact with the air.

Shells or cartridges are not loaded in time of peace in any quantity, because of the deleterious action of brass and smokeless powder upon each other. Brass is used because it provides more strength than copper, which has no such effect.

MACHINE FOR MAKING WINDOW GLASS.

Readers of this journal will doubtless remember an article published in these columns in the issue of December 1, 1906, describing a new machine invented by Irving W. Colburn, Franklin, Pa., for the making of window glass. The machine in question is the first of its kind which has ever been successfully introduced for the commercial manufacture of window glass. It draws a continuous sheet of glass 42 inches in width (although there is no limit of the width) at a linear speed of 56 inches a minute for single strength, and 48 inches a minute for double strength. This it does without the assistance of the gatherers, blowers, snappers, and flatteners usually employed in glass plants. The only skilled men employed are the cutters and the superintendent. The cutters will some day give way to automatic devices. With three men and six boys more glass and better glass can be made by the machine than by thirty-nine men with the cylinder process. At present the plant is running twenty-four hours a day, three shifts of eight hours each.

In the article mentioned only that portion of the machine was described which is actually concerned in the process of drawing the sheet from a pot of molten metal. The subsequent stages through which it passes were not discussed because at that time the machine, although in full operation, was still unprotected by patents, and could not be described in its entirety. Those of our readers who were interested in our previous article will find in the current SUPPLEMENT a complete illustrated description of the machine in which the mechanical process for drawing glass into a sheet and for conveying it through the lehr to the cutting table is fully discussed.

THE CURRENT SUPPLEMENT.

The current SUPPLEMENT, No. 1689, contains among many interesting articles, papers on "Malleable Castings made by Melting Wrought Scrap in the Crucible and in the Open-Hearth Furnace," "Washing and Coking Tests of Coal," and "Machine for Drawing Window Glass Continuously in Any Width." Prof. Watson's treatise on the elements of electrical engineering passes to its seventeenth installment, in which transformers and transformer systems are discussed. Practical problems involved in the Edison concrete house are presented by Percy H. Wilson. E. L. Elliott tells something of the magnitude of the lighting industries. Prof. O. N. Witt discourses instructively on gases and vapors. The life of a radioactive element is presented by A. T. Cameron. Flying-machine inventors will read with interest an article on the Cornu helicopter, in which article very complete information is given about this novel machine. The third installment of Dr. Everette's paper on the formation of mineral veins appears.

MOTORS FOR VITICULTURE.

The application of motors for agricultural purposes, and especially for viticulture, is attracting considerable attention in Europe. In view of this fact, the international competition for motor machinery for viticulture to be held at Palermo, Italy, the coming autumn is interesting. A royal decree sets forth that the machine adjudged the best will be awarded the diploma and about \$2,000, and that the minister of agriculture will purchase two of this class. The second prize consists of a gold medal and about \$600. Application for admission must be sent to the minister of agriculture at Rome not later than August 15, and the machines or apparatus must reach Palermo by the 16th of October.

THE WRIGHT AEROPLANE EXPERIMENTS.

Although we have been unable to authenticate the 2-mile flight of the Wright brothers' new aeroplane noted in our last issue, nevertheless these two secretive gentlemen are apparently experimenting with success at their old camping ground near Kitty Hawk, on the coast of North Carolina. According to the newspaper dispatches, they are making short flights almost daily for the purpose of testing a new steering device, and they expect shortly to make a long-distance flight along the coast. On the 8th instant the longest of ten flights made is reported to have been about $1\frac{1}{2}$ miles in about 2 minutes. The engine of the aeroplane is said to be a 4-cylinder French water-cooled motor of 30 horse-power, weighing 150 pounds.

* The Prolongation of Life. Optimistic Studies by Elie Metchnikoff, sub-director of the Pasteur Institute, Paris. The English Translation by P. Chambers Mitchell, M.A., D.Sc. Oxon., Hon. LL.D., F.R.S. London, 1908. G. P. Putnam's Sons.

THE "CATERPILLAR" TRACTOR.

BY THE ENGLISH CORRESPONDENT OF THE SCIENTIFIC AMERICAN.

For some months past the British military authorities have been experimenting with a new type of tractor for the haulage of heavy vehicles over rough and unstable ground. This machine represents a new development in traction. Briefly, its object is to crawl over the ground, there being a series of feet disposed along the periphery of two heavy side chains passing over fore and aft wheels. As this chain revolves, the feet are successively brought into contact with the ground, thereby impelling the machine forward or backward. Because of its peculiar movement,

about 40 horse-power. The motor is of the Hornsby double-cylinder internal-combustion heavy-oil type. The military engineers submitted the chain tractor to a prolonged series of heavy trials in the sandy and swampy stretches in the vicinity of the Aldershot camp, the results of which exceeded anticipations. Owing to the success of these experiments, the inventors built a second oil-engine-propelled tractor, developing some 20 horse-power, and in order to demonstrate the capabilities of the gasoline motor in the same field, constructed a 30 to 35 horse-power motor car with trailer. The latter two, though of less horse-power than that constructed for the War Office, present

carrying wheels pass over the inside track. The upper part of the chain pulled over by the driving wheel moves forward, and is guided by the front sprocket wheel to form a fresh and endless track. The weight of the tractor being carried on the long curved inverted arch of the chain, the pressure on the ground varies with its condition; and while on hard roads the pressure is less than with ordinary wheels, on soft ground the weight is so distributed that it can travel with safety where draft animals may not venture. The grip on the ground is vastly greater than it is with ordinary wheels, so that great loads can be hauled over ground which has hitherto been impassable. The chain track has a radius which is equal to a wheel 38 feet in diameter.

When it is required to turn, one of the chains is braked hard and the other allowed to travel.

In the gasoline tractor the whole weight of the vehicle is supported and balanced on the two inner wheels, midway between the end wheels and engaging with the inner lower surface of the chain, there being two such wheels on either side. The small wheel mounted above these simply takes the weight of the upper part of the chain. In the larger oil tractor built for the War Office three wheels are disposed on either side to fulfill this end, but we understand that the first-named arrangement has proved more satisfactory, and will be adopted in all future vehicles.

Steering is effected by a wheel mounted in the usual manner, the rotation of which in either direction



General View of the 30 to 35-Horse-Power Caterpillar Motor.

the soldiers at the Aldershot military center, where it is in operation, promptly christened it the "caterpillar."

The engine is the invention of Mr. David Roberts, M.I.M.E., to whose courtesy we are indebted for the information contained in this article and accompanying illustrations. It was evolved as a result of the difficulties encountered in transport operations during the South African war, where the heavy guns could be hauled only by powerful traction engines, but the movements of which were hampered by the absence of suitable roads. Much of the country in which the military operations were conducted was either rough and broken or sandy. The wheels of the traction engines sank up to their axles, and were only extricated with difficulty. Numerous gullies and torrents also constituted a severe obstacle to progress. In view of this limited radius of action possible with traction engines of the ordinary type, the military department encouraged the evolution of a new design of tractor, to which rugged configuration of the ground or unstable earth would offer no impediment. The present apparatus is the outcome of this investigation, and it has proved remarkably successful, hills, banks, marshy, sandy and rough soil, ditches, and other obstacles being negotiated with equal facility and at fair speed.

The engine acquired by the War Office develops

the same features and perform the same remarkable achievements as the more powerfully equipped engine now in use at Aldershot for the haulage of heavy field guns, baggage, and general military stores.

The design of the engine is disclosed in the accompanying illustrations. An endless chain travels around driving wheels of substantial steel construction and provided with teeth on their periphery so as to form enlarged sprockets. The chain track is provided on its outer surface with a number of feet shod with rubber or wooden treads tied together with intermediate locking links, which render the bottom portion of the chain rigid, so as to form an arc with a radius of about 19 feet. The links which render the chain rigid when pressure is exerted from the outside make it flexible on the inside, so that it bends around the two sprocket wheels situated at either end of the arc. The rear one of these is the driver, which, the sprockets being engaged on the links, propels the engine by pulling at the chain, the latter being held to the ground by the weight, while the weight-


operates the brakes controlling the movement of the chains. For instance, if it is desired to turn to the right, the steering wheel is revolved in that direction as usual, and in so doing applies the brake to the right-hand side of the compensating gear, the radius of the turn varying with the pressure exerted by the brake. It will thus be seen that steering is perfectly simple and effective, and should the vehicle be caught in unusually difficult ground, it can easily extricate itself by a slewing or worming action with the steering gear.

Owing to the increased area of the surface brought to bear upon the ground, not only is the weight distributed over a larger area, but an increased adhesion surface is secured. Consequently, even when passing over the softest soil, it does not sink to any depth, while at the same time, even upon loose or slippery surfaces, a firm purchase can be obtained without the slightest tendency to slip or skid.

The experiments conducted with the vehicles have
(Concluded on page 351.)



The Tractor About to Descend a Sand Bank with a 5-Ton Trailer.



Detail Showing Design of Feet with Interlocking Links.



Climbing a Clay Bank.

A CURIOUS MODE OF PROPULSION.

RANGE AND POSITION FINDERS FOR COAST ARTILLERY FIRE CONTROL.


With the near approach to completion of the comprehensive system of artillery defense of the harbors of the United States recommended by the Endicott Board in 1886, the question of an efficient administrative and tactical control of the fire from the various gun and mortar batteries has become one of vital interest. The building of gun emplacements with their defensive parapets, magazines, etc.; the mounting of guns and mortars on modern carriages; the installation of electrical power plants for lighting, manipulating the guns, and for ammunition service—these are but the preliminary steps toward effective harbor defense. Position-finding service must be provided, powerful searchlights installed to sweep the water approaches at night, mine defenses laid down, elaborate means of communication between the various defensive units installed, and land defenses provided to protect the fixed armament from possible capture by landing parties operating from the rear.

In addition to this material equipment, it is necessary to maintain a force of trained artillerists, and because of the highly technical character of the duties of the artillery soldier, picked and carefully trained men alone are suitable for the work. The duties require special mechanical and electrical knowledge on the part of the men, and since the pay is relatively small compared with that obtained for similar work in civil life, it is not surprising that the War Department finds it difficult to maintain our coast artillery garrison at full strength.

Artillery fire control, as developed in our coast defenses, is the result of an elaborate series of experiments covering the past eighteen years and recorded in the reports of the Board of Ordnance and Fortifications during this period. The fundamental basis of every modern system of artillery fire control is the range-and-position-finding service. This is due to the fact that with the high initial velocities, flat trajectories, and long ranges of modern high-power guns, the use of an accurate instrument for quickly and automatically determining the exact position of the target at the moment of firing, has become an absolute necessity.

In the case of a moving target (the real war target is always in motion) the time element has first consideration, and this for the reason that the delay of a second or two in firing will often mean the loss of a shot. In one second of time, a moving warship may change its range five, ten, or even fifteen yards, according to its speed, with a corresponding change in its direction from the gun. The old-fashioned method of finding the range, by firing several trial shots, is now out of the question with any except machine guns and rapid-fire guns of the smaller calibers. The method is prohibitively costly, since the money value of the ammunition expended in finding a single range may equal the first cost of a range finder; while the latter is more accurate and far more durable than the gun itself and is always available when the battery is in service.

The distinction between range finders and position finders should be clearly understood. The former are more simple in construction and less expensive; but since they find ranges only, and must be used for direct laying at or very near the gun, or in conjunction with a more or less complicated system of calculations and replotting, they are seldom used as independent instruments. Position finders determine both the range and the direction of the target, the direction being usually expressed in degrees and hundreds of a degree of azimuth, or the horizontal angular distance of the object from the meridian. These instruments may be located at the battery, or at very considerable distances from the battery, and in either case they may be used equally well for direct or indirect



The Lewis Depression Position Finder.

laying of the gun. Two general classes of position finders are in use for coast defense, namely:

1. Depression position finders, in which the working base is vertical and comparatively short, being the height of the axis of the instrument above sea level at the moment of taking an observation.
2. Horizontal base position finders, in which the working base is the comparatively long distance between two instrumental stations in which only horizontal angles are measured.

With instruments of the second class, the base end stations must be in reliable electrical communication with each other and with a third, known as the replotting station. A much larger number of operators and more time are necessary than with depression instruments. On account of the number of stations and operators required; the difficulties experienced in promptly identifying the target; the length and complexities of the lines of communication, and their unreliability for work at night; horizontal base position finders are used, if at all, only in connection with the depression instrument, or where the height of the battery and surrounding fortifications is too low to afford proper elevation for mounting an instrument of

the depressive type. The theory of the depression position finder, as illustrated in the accompanying sketch of a mortar battery, is based upon the properties of the triangle, by which if two angles and the contained side be known, the length of the other two sides may be calculated. The position finder is mounted on an elevation of known height above sea level, and the angle at the instrument is found by directing the telescope upon the distant ship. The vertical height above sea level representing one side of the triangle is known, and the angle formed by the vertical and the horizontal line to the ship at sea level is ninety degrees. These data, modified by proper corrections, as given below, enable the other sides of the triangle to be computed, thus giving the exact range or distance of the ship. The most serious difficulties to be overcome in the production of a depression position finder sufficiently accurate for coast artillery use are the following:

1. The short vertical base of triangulation (the height above sea level of the horizontal axis of the telescope at the moment of observation) varies constantly with the rise and fall of the tide.


2. The ranges must be measured along the arc of a great circle, and the automatic triangulation work of the instrument must mechanically and automatically compensate for effects of the earth's curvature.

3. Atmospheric refraction, which continually varies in amount under the constantly changing conditions of the air with respect to heat, light, moisture, motion, etc., is often a serious disturbing factor, unless mechanical means are provided for quickly applying a proper correction.

4. Since the range is found by following the distant water line of the ship by means of a telescope, it is essential that this telescope be specially designed for the work.

The American government is indebted to Major I. N. Lewis of the Coast Artillery for the initiation and perfection of its depression position-finding service. The position finder known by his name, the first of its kind produced in this country, was developed by the inventor under the auspices of the Board of Ordnance and Fortifications between 1888 and 1896. It was officially adopted as the standard type for harbor defense in the latter year, and during the war with Spain a large number were purchased and installed. More recently other position finders, embodying numerous mechanical changes and improvements in the type, have been produced, and various models have been tested and adopted for use. The list now includes the Rafferty, the Warner & Swasey, the Whistler-Hearn, and the Bausch-Lomb-Seagmuller.

A few months ago the War Department conducted an exhaustive series of competitive trials of depression position finders at Fort Wadsworth, New York. The conditions of the tests were made to approximately simulate those of actual war. The official report of the Artillery Board giving the results of the tests is published in the January-February issue of the Journal of the United States Artillery. The observations, taken on fixed and moving targets, day and night,



The position finder is located in a masked position on some suitable elevation of known height above tide level. This height forms the base for calculating the triangle. The angle at the base is 90 degrees; and the angle at the instrument being observed, the distance to the ship is calculated. This is done automatically and instantly by the instrument.

BIRD'S EYE VIEW OF TYPICAL MORTAR BATTERY, WITH POSITION FINDER ON ADJOINING ELEVATION.

under all conditions of weather and water, for a period of five weeks cover in all more than 50,000 separate range readings. No such exhaustive trials have ever before been undertaken in any service, and the results, as shown in the report referred to, are exceedingly gratifying, the Lewis depression finder being adopted as the standard for the Coast Artillery Service on the grounds of accuracy, simplicity of construction, ease of adjustment and operation, superiority of telescope, stability and permanency of adjustment, and adaptability to change of height. The results of observation, according to this report, show an average error of all ranges on this instrument of 24.4 yards as against 35.1, 38.9, and 55.8 yards for the three other competing instruments. The accompanying photograph shows the new model instrument completely assembled ready for use. It consists of a 500-pound cast-iron pedestal supporting a brass 20-inch table and all moving parts. The masonry or concrete foundation pier, 3 feet in diameter, is sufficient to hold the instrument accurately in azimuth adjustment. The range scale reads from 1,500 to 12,000 yards, and it is properly corrected for effects of earth curvature and normal atmospheric refraction, while an easily-applied thumb screw connection is provided to compensate for effects of abnormal refraction.

Structure of Hailstones.

BY CLEVELAND ABBE.

There are three plausible hypotheses as to the origin of the snowy ice at the center of a hailstone.

(a) The hailstone may have begun with the formation of a ball of snow, and the clear ice may be a deposit of cold water, frozen a few seconds later by the cold of the surrounding atmosphere. In this case the air that is mixed with the snowy ice at the center would be compressed by the freezing of the surrounding clear ice, and would be liberated as a bubble when the hailstone is melted under water.

(b) The nucleus of the hailstone may have been at first a large drop of water, containing dissolved air, which is forced out by the process of freezing, precisely like the bubbles of air that are seen in cakes of artificial ice. Cold water can dissolve an appreciable percentage of its volume of air, all of which is extruded when water freezes; a bubble of highly compressed air might thus be formed at the center of the hailstone. If such a hailstone be melted in cold water slowly, all of this air will be redissolved, and no bubble will be seen to rise to the surface. If the stone be dissolved in hot water rapidly, or especially if the stone be crushed forcibly and quickly under water, the air may escape as a bubble without having had time to be redissolved.

(c) A hailstone formed of pure water that has had no opportunity to absorb or dissolve air can be reduced to a temperature far below freezing, but will eventually suddenly turn to ice, at which moment its temperature will rise to 32 deg. F., and it will assume a crystalline structure, so as to resemble snow. Such a hailstone has, therefore, a snowy nucleus without any inclosed air, and on being melted under water will, of course, show no bubble. In fact, the central space is occupied, not by air, but by the vapor of water only, and as the pressure is very small, we may liken this to a partial vacuum.

All these three forms of hailstones, and other forms as yet unthought of, are possible; and if we could invent methods of distinguishing between these three kinds of hailstones, we should have a better knowledge of what goes on in the upper air during the formation of hail.

Those who have proper conveniences will find that the study of hailstones under polarized light gives additional information as to their crystalline structure, but has not as yet told us much about the process of formation.

As ice is a poor conductor of heat, it is worth while to make some effort to determine the temperature of the interior of a large hailstone. The external surface may safely be assumed to have the temperature of evaporation or the average wet-bulb temperature prevailing in the lower thousand feet of air through which the hail has rapidly fallen, but the center must be at a temperature more nearly corresponding to that at which the nucleus was formed. There is, therefore, a state of strain that should be revealed by polarized light. The average temperature of the whole hailstone may be easily and directly determined by allowing hail to melt within a calorimeter, where the heat consumed can be determined, and then the temperature be computed.—Monthly Review.




In Denmark only the inter-provincial, the inter-communal and the international telephones are worked by the state, while the local telephones are worked by private limited companies, under concessions.

THE ANNULAR ECLIPSE OF THE SUN IN JUNE, 1908.

BY PROF. FREDERIC R. HONEY, TRINITY COLLEGE.

During the year 1908 there are three solar eclipses. The first occurred on January 3, and was described by the writer in an article in the SCIENTIFIC AMERICAN for December 28, 1907. This eclipse was total, but the path of totality was wholly confined to the Pacific Ocean; and as a partial eclipse, it was visible from a very limited land area.

The accompanying figures illustrate the second eclipse, which will occur on June 28. During the interval of nearly six months, the earth will reach a point in its orbit nearly opposite that of January 3. Fig. 1



PATH OF THE ANNULAR ECLIPSE.

is a plot of the moon's orbit for the month of June, and may be compared with that of January. The orbit is here turned half way around, and presents a view looked at from a direction opposite to that of January 3. At the time of the eclipse of January 3 the moon was very near the descending node N' . On June 28 she will be near the ascending node N . As already explained, this page may be assumed to represent the plane of the ecliptic or the plane of the earth's orbit, which for convenience may be regarded as horizontal. That part of the moon's orbit for the first half of the month (represented by a full line) may be regarded as above the plane of the ecliptic; and the other half as below that plane. The position of the moon is

shown for each day of the month from the 1st to the 28th at Greenwich noon; and the position of the moon's center is also repeated on the 14th, at the time of full moon nearly two hours later (14d. 1h. 55.2m.). The position of the moon is shown on the 28th at Greenwich noon, and also at the time of the central eclipse at noon (28d. 4h. 30.7m.). The direction in which the sun is seen is shown at intervals of seven days; on the 7th at noon; on the 14th at the time of full moon; on the 21st at noon; and on the 28th at the time of the eclipse. The positions of the sun and moon are here shown by their longitudes. As seen from the earth, they appear to move in the direction of the arrows A and a . If more than one eclipse occurs during an eclipse season, the interval between the eclipses is about two weeks, i.e., the time occupied by the moon in traversing about one-half of her orbit. On the 14th, the date of full moon, when an eclipse might be looked for, the moon will be too far above the plane of the ecliptic to come within the earth's shadow. (Fig. 2.)

Fig. 3 represents the earth projected on a plane which is parallel to its axis, and perpendicular to the plane of the ecliptic. The meridians of Greenwich and those which are 90 deg. E. and W. are shown. The equator, the tropics, the polar circles, the parallel of Greenwich, and of 31 deg. 27.3 min. N. are also shown. The latter in longitude 66 deg. 55.3 min. W. is the position of an observer marked O , to whom the central eclipse will be visible at noon. In the figure the position of Greenwich (marked G) and of the point O are situated on the invisible hemisphere. The arrow indicates the direction in which the observer is looking. Since the sun is nearly four hundred times the distance between the earth and the moon, a line drawn to its center from the point O in the drawing, is nearly parallel to the plane of the ecliptic; and its distance from that plane does not differ very much from the distance between the moon's center and the plane of the ecliptic. Attention is called to the difference in the position of the observer during this eclipse from that occupied by him in the eclipse of January 3. In January the observer was south of the equator, and looking toward the right from Fig. 3. In June the line of vision will be in the opposite direction from a point north of the equator. In both cases the observer's position is above the plane of the ecliptic.

The moon at the time of the eclipse will be very near apogee, and will therefore subtend an angle which is a little in excess of the minimum angle subtended this year. Owing to the earth's nearness to aphelion, the sun will subtend an angle which also differs very little from the minimum. But the apparent diameter of the moon will be less than that of the sun. The moon's disk at the time of the eclipse will subtend an angle of 29 min. 58 sec.; and that of the sun, an angle of 31 min. 31.4 sec. The result will be a narrow annular-area of the sun's disk around the dark body of the moon, as shown in Fig. 4.

Fig. 5 is a map of a portion of the earth's surface. The heavy line shows the path of the annular eclipse, in which is situated the point O corresponding to the position shown in Fig. 3. The dotted line incloses the land area from which a partial eclipse will be visible; the remaining area is limited to the Pacific Ocean.

The maximum width of the ring of light surrounding the moon in an annular eclipse, would evidently occur if the moon were at apogee and the earth at perihelion at the same time. The moon would subtend a minimum, and the sun a maximum angle. The maximum apparent diameter of the sun is 32 min. 35.7 sec.; and the minimum diameter of the moon this year is 29 min. 26.4 sec. If an annular eclipse occurred under these conditions, the width of the ring surrounding the moon's disk would be twice as great as that shown in Fig. 4. If Fig. 4 is held at a distance from the eye equal to one hundred and nine times the apparent diameter of the sun, here represented, it will subtend the same angle as that subtended by the sun at the time of the eclipse. A circle one inch in diameter placed at a distance of nine feet (= 108 inches) from the observer, subtends an angle which is equal to that subtended by the sun on April 26, when the apparent diameter is a little greater than that at the date of the eclipse.

The Börsen Courier, Berlin, learns that the German Admiralty is planning the erection of a new shipyard for repairs in connection with the projected drydocks at Brunsbüttel, on the Kiel Canal. The new yard will be employed only in case of need for the construction of small auxiliary vessels, its usefulness otherwise being restricted to dock traffic. Above all, the Admiralty wishes to have a body of trained workmen at the mouth of the canal, and to be sure of being able at any time to effect repairs at the exit of the canal at Holtenau.

THE "CATERPILLAR" TRACTOR.

(Concluded from page 348.)

been especially severe. In one trial a lorry loaded with three tons was hauled by five horses into a swamp, where the vehicle sank to the axles, and from which position the horses failed to extricate it. By means of the tractor, however, the load was dragged out with ease. Similarly, a two-wheeled vehicle laden with 1.5 tons was hauled into the swamp by four horses, and, after sinking into the loose soil, it resisted the efforts of the animals to withdraw it, the horses themselves sinking to a depth of two feet under the powerful effort they exerted. In this instance similarly the vehicle was quickly drawn out by the chain tractor. In order to demonstrate the efficiency of the chain track system itself over the ordinary type of wheels, two horses were harnessed to the chain tractor, which represented a total weight of 3.75 tons, and with the engine gear disconnected to enable the chain to travel freely, it was easily hauled through the bog, neither the horses nor load showing any tendency to become stalled, while the imprint of the feet of the chain was only about two inches. Subsequently, the engine of the tractor was reconnected, and with a trailing load of five tons attached, the whole was driven through the swamp, and various maneuvers executed in the softest part without imposing the slightest strain upon the engine, thereby testifying to the value of the chain track system.

The engine also displayed its unique possibilities in the negotiation of obstacles in its path. When an ordinary wheel meets such an obstruction, it has to lift itself together with the whole of the superimposed weight. In the case of this tractor, however, the encountering of an obstacle simply gives a slight inclination to the chain track, which being raised forms a bridge for the weight gradually to surmount.

Ditches, gullies, or fords can easily be crossed therewith. The chain tractor moves on until it reaches its critical point, the front overhanging the ditch, when the forward feet move gently on the farther side, and the rigid chain track forms a bridge over which the engine travels. Ditches which, owing to width and depth, would be sufficient to bury the front steering or rear driving wheels of an ordinary traction engine, can be easily and safely passed over.

In the case of crumbling dry clay or soft slippery soil, owing to the extended surface of the chain track upon which the weight-carrying wheels rest, the tractor does not sink into the ground; while owing to its extended and greater adhesion surface giving enhanced purchase, considerable loads can be transported over soft clay and deserts, which would be impassable by other means.

The engine has also remarkable hill-climbing capabilities, no matter what the nature of the soil may be. In the tests a bank of soft clay 20 feet in height, which when measured gave a grade of 1 in 2, was mounted speedily and without effort. Even snow and ice offer no impediment to its progress, since it has hauled maximum loads up to the full power of the engine up hills of 1 in 10, covered with ice one inch in thickness without slipping or breaking the ice, and without any additional assistance in the way of spikes, sand, or gravel to give improved adhesion, the tractor simply relying upon the grip provided by the surfaces of its numerous feet.

For haulage purposes the manufacturers have evolved a special chain track for application to trailing vehicles, the utilization of which facilitates the operations of the tractor itself and enables high speeds to be maintained under the most difficult circumstances. Arrangements are being made whereby the system can be applied to gun carriages for field operations, the weight of which precludes their being hauled through treacherous ground by the general means in vogue. Efforts are also being made to simplify the system of animal traction by applying the principle to the wagon, since trials have shown that horses can haul vehicles thus equipped with far less exertion than the ordinary wheeled types.

For the heaviest haulage work in mountainous districts, such as the transport of a 4.7 or 6-inch naval gun, where the grade is in excess of 50 per cent the system adopted is as follows: The tractor first ascends the slope, paying out meanwhile a steel cable to which the trailing vehicle is attached. When the limit of the cable is reached, the tractor is chocked and the trailer hauled up behind by means of the winding drum on the tractor. The trailer is then chocked in turn, and the tractor sent ahead once more, chocked, and the trailer hauled up a second step, this cycle of operations being continued until the summit of the grade is attained.

The Railway Age states that 5,730 miles of new track was laid in the United States in 1907, being 8 per cent less than in the previous year. The States in which largest mileage was laid were Louisiana, 422 miles; South Dakota, 385 miles; Florida, 341 miles; Texas, 314 miles; and Washington, 311 miles.

Correspondence.

Audubon and His Snake Story.

To the Editor of the SCIENTIFIC AMERICAN:

Referring to the communication from Mr. George W. Colles in your issue of May 2, in reference to a former letter from Mr. W. N. Hutt on an alleged rattlesnake incident published by Audubon, it seems to me that the snake in question was much more probably a specimen of *Coluber obsoletus* or *Coluber guttatus* than a black snake. The largest specimens of the latter would have quite a time in swallowing an adult gray squirrel, and it would be a good square meal for the larger colubers even. Personally, also, I should consider *Coluber obsoletus* (our common chicken snake) more arboreal than the black snake, particularly when the greater rarity of the former in this section is considered.

No doubt Mr. Colles is correct in his supposition that Audubon simply made a mistake in his species.

Raleigh, N. C.

H. H. BRIMLEY.

The Fourth Dimension Simply Explained.

To the Editor of the SCIENTIFIC AMERICAN:

Those readers who were interested in the above question, so clearly dealt with in your issue of March 21, may perhaps be also interested in certain principles considered in a pamphlet by the late C. C. Massey, which I hope will be published, and from which I have drawn. Consider a living being of some form existing in a universe of two dimensions. Then, for this being, there will be matter with the quality of resistance in two dimensions. For anything in this universe will occupy space of two dimensions, and so will exercise resistance against any other thing touching it.

Now consider a living being in our space of three dimensions. This being, as we know, lives in a universe of matter which has the necessary quality of resistance, and I think this being may be assumed to have a fuller and higher life in a fuller and higher universe than the universe of two dimensions.

But when this being of a universe of three-dimensional space considers a universe of two-dimensional space, it finds there is *no matter* and *no resistance* in the universe of two dimensions! In reality, the being of two-dimensional space does not exist in a universe of matter and resistance; it only experiences matter and resistance because it is limited to an existence in a universe of two-dimensional space!

In exactly the same way, a living being in a universe of four-dimensional space would know that our universe of three-dimensional space is not really one of matter and resistance, but one in which we *experience* matter and resistance, simply because we are limited to existence in three-dimensional space.

The above line of reasoning, if logical in the assumptions of the existence of other spaces than that known to ourselves, is still as pure reason as was Kant's in his "Critique"; and I do not think this reasoning is metaphysical.

But the reader will understand how, metaphysically, this reasoning leads us to a conclusion (with Kant) that our ideas of space (and time) are of space (and time) as *subjective* and not *objective*.

F. C. CONSTABLE, M.A., Trin.Coll.Cam.

Corlis Court, near Bristol.

Official Meteorological Summary, New York, N. Y., April, 1908.

Atmospheric pressure: Highest, 30.53; lowest, 29.28; mean, 29.93. Temperature: Highest, 79; date, 26th; lowest, 27; date, 5th; mean of warmest day, 68.5; date, 26th; coolest day, 31.5; date, 4th; mean of maximum for the month, 59; mean of minimum, 42.2; absolute mean, 50.6; normal, 48.6; excess compared with mean for this month for 38 years, +2.0. Warmest mean temperature of April, 53, in 1878. Coldest mean, 41, in 1874. Absolute maximum and minimum of this month for 38 years, 90 and 20. Average daily excess since January 1, +1.2. Precipitation: 1.82; greatest in 24 hours, 0.78; date, 30th; average of this month for 38 years, 3.33. Deficiency, -1.51. Accumulated deficiency since January 1, -1.74. Greatest April precipitation, 7.02, in 1874; least, 1.00, in 1881. Wind: Prevailing direction, N. W.; total movement, 11,279 miles; average hourly velocity, 15.7 miles; maximum velocity, 60 miles per hour. Weather: Clear days, 13; partly cloudy, 11; cloudy, 6; on which 0.01 inch, or more, of precipitation occurred, 10. Thunderstorms, 28th. Snow, trace, date 2d. Frost, light, 14th; heavy, 17th.

An Eighth Moon for Jupiter.

The staff of Greenwich Observatory announce that they have discovered an eighth satellite of Jupiter. During an examination of photographic plates of Jupiter, Mr. Melotte, one of the assistant astronomers, discovered a faint marking occupying slightly different positions on the different plates. The satellite has a retrograde motion.

A MAGAZINE FOR THE BLIND.

Undoubtedly the whitest printing plant in the world is that in which the Ziegler Magazine for the Blind is published. The reason is obvious. No type is used, and no ink of any description is to be found except, of course, in the editorial room where pen, pencil, scissors, and paste are as essential as in every well-ordered editorial sanctum. The printing plant claims to be the largest of its kind; for the monthly magazine it turns out contains fifty leaves or reading pages and has a circulation of about 8,000. The scope of the magazine is very broad. It gives a monthly review of current events, some standard literature, both prose and verse, short stories, a page of music, and a page of conundrums and jokes. The last two pages are especially popular. A keen sense of humor is to be found in all the blind, while the trained ear of a blind man appreciates good music and his nimble fingers readily learn to operate the strings or keys of a musical instrument. The magazine is endowed by Mrs. Matilda Ziegler, and except for a nominal subscription of 10 cents a year to bring it within the postal requirements, it is circulated without charge to any person in the United States or Canada who can read the point alphabet.

In the composing room of the plant there are two machines, one of which makes the plates for the New York point edition, while the other serves for the American Braille. Very unfortunately, both of these point alphabets are in general use in the country so that the magazine has to be published in two editions. The system of using raised Roman characters has been almost entirely displaced by the point systems because it is far easier to feel a combination of raised points than to sense the curves and angles of an embossed Roman letter. In the point systems each character is made up from one to six raised points variously arranged in two rows of three places. In the New York point, which is the easier system of the two, the rows are horizontal, while in the American Braille, a modification of the system developed by a blind Frenchman named Louis Braille, the rows are vertical.

The composing machines punch the point characters on a thin brass plate. The keyboard of the machine with its black and white keys looks like a small section of a piano keyboard. By depressing these keys in various combinations the proper punches are brought into active position and then, on working a treadle, the group of points is simultaneously indented in the brass plate to form a single character. When the representative of the SCIENTIFIC AMERICAN visited the composing room the operator was struggling with the accents, umlauts, and various pronunciation marks of a German-English dictionary for the blind. Imagine learning a foreign language by touch!

The back cover page of each number of the magazine is illustrated. Usually a map is shown and an illustration of some prominent structure, such as the Brooklyn Bridge, or the Statue of Liberty. In one of our engravings we illustrate one of the brass plates used for the back cover page. A translation of the point characters has been written on the plate for the benefit of our readers. These cover plates must all be made by hand. Music is written by using different combinations of points for notes of different time value. No lines are used, so that to the ordinary seeing person a page of music looks no different from an ordinary reading page of the magazine.


The page plates of the magazine are read by a blind proofreader, because the blind can more readily detect errors than could a seeing person. Errors are noted by underscoring. The points are then obliterated by hammering them flat, after which the correct letter or word is punched in.

The printing is done on a new type of press, especially built for the Ziegler Magazine, and it has a capacity of ten thousand pages per hour. It will turn out in a day as much work as 320 men and 140 machines could do by the old interpointing process now in use in England. A single month's edition of the Ziegler Magazine, if printed by the interpointing process, would keep two men and one machine busy for two years. The new press is of a rotary type, comprising a pair of rollers. The brass plates are secured to one of the rollers and bear against a rubber blanket on the other roller. The paper is fed between the rollers and is indented by the raised points on the plate. The paper is moistened before being run through the press and after receiving the impression it must be dried. If the printing were done on dry paper the point characters would be flattened down very quickly by the pressure of the fingers in reading. About 400,000 pages a month must be moistened, printed, and then spread out carefully to dry. Instead of the universal method of moistening paper by dipping each sheet separately, a sprinkling device is used with which the sheets may be thoroughly moistened in bulk, thus effecting a great saving in time and labor. At present the printing is done on only one side of the paper, but it is expected that both sides may soon be printed by using a fluted plate to protect one impression, while the

other is being made. This will double the capacity of the press and reduce the magazine to half its present bulk.

After the sheets are dried they are placed in piles on a long table, the successive piles being so arranged that the magazine may be assembled by picking up the pages one at a time from consecutive piles. The work is done by girls, as is also the binding of the magazine. It is the policy of the Ziegler Publishing Company to employ blind operatives as far as possible, and this part of the work is especially adapted for such hands. Not all the girls in this department are sightless, but it has been noticed that the blind attend more strictly to their work and make fewer mistakes than their seeing associates. In the foreground, at the center of the picture of the assembling table, is a girl who, in addition to being blind, is a deaf mute. The chance of working at the printing plant and of actually earning money is one of the greatest blessings of her life. It appears that in doing work which requires the exercise of but one of the senses the possession of other faculties is often a hindrance rather than a help, as they tend to divert one from the work in hand. Thus the blind deaf

mute, while apparently at a greater disadvantage than the other girls, does the best work in the department. A rather interesting psychological study may be noted in the photograph just referred to. At the right




A Copy of the Ziegler Magazine for the Blind.


of the deaf mute is a girl in possession of all her senses. By gazing at some fixed object, to hold her attention, she was able to keep fairly quiet while the plate was being exposed, and made a fairly good picture. But the blind girl, at the left, was constantly distracted by various sounds, and unconsciously moved her head to follow the sounds, while her fingers were not quiet an instant, but persisted, involuntarily, in feeling of the edges of the magazine on which they rested. Had the hands hung idle and some loud steady sound, such as an electric bell, been used to fix her hearing, she would probably have made as good a picture as the rest. But it is doubtful if she would have maintained the absolute rigid quiet of the blind mute. When the mute was posed and made to understand by signs that she was to keep perfectly still, her entire attention was bent on following out her instructions, and with neither sight nor hearing to distract her, she was able to stand through a long exposure apparently without moving a muscle.

One of our engravings shows a typewriter for the blind, also the slate used by the blind in writing letters to each other. The typewriter impresses point characters on the letter sheet. Several keys are depressed at a time to form each character, and in some cases two characters may be impressed at the same time. The slate which is used for handwriting consists of a corrugated metal plate set in a wooden frame. The paper is placed on the corrugated plate and over it is fitted a metal guide strip in which several rows of rectangular openings are cut. The slate pencil is in the shape of an awl, and is used to punch the paper to form the point characters. The


corners of the rectangular openings are used as guides for the awl. Two openings provide all the places necessary for the longest New York point character, six of the corners being used for the points, and the other two being skipped to provide the space between characters. When the three lines of the guide strip have been filled, the strip is moved down over a fresh surface of the paper. The rapidity with which this point writing is done and the facility with which the point alphabet is read are remarkable. That the marvelously sensitive touch and acute hearing of the blind is not intuitive, but acquired, is shown by the fact that a large proportion of this class were not congenitally sightless, but lost the use of their eyes after reaching maturity. The fact that they can develop their senses in this way is a great blessing to them. The man who suddenly loses his sight, after a short period of despondency, awakens to a realization of the value of his other senses and finds that he can put up a fair struggle in competition with his seeing associates. This very struggle is an inspiration and the blind are almost always happy, while many of them are justly proud and even a trifle conceited over their accomplishments.




Details of the Blind Man's Slate.




The New York Point Alphabet, also Numerals and Abbreviations.



One of the Cover Plates Showing How Maps and Illustrations Are Made for the Blind.



The Point Typewriter and the Slate Used by the Blind in Writing Letters. Preparing a Plate on the Composing Machine; at the Left is a Blind Proofreader.



The Magazine is Assembled by Picking up a Sheet from Each Pile.

The Roller Point Printing Press Which Prints 10,000 Pages per Hour.

HOW CAVE AIR IS USED TO REGULATE THE TEMPERATURE OF A HOUSE.

BY C. H. CLAUDY.

In Page County, Virginia, a mile from the town of Luray, stands a house that is perfect in its ventilation, and whose inmates breathe as pure air as any house dwellers in the world. The house is built on top of a hill, above the famous Caverns of Luray.

Connecting the caves with the surface is an artificial air shaft. Connecting this shaft with the house is a large passageway, and through this passageway, air from the caves is pumped into the house at the rate of eight thousand cubic feet a minute. "Limair," the name of this unique homestead, is the result of years of labor and preparation. Mr. T. C. Northcott, who built and owns the house, is a retired heating and ventilating engineer. It had long been his dream to se-


cure property on which could be built a house embodying some pet theories, one of which is to the effect that air filtered through limestone is pure and healthful and aseptic. Now, as to the practical advantages; in the first place, the entire cubic contents of the house is changed every four minutes during the day and night, so there is never any foul air. As the air is practically germless, no sickness can ever be contracted in the house from germ causes. As the ventilation is so perfect, windows need never be opened except for cleaning them, and the result is a house which is nearly dustless. As the air supply from the caverns fluctuates in temperature only two degrees in the year, from 54 to 56 deg. F., the temperature of the house is under absolute control. On the hottest day in summer the interior of the house is cool and comfortable at 70 deg. An open fire can be built every night in the year with comfort, and is built frequently even during

the summer. In the winter, the cave air, slightly warmed by passing over steam coils, heats the house, and the inside is always at 70 deg.—or whatever the particular temperature desired may be. Finally, the humidity is always normal in "Limair"; it is regulated to 70 per cent at a temperature of 70 deg. Less


is too dry; more, too damp. Tests have been made with culture mediums and plates to determine the amount of bacteria in the cave air, and all but very few of the results were entirely negative, the two or three positive results revealing so minute a quantity of germs as to be practically negligible. It is inter-

esting to compare the results made in different localities. For instance, on tests made in the caverns, in various parts, on twelve plates there were two colonies! In nine plates in the house, six colonies resulted, in one test.

In one plate in a nearby farm house, perfectly clean and considered a fine dwelling, 143 colonies resulted. On one plate made in a city back yard, 450 colonies resulted. On one plate made in a New York street car, 1,600 colonies resulted. Two plates in the finest operating rooms in Johns Hopkins University showed 65 and 58 colonies. In




Ventilation; In and Out of a Room.




A Glimpse of the Stalactite Formation.

Copyright 1906 by J. D. Strickler.



Copyright 1906 by J. D. Strickler.

The Caverns of Luray; One of the Largest Chambers.



The Air Shaft Conducting the Cave Air to the House.

HOW CAVE AIR IS USED TO REGULATE THE TEMPERATURE OF A HOUSE.

other words, the cavern air is practically-germless, aseptic, and pure.

How can the air from a dark, damp cavern be pure and sweet like the air which is sunlit and constantly moving? All the air in the cave is drawn from outdoors, and has been sun-cured! Moreover, it is not stagnant air at all; the difference in the temperature from inside and outside keeps up a constant circulation of air, which is drawn in and exhaled through thousands, probably, of small openings in rock and earth. The air is filtered through limestone.

Cave air—lime-cave air—is considered ideal for all troubles of the throat and lungs; consumptives have, before now, tried living in caves. But the lack of sunlight


and the dampness did more harm than the pure air did good. But in "Limair" one has the pure air and the sunlight and the lack of dampness all together.

Dampness is entirely relative. A certain amount of air, at a certain temperature, will always absorb the same amount of water. This amount is stated in percentages. But a per cent of moisture at one temperature will be different as the temperature is raised or lowered. Consequently, the humidity normal to the

both as condenser and to warm the air slightly by sunlight when desired; the lower chamber is used when it is desired to have the air reach the house just as it comes from the cave.

All the air goes to a large plenum chamber in the basement. From here it flows up through smaller shafts to the various rooms in the house. At the base of each of these smaller shafts is a steam coil, which is heated in winter time. A valve is so arranged to each ventilator shaft exit that the warm or cold air can be turned on at will. The arrangement of the entrance and exit ventilators is shown in one of the photographs. Above the top ventilator is a paper napkin, which is blown out at a right angle by the force of the air coming in. At the bottom ventilator, where the vitiated air goes out to be discharged out of doors, is a candle, the flame of which is deflected inward, showing the current of air. Although the air in the rooms changes completely in from four to six minutes, there is no draft to be felt at any time or in any place. The air flows, rather than blows.

The air is propelled into the house by a five horse-power electric motor, of which three horse-power is all that is required. It is a 42-inch fan of the disk or propeller type, with a gasoline engine in reserve in case of accident to the current. The fan runs from 400 to 600 revolutions a minute.



Plan and Elevation of the Basement, Air Duct, and Air Shaft.


caves, 87 at 54 deg., reduces itself to 70 when the temperature is raised to 70 deg. In other words, when the air is expanded by raising its temperature, the moisture lessens in quantity because the quantity (bulk) of air is increased.

Some details as to the practical arrangement of this house may be interesting. The location of the house was first determined from the outside. Then a survey was run in the cave through a passageway entirely off the regular "run" for visitors, and this survey was made entirely by candle light. The survey comprised a great many twists and turns and great differences in elevation. The same distance and direction were surveyed on the outside, and a 35-foot shaft, 5 feet in diameter, was sunk. When the shaft broke through into the cave, a plumb, dropped from above, was within three inches of the corresponding stake in the cave. The shaft drops 35 feet through the hill, and the top of the chamber into which it breaks is 25 feet from the floor, so the total depth is 60 feet. The shaft house where the fan is located is 100 feet from the house, and connected thereto with the air ducts shown in the illustration. This passage is double, the top being of tin and the bottom of wood. The metal duct is used

yet highly effective means employed to control the temperature and relative humidity of the air, and to distribute it and deliver it in the required volume to the various rooms in the house.

As the air comes from the shaft it may be thrown directly to the passage leading to the house, or by means of a bypass valve be sent through a condensing chamber before it reaches the fan. It is here that the relative humidity of the air is regulated. After leaving the fan the air goes through a duct 4 by 7 feet and 105 feet long, to the plenum chamber in the basement of the house. From the plenum chamber reach


six different passageways for air, all below the floor level. From all of these six locations or distributing centers rise iron pipes 12 inches in diameter, and one of these pipes goes to each room in the house. These pipes are placed within large metal-lined flues. The central pipe carries the fresh air, and the flue about it carries off the vitiated air—if air which has been in a room four minutes can properly be called vitiated. The large ventilating flues continue to the attic, where



First Floor Plan, Showing Air Shafts.

they all open into a "gathering chamber," from which the air which has been throughout the house passes to the outside air again.

At the base of each pipe through which air is supplied to the rooms of the house is a mixing valve, controlled by a cord passing through the pipe to the room the pipe supplies with air. This valve controls the temperature of the air reaching a room, by determining the proportions of normal cave temperature and steam-heated cave air which are to form the body of air delivered to the room. The section elevation shows this arrangement plainly; the cord is visible in the photograph showing the ventilators in a sleeping room. Of course, heat is used only in cool or cold weather, there being no necessity or desire to heat the air in summer.



The Caves from Which the Air is Drawn.

Copyright 1908 by J. D. Strickler.

HOW CAVE AIR IS USED TO REGULATE THE TEMPERATURE OF A HOUSE.

It is reported that a French scientist has devised an apparatus capable of indicating as low as the one-hundred-thousandth part of the carbon dioxide present in the air in a closed room. The indicator is based on the fact that carbon dioxide will liberate iodine from a chemical combination of that element, and the gas so released will effect a coloring of chloroform. The carbon dioxide contained in the air should never exceed one part in one thousand.

A NEW ELECTRIC RENOVATOR.

A novel adaptation of the vacuum cleaner principle to light domestic work is shown in the accompanying illustration.

A small but powerful electric motor is mounted on wheels, and fitted with a handle after the manner of an ordinary carpet sweeper. Power is obtained by connection with an electric light fixture. In carpet sweeping a rapidly-revolving brush loosens the dirt and dust, which is then drawn into the cleaner by a revolving double fan and dropped into a separator. Matches, paper, and heavier fragments fall into a separate drawer.

For other household cleaning special attachments are provided, fitted to flexible tubes. One of these is used for cleaning cushions, mattresses, and upholstery in general. This may be done either by suction or by forcing air through the material to be cleaned; in practice the dust is usually first drawn into the machine, and a current of clear air afterward driven through the cleaned object. A second attachment is adapted for cleaning corners, crevices, and other awkward places, while a third is used for cleaning walls, curtains, moldings, and similar surfaces.

The work of the cleaner is very thorough, the suction of the air tending to reach the under-surface dust, which is often passed over by mechanical brush sweepers and similar appliances.

A FRENCH UNIVERSAL SYSTEM OF MACHINE MOLDING.

BY FRANK C. PERKINS.

It has generally been considered among modern foundry owners that machine molding is only practicable when a great number of castings of the same pattern are required, and such castings are flat, with a lot of taper, and therefore easily molded. Most of the molding machines in use are simply presses actuated by hand, or by compressed air or hydraulic power, but little attention is paid to making the pattern plates, when this is the main point to be considered in machine molding. It is on this account that machine molding is so little used.

With the ordinary means employed, the making of pattern plates is very expensive even for easy castings, and in order to obtain the required accuracy, first-class fitters are required. For motor-car castings, which are more or less intricate, it is necessary to make a special and very costly machine for each casting. Very often special flasks are needed, which are accurately machined, adding still further to the cost, and in most cases the above reasons have caused founders to conclude that machine molding is not practical.


The new French universal system of machine molding is said to have largely done away with these drawbacks and difficulties, and it may be of interest to consider it in some of its details, as the new process is said to be really "universal," and conforms to all possible cases, from the easiest castings to the most intricate ones; and this is accomplished with an enormous saving, not only on hand molding, but on the accepted and general machine molding now in use. The molder is himself able to make the pattern plates, as the whole system has been designed especially for making

the pattern plates and stripping plates in the foundry without depending upon the machine shop. Even the most intricate pattern plates are made more cheaply and quickly than by any other system, and this enables the founder to make them to advantage for as few as fifty castings.

In one of the accompanying illustrations there is a very good example of the reversible pattern plate, indicating clearly the




number of patterns used on the plate and the results obtained.

A great part of the core, cylindrical, or extremely intricate work can be made on the machines by different combinations, and it is absolutely true in position and accurate in size. Heavy cores in the drag can be molded direct on the machine. No accurately machined boxes are required, as the machines can mold either with non-machined flasks when dry molds

**A NOVEL ELECTRIC RENOVATOR.**

are needed, or with only a few boxes when green sand is used. When a casting is not too large, and of such a shape to allow it, reversible pattern plates are used, so that when two boxes are rammed off, a complete mold is the result, and the number of castings obtained is doubled.

A special appliance has been designed for smaller pieces, which is really a small reversible pattern plate,

**A Reversible Pattern Plate.****Machine Arranged for Molding Top and Bottom Molds at the Same Time.****Hydraulic Molding Machine With "Cliche" Table.****Molding Machine Arranged for Ramming Flasks With Bars.****A FRENCH UNIVERSAL SYSTEM OF MACHINE MOLDING.**

and is called a "cliche" appliance. It is made in a very short time, and is entirely of metal. One of the accompanying illustrations shows a small hydraulic molding machine arranged with extension brackets to take the cliche table. The piston for the pattern drawing mechanism is worked by a pedal in this machine, while the others have a cylinder after the style of the ramming cylinder, and work simultaneously. It will be noticed that the various sections are in place in this cliche table. A cliche is made by an average molder in from one-half hour to two hours, and is made from an ordinary pattern such as is used every day in the foundry, two castings for each pattern.

A machine for molding the top and bottom of the molds at the same time, so that they can be placed one on top of the other, is also illustrated herewith, together with a number of the castings made on this machine. It will be seen that for this process there are two pattern plates, one on the table of the machine in the usual way, and the other bolted to the ramming plate. This same machine is also arranged for ramming flasks with bars, as very often when a shallow mold is required with a large surface, it is impossible to hold the sand together over the large area without bars. These molding machines are capable of making from fifty to eighty half molds per hour, according to the skill of the operator and the nature of the work. The machines of various sizes are designed to take flasks from 10 inches by 10 inches to 3 feet by 5 feet and even more.


With their limits the machines will take any size and depth of flasks, any style of castings, and any style of pattern plates. Vibrators can be used if required, and intricate pattern plates with stripping plates can be mounted in a moment. Hydraulic power is used instead of compressed air, and after careful consideration of the advantages and disadvantages of hydraulic power and compressed air, the former agent with a pressure of 750 pounds per square inch was selected on account of the perfect and steady movements obtained either in drawing the pattern or in ramming. It is stated that one horsepower is sufficient to drive from four to six molding machines, which is about twenty times less than that required for compressed-air machines, while the first cost and maintenance of the hydraulic plant is said to be trifling as compared to the first cost and maintenance of a compressed-air plant of the same working capacity.

Steel Belting.

Consul Frank S. Hannah, of Magdeburg, writes that in a recent issue of a German technical paper, the use of steel bands to take the place of leather belting for the transmission of power is stated to have proved practicable after repeated tests by a firm in Charlottenburg, its advantages being given as follows:


The points of superiority claimed for this new method for the transmission of power are the following: On account of its solidity a much narrower band can be used, one-sixth of the width of the usual leather band being sufficient; as a result of this the steel band is not so heavy as the usual band, and, as it can be very tightly adjusted, the distance between the engine and the machine is not a matter of importance, as is

the case with the leather belting; where the transmission of power is dependent upon the weight of the hanging belt; by a unique contact, the slipping is much reduced, experiments showing not over one-tenth of 1 per cent. The entire loss of power is very small, about 1 per cent. By the lightness of weight of the steel belting, the influence of the centrifugal force is not so great, allowing increased velocity.



RAIL LOCK AND TIE PLATE.

A combined lock and tie plate for railway rails has recently been invented, which is adapted to effectually prevent the rails from spreading or having any lateral movement. The device may be used on any form of sleeper, and is of simple and durable construction. Our




RAIL LOCK AND TIE PLATE.

illustration shows a section of a track on which this lock and tie plate is used. Secured to the tie *A* is a plate *B*, which extends practically the entire length of the tie under the rails *C*. The plate is formed with a shoulder at each end, which bears against the outer base flange of each of the opposite rails. The rail lock comprises two sections, indicated respectively at *D* and *E*. The brace section *D* is provided with a lug, which enters a recess in the tie plate *B*. This serves to hold the brace section in fixed relation to the tie plate and rail *C*. The brace section is formed with an upward extension, which terminates in a wide head adapted to fit against the head of the rail. The guard section *E* of the rail lock is fitted against the inner edge of the base flange of the rail. This section is also held in position by means of lugs, which enter recesses in the tie plate *B*. Both sections of the lock are secured by means of spikes driven through the tie plate into the tie. Probably in practice it will not be necessary to use more than one lock to each rail, and where the lock is not used, the rail may be secured to the tie plate in the usual manner by means of spikes driven into the sleeper through the tie plate. A patent on this rail lock and tie plate has recently been secured by Mr. William N. Reynolds, of Litchfield, Conn.

FOLDING WASHING MACHINE FOR STATIONARY TUBS.

Pictured in the accompanying drawing is a folding washing machine made for stationary tubs. It is of light weight and can conveniently be applied to any tub. The wash is cleansed by alternate pressure and suction and there is no rubbing. Hence, there is no wear or tear of even the finest fabrics. The machine will operate with equal facility on heavy blankets. It comprises two leaves, each of which is composed of transversely-arranged slats. The leaves are hinged together at one end and one of the leaves is secured to the bottom of the tub, while the other is arranged to swing toward and from the stationary leaf so that the water and suds in the tub will alternately be drawn in and forced through the clothes placed between the leaves. It will be observed that the slats are beveled at one side. The purpose of this is to catch the clothes to prevent them from slipping out when the upper leaf is forced down upon them. The lower leaf is provided with a pair of vertical side




FOLDING WASHING MACHINE FOR STATIONARY TUBS.

bars which are hinged thereto and which are secured to the sides of the tub by means of U-shaped clamps. No special adjustment is required to accommodate the washing machine to various quantities of clothes. If a large number of pieces are put under the swinging leaf, the latter is operated at a greater angle with the lower leaf. At one side the two leaves are cut away to provide access to the drain, or discharge pipe of the tub, so that the plug may be removed without lifting out the machine, and the wash water may flow out without being impeded by the clothing in the machine. Whenever desired the clamps may be loosened and the machine lifted out of the tubs and completely folded. In its folded position the machine takes up little room and may be conveniently carried about. The inventor of this machine is Mrs. J. W. O'Connor, 106 East 81st Street, New York.

HOSE NOZZLE WITH MOVABLE SPRAY CAP.

The accompanying engraving illustrates an improved hose nozzle, provided with a movable

spray cap and an independent means for regulating the volume of water which passes through the nozzle. The spray cap is hinged to the outer end of the nozzle, and may instantly be brought into active position whenever desired, adapting the nozzle for spraying plants, shrubbery, and the like. The nozzle consists of a tapered tube *A*, which may be connected to any suitable cut-off cock on the hose. The tapering tube is oval in cross section. The spray cap is indicated at *B*, and is hinged to the outer end of the tube *A* in such manner that it will drop over the end of the tube. The spray cap is formed with a sinuous opening *C*, through which the water passes to become a spray. At one side the cap is provided with an arm *D*, at the free end of which a locking member *E* is secured in such manner that it may be slipped under the tubular body *A* to hold the spray cap open, and over the tube *A* to hold the cap closed.



HOSE NOZZLE WITH MOVABLE SPRAY CAP.

Within the tubular body *A* there is a spring valve *F*, comprising a plate shaped to conform with the inner wall of the nozzle and cut away toward the front end, where it is substantially semi-circular in form. A thumb screw *G* in the top of the tubular body bears against the spring valve *F*, and provides a means for depressing the valve, thus partially closing the nozzle and controlling the flow of water. The inventor of this hose nozzle is Mr. Sugaji Suzuki, of 2204 Quincy Avenue, Ogden, Utah.


Prof. Myers's New Airship.

Prof. Carl E. Myers, of the balloon farm, Frankfort, N. Y., announces that he is constructing for western use the largest airship yet built by himself or any one else in this country. It is of his well-known spindle shape, and has a circumference and length of 84 feet and a buoyancy of 1,700 pounds. This will be finished in two weeks, when he will begin construction of a still larger airship on the lines of the government specification, but twice the dimensions of the late accepted bid. Within the past five days he has wholly constructed two captive hydrogen gas balloons and nets for the United States government. This speed is only made possible by the use of ready machine-varnished hydrogen-proof fabrics originated by him and in use exclusively during thirty years, and from which he has already built 150 hydrogen balloons for the War and Weather Departments of the United States. Ordinarily, by the usual systems it requires from thirty to sixty days to completely varnish a hydrogen-tight balloon.

IMPROVED SWITCHBOARD PLUG.

An element of considerable expense in all telephone exchanges is the maintenance and repair of the switching cords. The cords give way just below the point where they are attached to the plug, because when inserted in the switchboard they are bent at right angles and twisted at this point. Efforts have been made to eliminate this trouble by reinforcing the cords with braids, but the cord trouble seems to remain almost as great a disadvantage as ever. A ball and socket plug and cord connection has recently been invented, with the purpose of overcoming this defect. This

plug is shown in the accompanying engraving. The cord is fitted into a head *A*. The latter carries a ball *B*, which engages a socket *C* secured to the plug proper. The socket *C* is made in two pieces, which are bolted together, and over them is fitted a sleeve *D*. The two terminals of the cord *E* and *G* are secured to posts in the head *A*. The terminal *E* connects by a flexible wire to a bar *F* and button *H*, which is suitably insulated from the plug, while the terminal *G* is electrically connected through the metal casing of the plug to the sleeve *K*. The plug may be used in the usual



IMPROVED SWITCH CORD PLUG.


manner on any switchboard, and when inserted in the switchboard the head *A*, owing to its ball-and-socket connection with the plug, is free to move in any direction, as indicated by dotted lines in one of the views. The ball-and-socket joint also prevents twisting the cord when the plug is moved laterally to different parts of the switchboard. A patent on this switchboard plug has been granted to Messrs. E. L. Smith and G. F. Childress, of Wills Point, Texas.

FOLDING STEP LADDER.

Painters and paper hangers often find it necessary to use a step ladder on a stairway or in some other inconvenient place, where the tread part of the ladder must be set on a different level from the legs.

In such conditions a folding ladder, like the one here illustrated, would be found indispensable. This ladder is not intended for the use of decorators alone, but is adapted for all the requirements of the household. Both the tread portion and the supporting legs are made in sections which may be separately folded, as desired, to make either side longer or shorter than the other. When both sides are fully extended, the ladder has the proportions of an ordinary step ladder, and when both sides are folded the ladder is reduced to one-third its original length, so that it may be stowed away in a small space.

The tread portion of the ladder is formed with a separate section for each step. Each section slides within the one below, and may be secured either in the extended or folded position by a double pin at each side, as shown in the detail view, Fig. 2. This method of coupling the sections makes a very strong and firm joint. A small wire hook is suspended above each double pin and serves as a retainer to prevent the pin from being entirely withdrawn. This does away with the danger of losing the pins and keeps them always in position for instant use. The leg portion of the ladder is composed of fewer sections, but by providing intermediate holes on each section for the locking pins, it is capable of the same adjustment as the tread portion of the ladder. The usual folding brace is provided to hold the leg and tread portion apart and the ladder is furnished with the ordinary extension board to hold a pail or the like. The inventor of this folding ladder is Mr. Albert Dahl, of 302 West 144th Street, New York City.



FOLDING STEP LADDER.

RECENTLY PATENTED INVENTIONS.

Electrical Devices.

RHEOSTAT.—J. W. MERTZ, Mount Clemens, Mich. More particularly the invention relates to a type of rheostat of special service in connection with arc lamps for the production of moving pictures. The more particular purpose is to give the operator a more extensive control over the current so that he can closely graduate the resistance and govern it completely within wide limits.

CURRENT-DISTRIBUTING DEVICE FOR IGNITING EXPLOSIVE-ENGINES.—H. DE LA VALETTE, 111 Boulevard de Menilmontant, Paris, France. The object of this invention is to avoid the serious drawback which often happens in apparatus where the sparks move off and to a distance between the different metal pieces and thus give rise to untimely ignition in the cylinders, and the invention consists in a particular fitting of the insulating parts separating the several metal pieces used for the in-coming and out-going currents.

Of Interest to Farmers.

CORN-HUSKER.—S. H. MINNIS, Carrollton, Mo. The husker is designed to be worn upon the hand during the operation of husking. The inventor's object is to produce a device which can be readily and quickly attached to or detached from the hand, which is positive in its action and protects the upper part of the hand and thumb from the action of the corn-husk.

COTTON-PICKER.—I. A. MURCHISON, Manchester, N. C. The improvement relates to cotton pickers, the more particular purpose being the production of a small picker suitable to be carried in one hand and in which the picking mechanism and movable parts for operating the same are of comparatively simple construction.

BAND-CUTTER AND FEEDER.—A. BÖTTCHER, Benndorf, near Delitzsch, Germany. The invention comprises two endless traveling feed-carriers in the cross direction only of the threshing, a reciprocating pusher movable in the longitudinal direction of the threshing and adapted to push the grain off the one feed-carrier to a chute leading to the threshing drum, an adjustable band-cutting disk and a reversible box for supporting the other feed-carrier and the band-cutting disk.

Of General Interest.

AERIAL APPARATUS.—M. B. SELLERS, Baltimore, Md. In this kite form of apparatus the wings operate as an aeroplane and the object of the invention is to produce a construction of the greatest lifting power for a unit area and one having little wind resistance, and which can be easily adjusted to properly fly in the practical operation of the improvement.

EYE-SHIELD.—G. E. HENRY, Philadelphia, Pa. One purpose of the invention is to provide a light shield adapted to be worn upon the nose in the same manner as an eyeglass, or which can be quickly and conveniently adjusted to the bow section of an eyeglass or the bridge of spectacles in such manner that the attachment can be readily removed when desired.

BELT-FASTENER.—P. A. HUDSON, New York, N. Y. This belt is simple and durable in construction and arranged to securely fasten the ends together, without danger of tearing the belt material and without producing undesirable thicknesses or projections on either face of the belt, thus allowing the passing of the belt with either face over the pulleys.

PIPE OR TUBE CLEANER.—E. A. JABLONSKY, New York, N. Y. In this patent the object of the inventor is to provide a pipe or tube cleaner, more especially designed for use in the water pipes or tubes of boilers to remove adhering scale and other extraneous matter in a very effective manner and in a comparatively short time.

LOADING DEVICE.—W. F. KLEWITTER, Mosinee, Wis. Mr. Klewitter's invention pertains to a loading device and has for its principal object the provision of a device in which the strain is evenly distributed through the frame. Still another object is to provide adjustable side braces which may be disposed from the top of the frame to the ground.

MITER-BOX.—J. MCCUNE, Santa Cruz, Cal. In this instance the invention refers to miter boxes, and is particularly designed to provide means adapted to enable a saw to be held in a vertically inclined plane while cutting diagonally across an object, so as to cut angles in two directions at the same time.

HOLDER FOR NURSING-BOTTLES.—M. L. SURPRENANT, Indian Lake, N. Y. The inventor has in view a holder for supporting and holding in convenient accessible positions while in use, an ordinary or other form of nursing-bottle, whereby the child may be in easy reach of the bottle and be relieved, to an extent, of its weight, in addition to it being impossible for the bottle to be dropped to the floor and broken.

ADVERTISING DEVICE.—I. O. THORLEY, Philadelphia, Pa. This device is particularly adapted for use in cars for indicating stations or streets, the object being to provide a device that will be simple in construction and in which are two sets of reversible or transferable slides bearing advertising matter, such for instance, as the names of streets or stations.

Hardware.

FUNNEL.—J. P. MURTHA, Little Rock, Ark. The funnel is provided with a large bowl or body and interchangeable spouts of different sizes, to permit convenient filling of large or small bottles, and to allow filling successively of a number of bottles with one charge and without danger of spilling or wasting liquid retained in the bowl during the transfer of the funnel from one bottle to another.

SAW.—J. DOWLING, Olympia, Wash. This saw is such as used by carpenters, and is provided with means for attaching the handle to the butt thereof. The handle is provided with spirit levels, the arrangement being such that the levels are protected from injury. The levels are accurately aligned with respect to the rear edge of the saw blade which constitutes a straight edge.

Heating and Lighting.

MINER'S LAMP.—R. L. GRAVES, Sumpter, Ore. The invention relates to lamps in which paraffin, wax, or other solid fuel is used and is designed as an improvement on the lamp shown and described in an application formerly filed by Mr. Graves, the object being to render the lamp more convenient in handling, in that the wick tube can be readily removed and rewick with little or no trouble.

DRYING-FLOOR.—H. O. ROBINSON, Brookline, and C. STEADMAN, Salem, Mass. One of the purposes here is to provide a heating floor for drying green bricks and like materials, the floor being so constructed that various heating agents can be utilized, namely, exhaust steam, chimney gases, or waste heat from kilns, and to so construct the floor that it is impervious, and so that the heat will be consistent throughout the entire floor area.

INCANDESCENT GAS-LAMP.—H. SÜSSMANN, 144 Alte-Jacobstrasse, Berlin, Germany. Mainly this invention relates to the particular formation of a closed air container. This container should be constructed in such a manner as to surround the chimney or chimneys through which the combustion gases are conducted wholly or partially through the incandescent bodies, and which at the same time receives the mixing device and mixing passage. The arrangement may also be such that only the burner head or heads and the incandescent bodies extend through the bottom of the air reservoir into the combustion chamber of the lamp.

Household Utilities.

EGG-OPENER.—D. P. STEVENS, Rio, Wis. The purpose of the invention is to provide a simple and economic opener so constructed that it can be expeditiously and conveniently operated, and the egg broken and its contents discharged in a cleanly manner, free from particles of shell. The empty shells are automatically discharged.

Machines and Mechanical Devices.

SYLLABIC KEYBOARD FOR TYPE-WRITERS AND TYPE-SETTING MACHINES.—H. G. MCCOOL, Carmichaels, Pa. In the present patent the object is to obtain great speed and thus enable more work to be done in a shorter time than has been heretofore possible on typewriters and analogous machines. To accomplish this, both letters and syllables are used in a new arrangement or association.

BALANCED PUMP.—A. P. SMITH, Sumpter, Ore. The object of the inventor is to provide a pump, arranged to require comparatively little power for operating the pump by employing two simple-acting pumps, of which one delivers through the other, and the descending plunger of one pump aids the lifting of the water in the other.

MEANS FOR USING FROM A DISTANCE THE VARIATIONS IN TEMPERATURE.—J. B. FOURNIER, 62 quai des Orfèvres, Paris, France. In this case a manometer comprises a curved manometric tube and having its other end closed, both tubes containing liquid and the above named tube containing in addition a solid material distributed substantially throughout its entire length so as to restrict the space left for the liquid held within the said tube.

Prime Movers and Their Accessories.

CARBURETER.—W. L. WAYRYNEN, Dolph, S. D. More particularly the invention refers to means whereby a mixture of uniform composition may be formed irrespective of the quantity of gasoline or other fuel in the supply tank and irrespective of the speed of the engine. The presence of impurities in the liquid fuel does not interfere with the operation of the device, as no needle valve or fine passage is employed.

MEANS FOR PRODUCING MOTIVE POWER.—J. L. TATE, Jersey City, N. J. An object of this invention is to utilize the products of combustion of a liquid or gaseous fuel for operating an engine and to add to the products by the injecting action thereof, a second fluid of a low temperature, whereby a motive fluid is formed of a temperature sufficiently low to prevent injury to the engine, but, at the same time, of high pressure and velocity.

INTERNAL-COMBUSTION ENGINE.—C. J.

MUNDHENE, Freeport, Ill. The invention relates more particularly to improvements in the cylinder and cylinder head construction whereby the cylinder may be more efficiently and uniformly cooled, the means for distributing the cooling agent being so disposed as to aid in the support of the cylinder and strengthen the same.

COMBINATION GAS AND STEAM ENGINE.—M. S. FLAIG, La Crosse, Wis. The intention in this improvement is to provide a new combination gas and steam engine, in which a mixture of steam and gas under pressure is produced in a very economical manner, and the said mixture is utilized to drive the engine to the fullest advantage.

Pertaining to Recreation.


CALCULATING DEVICE.—T. T. CROUCH, Chicago, Ill. This scientific device is for use in handicapping horses at different race tracks, different weights, under different conditions and ridden by the same or different jockeys; and also for arriving at track conditions. The invention consists in the novel construction and arrangement of the mechanical parts including the shiftable dials and index hands moving over the dials and adjusting the same, whereby the results are carried out in a simple, rapid, and correct manner.

REEL-CRANK.—J. J. NEWLANDS, New York, N. Y. The invention refers to reel-cranks, such as used by fishermen, the more particular object being to provide improvements in the construction whereby the practical length of the hand crank of the reel is changed at will, and also improvements in the means whereby the crank may be locked in a predetermined extended position.

POKER-TABLE.—I. MASON, New York, N. Y. A purpose here is to provide a table top for the game of poker, which poker top is adapted to constitute an auxiliary top for the table, particularly for a table having a rectangular top member, and also to so construct the auxiliary top that it can be quickly and conveniently placed and held in position on a table and as easily removed, without in any manner marring the table.

FISHING-FLOAT.—M. E. LOEHR, Claypool, Ind. The aim of this improvement is to produce a float of simple construction adapted to rest upon the water, and which is provided with a line carrying a hook. The construction is such that when the hook is taken by a fish, the device operates to strike so that the fish becomes caught. The device indicates whether it has been snapped or not; that is, whether or not a fish is on the line.

NOTE.—Copies of any of these patents will be furnished by Munn & Co. for ten cents each. Please state the name of the patentee, title of the invention, and date of this paper.



HINTS TO CORRESPONDENTS.

Names and Address must accompany all letters or no attention will be paid thereto. This is for our information and not for publication. References to former articles or answers should give date of paper and page or number of question. Inquiries not answered in reasonable time should be repeated; correspondents will bear in mind that some answers require not a little research, and, though we endeavor to reply to all either by letter or in this department, each must take his turn.

Buyers wishing to purchase any article not advertised in our columns will be furnished with addresses of houses manufacturing or carrying the same.

Special Written Information on matters of personal rather than general interest cannot be expected without remuneration.

Scientific American Supplements referred to may be had at the office. Price 10 cents each.

Books referred to promptly supplied on receipt of price.

Minerals sent for examination should be distinctly marked or labeled.

(10759) V. E. M. asks: 1. What is the method of making a small battery such as is used in a small vest-pocket electric light? The battery can be bought for about 25 cents. A. The battery for lighting miniature lamps usually contains three dry cells. We published in our SUPPLEMENT, Nos. 1383 and 1387, price 10 cents each, a full description with illustrations of the manner of making such cells, with all the materials used and all necessary instructions. 2. What is the method of making a Fuller battery? A. The Fuller cell (see SUPPLEMENT, No. 159, price 10 cents mailed) is a bichromate cell in which there is a continuous amalgamation of the zinc. The zinc is in the bottom of the porous cup, and has a quantity of mercury, an ounce to a cell will answer, poured around it, which maintains the amalgamation of the zinc through the life of the cell. A brass or copper rod covered with gutta percha is fastened to the zinc, and extends above the cell as a terminal to which the circuit is connected. The carbon plate is placed in the glass jar and surrounded with a bichromate solution. Water is poured into the porous cup upon the zinc. The acid diffuses through the porous cup fast enough to act upon the zinc and produce the current. The cell evidently will not furnish a strong current. A good formula for the bichromate solution may be given: Take 21 ounces of sodium bichromate and 3 quarts of water. When

the solution of the salt is complete, add slowly and with constant stirring, 1 pint of strong sulphuric acid. The solution is ready for use when it has cooled.

(10760) W. D. O. says: I would like to know the composition of the preparation with which the particles of carbon, in the carbon pencils for electric arc lamps, are held together; that is, the cementing substance. A. Arc light carbons, carbon plates for battery cells, and similar articles are made from coke. The higher grades are made from coke derived from the residue of petroleum stills. The crude material is dried, ground fine, and sorted into different sizes. The binding material may be a coal-tar product, or some other substance containing carbon, and which will be reduced to carbon by the heat of the furnace. These are thoroughly mixed, pressed into forms by hydraulic pressure, and afterward baked in a furnace. For a full description see SUPPLEMENT, No. 1237, price ten cents.

(10761) R. S. C. asks: Why, if known, does the skin of a chameleon change in color, in moving from an object of one color to one of another color; that is, why does its skin always assume the same color as the object it may be resting upon? A. One answer to the question, "Why does the chameleon change the color of its skin?" is that the chameleon has a better chance of life by reason of this protective resemblance to its surroundings. Those chameleons which had the largest range of change of color in the past have survived, and the capacity of change has been evolved in their descendants to a higher degree, so that all chameleons now living readily change the color of their skins to that of the bark of the tree upon which they at the time may be. They are thus protected from their enemies. There are many such adaptations of creatures to their habitat or environment. The polar bear, living among Arctic snows, is white. The tiger in the jungles is striped, as if painted to resemble rushes, reeds, or other stiff and straight plants. Many fish have backs of the hue of the sand or sea bottom upon which they lie. Nature has thus attended to the needs of her weaker children. Another answer might be that the effect of the color of the surroundings is to produce a change in the pigment in the cells of the skin, so that the color becomes like that of the surface upon which the animal is resting. In the chameleon this is comparatively rapid.

(10762) W. A. T. asks: Would you kindly give me directions for a spark coil for 3-horse-power gasoline engine? Size of core, feet, and number of wire for primary; also feet and number of wire for secondary. I have 550 feet of No. 18 cotton-covered wire that I would like to work into the coil. Want coil to give about 1/4-inch spark. A. SUPPLEMENT, No. 1281, gives full information concerning a coil for gas engine ignition, if one has general knowledge of the work of construction. Lacking this, it would be best to get Norrie's "Induction Coils," price \$1, which gives detailed instruction in this work, together with tables of data for all the parts of coils of all sizes up to a 12-inch spark. Do not use so coarse a wire as No. 18 in a secondary coil, and use a coarser wire in the primary. Two layers of No. 14 will be right for primary, layer 6 inches long. Three-fourths pound of No. 36 silk-covered will be right for secondary to give a half-inch spark. Core should be 3/4 to 1 inch in diameter and 7 inches long. 2. If a person sparked his engine with a magneto, would he need a coil also? A. A magneto can be made which will render a coil unnecessary, but a battery and coil are necessary till the machine has speed enough to enable the magneto to generate.

(10763) C. S. J. asks: I wish to learn the cause of trichinae in pork. A. The trichina spiralis is a worm, a parasite of the hog. It is often found in great numbers in the flesh of these animals, in the encysted condition but still alive. If such meat is eaten without cooking thoroughly, the parasite is taken into the body and is rapidly propagated. The worm came originally from the rat. As hogs eat rats, they pass into the hog and thence into man. The only preventive is thorough cooking. This kills the trichinae. No rare or underdone pork should ever be eaten. The risk is too great. The cost of immunity is so little that anyone may be safe. Cook all pork thoroughly. 2. The cause of ptomaine poisoning by eating pork. What causes the presence of the poison, how the poison can be prevented, and whether or not there is any way of detecting the presence of poison before using the meat? A. Ptomaines are formed by decomposition. If only fresh food is used, one will be safe from these poisons.

(10764) J. A. H. asks: Will you kindly explain how voltmeters and ammeters can be read to 1/10 their divisions? A. A scale is usually read to a tenth of a division by estimating the fractional part in tenths with the eye. This is of course not accurate, but the best that can ordinarily be done. The error, with experience, need not exceed a tenth. Sometimes voltmeters and ammeters are provided with shunts, which change the value of a division of the scale. Thus you can have a shunt made which will make one division have one-tenth of its present value. This will be much better than to estimate by the eye the fractional part of a division indicated by the pointer.

NEW BOOKS, ETC.

THE AMERICAN BATTLESHIP AND LIFE IN THE NAVY. By Thomas Beyer. Chicago: Laird & Lee, 1908. 12mo.; pp. 246. Price, \$1.25.

A book devoted to a description of life in the United States navy from the standpoint of the seaman must necessarily possess a special value. Literature bearing upon the navy, whether in description of the ships, or of the life led by those who form the ships' complement, is plentiful; but these delineations of a naval man's life at sea are more or less of a fictional character. Hence the present volume, written by a "ship's fitter of the first class" in the United States navy, and based on his personal experience, has a special value of its own, and will be welcomed by that large class of readers who wish to learn about life on the ships of our navy as it actually is. The book divides itself naturally into two parts, the first half dealing with the day-by-day life of the seaman, his duties, drills, pastimes, chances of promotion, etc., and the second half containing an excellent description of the manner in which the ships are designed and constructed, and the uses to which they are put. The first chapter deals with the building and commissioning of the vessel, and the way in which officers are made. Chapter II. describes the preparations for a voyage, the life at sea and in port, giving its daily routine and a description of the drills of the week. For those who are seriously thinking of entering the navy, and are seeking information regarding the life and its opportunities, Chapter III. will be found particularly useful. It describes the crew and their duties, under the head of Engineers' Department, Carpenters' Gang, Deck Force, Ordnance Department, Pay and Medical Departments, and the Clerical Force. The rates of pay are given, and the opportunities for advancement both in rank and remuneration. The chapter closes with a description of the amusements and pastimes and a curious dictionary of "Man-of-War's" lingo. The last three chapters are devoted to the description of a battleship, its ordnance, guns, gun crews, ammunition, projectiles, and torpedoes. The nomenclature of the different parts of the ship are given, with a clear description of the drainage, ventilation, and fresh and salt water systems; and it closes with a description of the United States vessels, which includes six pages of tables giving full particulars of the size, horse-power, speed, battery, weight of discharge from guns, and the number of men carried, on every important ship of the navy. The tone of the book throughout is healthy and optimistic. The author, as the result of his personal experience, is an enthusiastic believer both in the excellence of our ships and the quality of the officers and men who man them. It is worthy of a wide circulation, and should prove a valuable aid in encouraging the better class of men of this country to enlist.

THE COPPER HANDBOOK. A MANUAL OF THE COPPER INDUSTRY OF THE WORLD. Vol. VII. Houghton, Mich.: Horace J. Stevens. 8vo.; cloth; 1228 pages. Price, \$5.

The new edition of the "Copper Handbook," Vol. VII, has just been issued. It has 1,228 pages, octavo, breviter type, being materially larger than before. The author apologizes for his inability to revise the book throughout, explaining that fire, sickness, and loss of five months' time prevented, but the new volume contains about 180,000 words of new matter in addition to the matter remaining unchanged from the preceding issue. This new edition of the "Copper Handbook" contains twenty-five chapters, an increase of nine, treating of copper under the headings of History, Geology, Chemistry, Mineralogy, Mining, Milling, Concentrating, Hydrometallurgy, Pyrometallurgy, Electrometallurgy, Alloys, Brands, Grades, Uses, Substitutes, Terminology, Geography, Copper Deposits, and Copper Mines and Statistics. The treatment given the subject is encyclopedic in scope, but the logical and orderly arrangement of the great mass of facts presented, coupled with the table of contents, full index, and alphabetical arrangement of districts, countries, mines, minerals, and glossary, render it possible to ascertain any given fact with almost as much ease as a word is found in a dictionary. This is a point of much value to readers that has been overlooked in many other works of reference. The "Copper Handbook" is not intended to replace other works for the use of technical men, but it does supplement all other technical books on copper, while for the average reader its hundreds of pages devoted to the scientific and technical features of the subject will be found to cover every point of interest. The language is plain throughout, and the layman will find the clear and easily understandable exposition of scientific facts a great aid, as the highly technical language used in many of the best scientific works is a serious stumbling block in the path of the man not technically trained.

STEAM TURBINES. By Carl C. Thomas. Third edition, revised and enlarged. New York: John Wiley & Sons. 8vo.; cloth; 334 pages, plates. Price, \$4.

The logical arrangement of Prof. Thomas's "Steam Turbines" and the numerical examples applying the underlying principles to problems of design, have obtained for the book an extensive use by teachers in colleges, and by

engineers wishing to master the fundamentals of the subject. The hydraulic, mechanical, and thermodynamic principles involved in turbine calculations are carefully but briefly set forth, and the methods of calculation actually in commercial use at the present time are employed in the problems worked out in the book. This gives the reader a grasp of the principles and methods of calculation, and conveys an understanding of the use of heat diagrams, velocity diagrams, and the graphical processes so generally used by engineers. The use of experimentally determined data, and the methods of design involving empirical coefficients are given prominence. The purpose of the book is to set before the reader principles and methods, and not to trace in detail the ever-changing mechanical arrangements found in practice. A careful working out of the practical examples contained in the book cannot fail to familiarize the student with that which is essential to a clear understanding of the action of steam turbines.

SOLDER. Its Production and Application. With a Brief History of Tin and Lead. By F. W. Schultz. Baltimore. 16mo.; cloth. Price, \$1.25.

In this age of rush, any one desiring to give information must be very concise in order to have attention bestowed upon him. The author of "Solder" has shown his realization of this fact, and presents in plain and simple language the observations he has made during a period of nearly forty years, regarding the manufacture and use of this important compound. The two metals from which solder is made are no doubt among the first that were obtained by mineralogical process; owing to their low melting points. Just when the alloy of the two came into use is not known accurately, yet it must have been at a very early date. The author calls attention to an odd fact existing in connection with the melting points of solders containing different proportions of tin and lead. Starting with 56 parts tin and 44 parts lead, having a fusion point of 345 deg. F., the melting point rises gradually as the proportion of tin is increased and then falls until a mixture of 20 parts tin and 30 parts lead is reached, when the melting point is again 345 deg. F. Further addition of tin causes a rise in the fusion point. This is no doubt due to the formation of some sort of a compound of tin and lead, to the formation of an allotropic modification of one of the constituents, or to the change in the nature of the solvent.

MODERN PIGMENTS AND THEIR VEHICLES. THEIR PROPERTIES AND USES CONSIDERED, MAINLY FROM THE PRACTICAL SIDE, AND HOW TO MAKE TINTS FROM THEM. By Frederick Maire. New York: John Wiley & Sons. 12mo.; cloth; 266 pages. Price, \$2.

The purpose of this book is to give a brief and concise history of all valuable pigments useful in painting—the main sources of their derivation and supply; their properties and chief uses; their good qualities and their defects will be pointed out and incidentally there will be presented the best methods of detecting adulteration. It is impossible in its small volume as this to enter into the chemistry of pigments nor into some of the intricate details of manufacture and preparation for use, except in the briefest manner that will give the reader a fair idea of the composition. This is about all that painters or dealers require to know of the chemical side of pigments. Additional details would be of no importance, and no one but a manufacturer of colors would be interested in them.

AN INTRODUCTORY COURSE OF CONTINUOUS CURRENT ENGINEERING. By Alfred Hay. New York: D. Van Nostrand Company. 8vo.; cloth; 327 pages, illustrated. Price, \$2.50.

This work is introductory in the sense that only elementary methods of treatment are made use of throughout, and that no attempt is made to cover the entire field of continuous current engineering. It furnishes a simple account of the component parts of a continuous current lighting and power plant—dynamo, motors, secondary cells, measuring instruments, and the other apparatus and principles with which it is well to be familiar.

INVENTIONS: HOW TO PROTECT, SELL AND BUY THEM. By F. B. Wright. New York: Spon & Chamberlain. 1908. 16mo.; pp. 108. Price, 25 cents.

The author states in his preface that this book does not pretend to teach inventors how to be their own attorneys, nor how to prepare and prosecute an application for a patent. The time-worn adage that he who is his own lawyer has a fool for a client, is as true of patent law as it is of other branches. This is good advice. We can hardly say as much for the section devoted to selling and buying as it is devoted simply to the suggested forms employed as licenses, transfers, etc.

PRINCIPLES AND PRACTICE OF ARTIFICIAL ICE-MAKING AND REFRIGERATION. By Louis Schmidt. Third edition, revised and enlarged. Philadelphia: Philadelphia Book Company. 8vo.; cloth; 437 pages, 205 engravings. Price, \$3.

The third edition of "Ice-making and Refrigeration" will be found to contain a large amount of new material, in addition to the greater part of the original matter contained

in the former editions. The scheme of subdivision into four parts has been adhered to as heretofore, although there has been some rearrangement of material. All that need be said of this book is that it is already considered the standard work upon refrigeration.

THE FIRE ASSAY OF GOLD, SILVER, AND LEAD IN ORES AND METALLURGICAL PRODUCTS. By Leonard S. Austin. San Francisco: Mining and Scientific Press. 8vo.; cloth; 88 pages, illustrated. Price, \$1.

A system of assaying, covering determinations of silver and gold, and of lead as well, according to the methods commonly recognized in the Rocky Mountain States. To prevent embarrassment to the beginner, but one method is described, although others of equal merit may exist.

THE THEORY OF LIGHT. A Treatise on Physical Optics. By Richard C. MacLaurin. In Three Parts. Part I. Cambridge, England: University Press. 8vo.; cloth; 326 pages. Price, \$2.75.

The treatise, of which this volume forms the first part, gives an account of the theory of physical optics that is systematic, and is as complete as possible within the somewhat narrow limits by which the work is bounded. The treatment is designed to lay a foundation for the establishment of the relation between light and electricity. The second volume will bring out this point more clearly; dealing with the branches not taken up in the first part, namely, dispersion, the rotations, both structural and magnetic, aberration, diffraction, etc. The connection between light and electricity is often imperfectly presented, for in many books it is not referred to, except in a sketchy way toward the close. The third and last volume of the series will be devoted to a history of optical theories. One of the features of the first volume, which as yet is the only one to have reached us, is the close connection maintained between theory and experiment.

AFTER EARTHQUAKE AND FIRE. A Reprint of the Articles and Editorial Comment Appearing in the Mining and Scientific Press Immediately After the Disaster at San Francisco, April 18, 1906. San Francisco: Mining and Scientific Press. 8vo.; cloth; 194 pages, illustrated. Price, \$1.

A reprint of the articles and editorial comment appearing in the Mining and Scientific Press directly after the disaster at San Francisco two years ago. Although, following our racial custom, we have very nearly forgotten that such an event took place, the photographs reproduced show very clearly what are the effects of an earthquake. Some interesting remarks upon the cause of the displacement that did so much damage are also included.

ELECTRICAL RAILROADING, OR ELECTRICITY AS APPLIED TO RAILROAD TRANSPORTATION. By Sidney Ayler-Small. Chicago: F. J. Drake & Co. Illustrated. 12mo.; pocketbook form and limp leather; 919 pages. Price, \$3.50.

A book written principally for railroad men who have to do with the electrical machinery and apparatus which is installed upon steam roads, and for those who wish to keep pace with the increased use of electricity in all branches of life. No man can profitably refuse to learn something of this so generally used force. The style of the book makes it convenient to be carried in the pocket, and the method of teaching, while simple and elementary, is not insulting to the intellect. A more complete and satisfactory book it would be hard to imagine.

THE ENGINEERING INDEX ANNUAL FOR 1907. Compiled from the Engineering Magazine during 1907. New York: The Engineering Magazine. 8vo.; cloth; 435 pages. Price, \$2.

The information on a given subject is so broadly scattered in this age of technical literature that it is impossible for a member of any profession to keep track of important articles that have a bearing upon his work unless there is at his disposal some sort of general index, or publication of classified abstracts. "The Engineering Index" furnishes a classified list of various articles germane to the subject that have appeared in the past year. The "classified" system is followed, instead of the "alphabetical" system of former volumes, as this method makes the locating of any special branch possible with greater facility.

WOOD. Manual of Natural History and Industrial Applications of the Timbers of Commerce. By G. S. Boulger, F.L.S., F.G.S., F.R.H.S., A.S.I. London: Edwin Arnold, 1908. 8vo.; pp. 348; 48 plates and 42 illustrations. Price, \$4.20.

This is the second edition revised and enlarged of what has proved to be a most valuable work of reference. It is filled with interesting statistical matter, and the chapters relating to testing of wood, the various uses of wood; seasoning and storage of woods, are all very valuable. It is a most excellent work and is deserving of a large sale. The section devoted to woods of commerce, their sources, character, and uses, is arranged in alphabetical order, facilitating reference. There is also a select bibliography, and an appendix giving the distinctive microscope structures of woods. The book is well indexed.

INDEX OF INVENTIONS

For which Letters Patent of the

United States were Issued


for the Week Ending

May 5, 1908.

AND EACH BEARING THAT DATE

[See note at end of list about copies of these patents.]

Acid and making the same, soluble salts of the anhydro-oxy-methylene-diphosphoric, S. Posternak	886,852
Adding machine, G. Roth	886,543
Adding machine ribbon controlling mechanism, Wetmore & Niemann	886,747
Alloy, aluminum, W. Gosmann	886,597
Alloys, producing low carbon ferro, E. F. Price	886,858
Aluminum and other metals, reducing, H. S. Blackmore	886,757
Amusement apparatus, C. C. Langsdorf	886,614
Amusement apparatus, C. A. Carlson	886,762
Amusement device, H. O. Neebe	886,627
Animal trap, A. W. Little	886,381
Arch construction, automatic adjustable, W. M. Thomas	886,666
Automatic carrier and dumper, H. G. Diefenbaugh	886,959
Automobile, H. K. Holman	886,506
Automobile, E. Koeb	886,520
Automobile steering device, J. Horat	886,508
Automobiles, cushion attachment for, J. E. Marriner	887,002
Automobiles, motor driven and steered fore carriage for, L. Krieger	886,990
Bag fastener, Hfingel & Fuller	887,044
Bag frame lock or fastener, Lau & Melzer	886,708
Bag or purse fastener, L. B. Prahar	886,855
Bait holder, L. R. Balken	886,337
Barium oxide, making, C. B. Jacobs	886,607
Barrels, casks, and the like, metal head for, A. A. Hurst	886,981
Bath tub supply pipe connection, W. G. Stewart	886,888
Bath tub trap, T. S. Chew	886,943
Batteries, negative element for primary, C. B. Schoenmehl	886,651
Battery. See Electric, battery.	
Battery cover and element support, C. B. Schoenmehl	886,649
Beading implement, G. E. Morris	886,394
Bearing, ball, R. G. Cornforth	886,949
Bearing, roller, W. S. Sharpneck	886,547
Bearings, means for lubricating sleeve, W. H. McGauley	886,625
Bed, folding, N. C. Merrill	886,622
Beehive forming mechanism, P. J. Fink	886,488
Belt, A. Susseles	886,439
Belt, R. B. Dwyer	886,780
Belt for power transmission, G. Magaldi	886,525
Belt-shifting mechanism, I. A. Rommer	886,730
Billet loop, G. D. Bailly	886,575
Blast or exhaust apparatus, G. Elbel	886,590
Blocks, form for setting up and holding sectional, W. T. Huening	886,373
Bobbin spindle, H. Wyman	886,459
Boll weevil catching machine, W. M. & R. J. McCurdy	886,535
Book for manifold writing, W. E. Easterbrooks	886,782
Bookbinder's strip applying machine, C. J. Duggan	886,961
Bookbinding, W. H. Rademaekers	886,726
Boot and shoe cleaning stand, A. F. Bigford	886,756
Bottle, Hoffmann & Muller	886,807
Bottle, non-refillable, J. F. Hedge	886,803
Bottle or jar closure, C. J. Lundquist	886,618
Bottle packing, B. Kochs	886,818
Bowling alley ball stop, W. W. Veering	886,556
Box top, powder, W. H. Perkins	886,632
Boxes, crates, etc., reinforced corner for, H. M. Amos	886,462
Bracelets, making, P. H. Long	886,616
Brake, S. E. Chidister	886,944
Brake head, adjustable, P. T. Handiges	886,603
Brake lever, J. J. Byers	887,030
Brake shoe, I. A. Gibbs	886,694
Brake-shoe, W. H. Thrash	886,553
Braking system, L. B. Aikman	886,460
Broom holder, C. J. Wren	886,458
Brush, blacking, R. T. Overton	886,848
Brush, fountain, H. L. Loring	886,996
Brush holder, W. L. Waters	886,559
Buggy-top support, J. Elms	886,785
Building block forming machine, W. Raab	886,404
Building structure, M. A. Morton	887,008
Bundle or package tie, H. B. Ward	886,905
Burglar and fire alarm, invisible electric, J. W. Dawson	886,355
Burial apparatus, Garphelde & Westerheide	886,593
Burial casket, A. S. Seidel	887,019
Button fastener, M. B. Ryan	886,731
Buttonhole tape, A. Bernstein	886,924
Cabinet, dispensing, L. Lammer	886,823
Cable hanger, H. W. Pleister	886,634
Calculator, J. E. Duncan	886,588
Camera, folding photographic, F. A. Brownell	886,473
Cameras, device for focusing photographic, W. Thorner	886,739
Can opener, J. Zander	886,919
Cans, packing composition for seams of, L. C. Sharp	886,423
Car construction, J. R. Cardwell	886,761
Car coupling, C. H. Tomlinson	886,554
Car coupling, G. P. Ritter	886,864
Car door operating mechanism, C. A. Lindstrom	886,380
Car, dump, H. B. Earling et al.	886,781
Car grain door, railway, Marxen & Woodward	886,529
Car lighting system, W. A. Turbayne	886,449
Car replacer, G. H. Sargent	886,644
Car vestibule, L. Uilo	886,744
Cars, attachment for dirt push, J. W. Grubbs	886,800
Cars, etc., ventilator for railway, J. E. Ward	886,558
Carbureter, T. E. Puddington	886,403
Carbureter, W. L. Marr	886,526
Carbureter, G. M. Schebler	886,545
Carbureter, T. E. Puddington	887,017
Carbureting mechanism for internal combustion engines, A. P. Brush	886,760
Card record, I. S. Bassett	886,753
Carriage, mechanical doll, C. H. Hood	886,507
Carriage robe, cushion, and attachment for holding toilet essentials, combined, K. A. Werle	886,907
Cart, fodder, T. F. Talbott	886,664
Cash box, R. S. Burns	886,345
Cash carrier, pneumatic tube, D. S. Hager	886,496
Cement chair mold, M. Serrier	886,877
Cementing material and making same, T. W. Cappon	886,579
Chain, J. F. Wagner	886,904
Chair seat making machine, L. G. McKnight	886,721
Chart, school room, A. E. Osborne	886,639
Check register, D. W. Morse	886,839
Check, sales, G. Heinersdorf	886,976
Cheese cutter, computing, J. W. Isler	886,982
Cherry pitter, A. G. Wehnhardt	886,906
Choke coil, L. O. Langworthy	886,824
Chuck, lathe, J. M. Jipperson	886,812
Churn, D. W. McNeel	886,626
Churn, J. Moir	886,836
Cigar ash thimble and protector, H. S. Cunningham	886,352
Cigar boxes, price marker and lid holder for, Gale & Davis	886,692
Clamp. See Trolley line clamp.	
Clamping joinery work, means for, C. Krogh	886,613
Cleaning and polishing composition, S. R. Fee	886,787



LATHE LESSONS

The test of time has proved to mechanics, electricians, model makers, gunsmiths, etc., the superiority of

STAR Foot Power LATHES

High grade in every respect, improved up-to-date, scientifically constructed and most profitable for machine shop and tool room service. Ask for Catalog "B-2"

THE SENECA FALLS MFG. CO.
695 Water St., Seneca Falls, N. Y.

Engine and Foot Lathes

MACHINE SHOP OUTFITS, TOOLS AND SUPPLIES. BEST MATERIALS. BEST WORKMANSHIP. CATALOGUE FREE


SEBASTIAN LATHE CO., 120 Culvert St., Cincinnati, O.

Foot and Power and Turret Lathes, Planers, Shapers, and Drill Presses.
SHEPARD LATHE CO., 133 W. 2d St. Cincinnati, O.

Veeder Counters

to register reciprocating movements or revolutions. Cut full size. Booklet Free

VEEDER MFG. CO.
18 Sargeant St., Hartford, Conn.
Cyclometers, Odometers, Tachometers, Counters and Fine Castings.



MAKE YOUR BICYCLE INTO A MOTORCYCLE

at small cost by attaching the **ERIE**. This includes all parts so that anyone can make a strong, durable machine that will climb steep hills. Send for stamps for either bike Attachment catalog S, or Motorcycle catalog C.

Motorcycle Equipment Co., Hammondsport, N. Y.

PATENTS

Our Hand Book on Patents, Trade-Marks, etc., sent free. Patents procured through Munn & Co. receive free notice in the


SCIENTIFIC AMERICAN

MUNN & CO., 361 Broadway, N.Y.
BRANCH OFFICE: 625 F St., Washington, D.C.

Manufacturing Engineers

We design and build special machinery of every description. Let us develop your ideas.

CHAS. E. DRESSLER & CO.
141-149 East 23d St., New York City
ESTABLISHED 1884



FOR GUNSMITHS, TOOL MAKERS, EXPERIMENTAL & REPAIR WORK, ETC.

From 9-in. to 13-in. swing. Arranged for Steam or Foot Power. Velocipede or Stand-up Treadle. Send for Lathe Catalog.

W. F. & JNO. BARNES CO.
Established 1873.
1899 Ruby St., Rockford, Ill.



THE ROCKFORD 14-INCH DRILL

is adapted for work from 1-16 inch to 3/4 inch. A strong, substantial, well built drill. Plain lever or power feed as desired. We build a full line of Drills. All sizes furnished in Gangs. Also have 9-in. and 11-in. Screw Cutting Lathes, and a 24x2-in. Wet Tool Grinder. Catalog S on request.

ROCKFORD DRILLING MACHINE CO.
Rockford, Ill.
European Branch, 149 Queen Victoria St., London, E.C.



USE GRINDSTONES

If so we can supply you. All sizes mounted and unmounted, always kept in stock. Remember, we make a specialty of selecting stones for all special purposes. Send for catalogue "I".

The CLEVELAND STONE CO.
2d Floor, Wilshire, Cleveland, O.

HOW Manufacturers Can Increase Their Business

Read carefully, every week, the

Classified Advertising Column

in the

SCIENTIFIC AMERICAN

Some week you will be likely to find an inquiry for something that you manufacture or deal in. A prompt reply may bring an order.

Watch it Carefully

Clothes hanger, T. M. Anderson.....	886,917
Clothes pounder, J. H. Bowling.....	886,675
Clothes washer and drier, F. A. Dinsmore	886,358
Clutch, H. Haeblerlin.....	886,600
Clutch, A. W. Wigglesworth.....	886,697
Cock, water, L. W. Eggleston.....	886,390
Coffee roaster, B. T. Shortt.....	886,427
Coherer and decoherer, J. L. Jones.....	886,983
Coil support, W. L. Waters.....	886,561
Coin actuated mechanism, W. M. Reason...	887,048
Coin detector, F. Eckert.....	886,962
Coin receptacle, B. vom Eigen.....	886,687
Coin repository, B. vom Eigen.....	886,784
Coin testing machine, M. D. Sadtler.....	887,049
Collapsible box, W. F. Mestemacher.....	886,530
Collar, G. F. McManus.....	886,844
Compound engine, H. M. Sullivan.....	886,438
Concrete mixer, J. H. Stewart.....	886,434
Concrete mixer, J. F. Crowe.....	886,680
Concrete mixer, P. P. De Bogory.....	886,768
Condenser system, surface, J. Stumpf.....	886,661
Condensing apparatus, J. Astrom.....	886,465
Connection box, R. D. Holabird.....	886,978
Controller, G. B. Schley.....	886,733
Conveyer, R. C. Straight.....	886,891
Core making machine, Blau & Kelly.....	886,927
Core oven, B. H. Prack.....	886,854
Corn and the like, holder for, G. P. Huguet	886,510
Cornet or the like, T. C. Edwards.....	886,733
Cotton picker's sled, T. A. Windsor.....	886,451
Course and log recorder, T. M. Foote.....	886,788
Crate, laundry, J. Eastman.....	886,685
Cream separator, E. R. Bailey.....	886,921
Cream separator, liner for centrifugal, Marsh & Morgan.....	886,384
Cream separators, liner for centrifugal, T. W. Morgan.....	886,393
Cuff, D. H. Anderson.....	886,671
Cuff protector, M. P. Vucassovich.....	886,903
Cultivator, C. S. Sharp.....	886,422
Curtain pole, J. Kroder.....	886,991
Cut-out block, F. Brunberg.....	886,475
Cycle handle bars, handle grip for, M. C. Stokes.....	886,889
Damper regulator, C. C. Koster.....	886,988
Derrick, dirt, G. Sorteberg.....	886,657
Desk table, S. M. Wirts.....	886,452
Display holder for jewelry and the like, M. Jersemann.....	886,608
Display rack, J. B. Whitaker.....	886,748
Display stand, W. Crowther.....	886,480
Door bolt, F. A. Tomkins.....	886,742
Door fixture, sliding, C. Metterhausen.....	886,531
Door holder and bumper, combined, J. B. Hightower.....	886,503
Door opener, electric, J. Loch.....	886,827
Draft equalizer, A. Hines.....	886,805
Draft tube, H. A. Maxwell.....	886,386
Dredge, E. J. Bevan.....	886,343
Dredge, siphonic, W. J. Moninghoff.....	886,390
Drill bit, fluid feed side inlet, J. H. Wiest	887,051
Drilling apparatus, P. Repsold.....	886,862
Drum, bass, G. W. Britton.....	886,471
Drums, construction of, F. C. Poland.....	887,016
Dust guard, H. C. Lafferty.....	886,822
Dye and making same, brown sulphur, Moffatt & Spira.....	886,532
Dye and making same, green, P. Julius.....	886,815
Dye and making same, red trisazo, G. Kallischer.....	886,985
Ear stopper, G. B. Frank.....	886,790
Egg holder, J. Csincsak.....	886,954
Electric battery, C. B. Schoenmehl.....	886,652
Electric cable, C. E. Wilson.....	886,566
Electric heater and rheostat, J. H. Delany	886,932
Electric furnace, E. P. Price.....	886,856
Electric machine, dynamo, W. I. Waters.....	886,562
Electrical connection, Jacob & Hagadorn...	886,811
Electrical distribution system, A. S. Hubbard.....	886,371
Electrical regulation system, M. Moskowitz	886,395
Electrical system of distribution, W. E. Winship.....	887,052
Electromagnet, H. Rowntree.....	886,869
Elevated carrier, W. J. Chance.....	886,763
Elevator, F. L. Eager.....	886,764
Engine, spark plug, explosion, E. A. LaHar.....	886,523
Engraving machine, Turner & Corley.....	886,898
Envelope, M. A. Corliss.....	886,350
Envelope, G. Hitzler, Jr.....	886,977
Envelope and letter sheet, combined, I. L. Greenblatt.....	886,971
Envelope, return, T. C. West.....	886,449
Excavator, T. P. Rochford.....	886,729
Explosion motor, A. Peugeot et al.....	886,539
Explosive, C. E. Bichel.....	887,027
Explosive engine, W. R. Harris.....	886,500
Explosive engine, K. Nicoll.....	886,846
Expression device, F. W. Wood.....	886,649
Eye testing apparatus, R. Dodge.....	886,772
Fabric, See Knit fabric.....	
Fan, O. Selg.....	886,419
Farm gate, W. N. Mark.....	886,383
Fastening device, W. S. Vollmer.....	886,902
Faucet, altering, J. Koehler.....	886,819
Feed box, vermin exterminating, D. A. Bradford.....	886,934
Feed for automatic machines, F. H. Richards.....	886,408
Feed water heater, boiler, R. Kabitz.....	886,516
Feeder and exerciser, poultry, W. M. Conner.....	886,580
Feeder, pig, F. B. Espy.....	886,485
Fence, W. M. Dillon.....	886,483
Fence-making device, V. Landholm.....	886,376
Fence post, W. H. Sawyer.....	886,544
Fence stretcher, I. K. Hollinger.....	886,369
File and assembling means, document, J. J. Nicholson.....	887,011
File, bill, E. D. Fales.....	886,486
File, bill, G. C. Odor.....	886,724
Files, guide card or partition for vertical, L. Senge.....	886,421
Filter elements, lining for, C. Sellenscheidt	886,420
Filter plate, H. M. Ashby.....	886,464
Finger spreading apparatus, R. Finger.....	886,591
Fire alarm, automatic, W. T. Munro.....	886,624
Fire curtain, A. M. Fuller.....	886,968
Fire extinguishing receptacles, cover for, J. F. MacWilliam.....	886,713
Fire hose bridge, R. C. Groh.....	886,798
Fire pail, chemical, J. G. Mastin.....	886,385
Fish hook, E. L. Gilmore.....	886,794
Fish screen, J. R. Grant.....	886,797
Fishing line drying reel, C. L. Fowle.....	886,690
Floor dressing machine, A. L. Blodgett.....	886,928
Flue scraper, E. F. Fletcher.....	886,332
Flushing tank, E. J. Wackerle.....	886,446
Flushing tank and closet, J. O. Bree.....	886,470
Folding box, F. P. Bulett.....	886,810
Forceps, animal, Rowe & Reimer.....	886,414
Forge, blacksmith's, H. P. Dorsheimer.....	886,773
Form, garment, H. Frankel.....	886,490
Form or display rack for shirt waists and similar garments, bust, M. Litt.....	886,524
Frame, J. Mueller.....	886,840
Frictional brake, W. Love.....	886,997
Fruit and flower picker, J. B. Tuttle.....	886,555
Furnace wall, K. C. Hoxie.....	886,370
Furnaces, air feeding grate for, J. O. Schmidt.....	886,546
Fuse, mechanical time, K. Wieser.....	886,564
Gage and signal device, combined, M. G. Melvin.....	886,833
Game apparatus, T. A. Randall.....	886,861
Game apparatus, G. S. Parker.....	887,014
Garment attachment, Thompson & Fowler	886,894
Garment, child's, F. H. Sprague.....	886,735
Garment clasp, J. Lemay.....	886,709
Garment hook and hat holder, M. S. Gorman.....	886,365
Garment supporter, D. Backlund.....	887,025
Garment supporter attachment, A. H. Sawtell.....	886,732
Gas burner controlling mechanism, F. Cais	886,677
Gas burner, incandescent, Busquet & Ramassot.....	886,940
Gas generating apparatus, A. L. Blaesy.....	886,469
Gas, generating power, Boyd & McKay.....	886,577
Gas generator, acetylene, J. Heaton.....	886,699
Gas keys, safety cap for, E. J. Cherrington	886,478
Gas light fixture, J. Maas.....	886,712
Gas lighter, automatic, E. Zickwolf.....	886,914
Gas pressure gage, W. Thomas.....	886,552
Gas producer, J. R. George.....	886,491
Gas producer feeding mechanism, V. E. Edwards.....	886,484
Gas producers, fuel feeding mechanism for, D. Baker.....	886,672

73 Million Dollars

IN

37 WEEKS!

Ordinary Life Insurance Issued.

The New Low Cost Policy

OF

The Prudential

is the Greatest Triumph in Life Insurance!

This is the Policy the People Want!


After eight months of unparalleled success, read what our Enthusiastic Field Managers say:

THESE ARE SELECTED FROM HUNDREDS OF LETTERS.

- "The Prudential agent is to-day invincible, and is envied by representatives of all companies."—R. J. Mix, New York City.
- "I delight in selling it because I know the insured will never be disappointed in the result."—O. Edgar Fell, Seattle, Wash.
- "New Policy a strong card. In competitive cases have written every one against entire field."—B. H. Timberlake, Minneapolis, Minn.
- "Public clearly understands the liberal guaranteed contract. Most insurance for the least money."—H. R. Gould, Omaha, Neb.
- "The Policy sells—and it satisfies."—James Perry, New York City.
- "New Policy has met a popular demand. Good insurance at low cost."—H. A. Austin, Kansas City, Mo.
- "That the cost has been reduced appeals directly to the intelligence and common sense of the people."—C. H. Johnston, Des Moines, Ia.
- "This office is 50% ahead of last year's business for same period. This is responsible for my enthusiasm."—F. J. McGrath, Sioux City, Ia.
- "New Policy, Liberal Provisions, Low Premiums, attract prospective insurers."—B. D. Van Ostrand, Topeka, Kans.
- "All the people need is a clear presentation of facts to lead them to buy the New Policy. Our business this year is better than last two years."—R. S. Boyns, San Francisco, Cal.
- "New Low Cost Prudential Policy is the standard. We represent the best."—O. O. Orr, Denver, Colo.
- "Prudential's great size, tremendous business, absolute safety and New Policy make competition a thing of the past."—H. B. Nelles, Los Angeles, Cal.
- "Our contracts are to-day about as near perfect as human ingenuity could devise."—S. H. Chiles, McAlester, Okla.
- "It is poor business to pay a high premium for privilege of getting a small percentage of cost back. It is best to begin with a net premium as provided in The Prudential New Low Cost Policy."—J. B. Anderson, Zanesville, Ohio.
- "We have never written as much business in the same period. Competition fades before us."—L. B. Hall, Grand Rapids, Mich.
- "It is what the public has been looking for."—F. H. Butler, Butte, Mont.
- "We have what the public want. Recently wrote two applications \$50,000 each. Eight companies had been soliciting, but business came to us unsolicited."—C. C. Cornet, Detroit, Mich.
- "During past six months our business has been more than twice what it was the preceding six months. An eloquent tribute to the selling qualities of the New Policy."—Hodges, Mitchell & Reynolds, Asheville, N. C.
- "New Policy best ever offered the public."—A. W. McNeil, Newark, N. J.
- "My business for first quarter of 1908 was 50% better than same period 1907."—J. M. Skinner, Atlanta, Ga.

Annual Cost Whole Life Policy Per \$1,000

Age 20	-	-	-	-	\$14.96
Age 25	-	-	-	-	16.77
Age 30	-	-	-	-	19.08
Age 35	-	-	-	-	22.10
Age 40	-	-	-	-	26.09
Age 45	-	-	-	-	31.47
Age 50	-	-	-	-	38.83
Age 55	-	-	-	-	48.98



This is the Very Best Policy for the Man Without Life Insurance, and for the Man Who Needs More.

SEND FOR SPECIMEN POLICY TODAY.

State age, nearest birthday, and occupation.

Write Dept. 121.

The Prudential

Insurance Co. of America

Incorporated as a Stock Company by the State of New Jersey.

JOHN DRYDEN,
President.

Home Office:
NEWARK, N. J.

Popular Books

HOME MECHANICS FOR AMATEURS

By **GEORGE M. HOPKINS.**
Author of "Experimental Science"
12mo. 370 Pages, 320 Illustrations
Price, \$1.50 Postpaid

The book deals with wood working, household ornaments, metal working, lathe work, metal spinning, silver working; making model engines, boilers and water motors; making telescopes, microscopes, and meteorological instruments, electrical chimes, cabinets, bells, night lights, dynamos and motors, electric light, and an electrical furnace. It is a thoroughly practical book by the most noted amateur experimenter in America.

Experimental Science

By **GEORGE M. HOPKINS**
Revised and Greatly Enlarged. 2 Octavo
Volumes. 1,100 Pages, 900 Illustrations
Cloth Bound. Postpaid, \$5.00

Owing to the amount of new matter added the book is now published in two volumes, handsomely bound in buckram. Of the additions which have been made, among the most important are: A full illustrated description of the Electric Motor, prepared expressly for this edition of "Experimental Science"; chapters on Alternating-current Machinery, and clear, concise Explanations of Wireless Telegraphy and Telephony, Electrical Measuring Instruments, the Electric Clock, the Telephone, High Tension Currents, the Nernst Lamp, and methods of measuring the heat of the stars. No other work contains such a fund of trustworthy up-to-date scientific information, presented in a clear and simple style. Send for descriptive circular.

Scientific American Reference Book

12mo. 516 Pages, Illustrated, 6 Colored
Plates. Price, \$1.50 Postpaid

The result of the queries of three generations of readers and correspondents is crystallized in this book which is indispensable to every family and business man. It should be found on every desk. It is extensively used by government officials. It has been revised by experts. The book contains 50,000 facts and is much more complete and exhaustive than has ever been attempted. It is profusely illustrated with engravings, many of them imparting the information by means of comparative diagrams.

The Scientific American Boy

By **A. RUSSELL BOND**
12mo. 320 Pages. 340 Illustrations
Price \$2.00 Postpaid

This is a story of outdoor boy life, suggesting a large number of diversions which, aside from affording entertainment, will stimulate in boys the creative spirit. In each instance complete practical instructions are given for building the various articles.
The needs of the boy camper are supplied by the directions for making tramping outfits, sleeping bags and tents; also such other shelters as tree houses, straw huts, log cabins and caves.

MAGIC Stage Illusions and Scientific Diversions, including Trick Photography

The illusions are illustrated by the highest class of engravings, and the exposes of the tricks are, in many cases, furnished by the prestidigitators themselves. Conjuring, large stage illusions, fire-eating, sword-swallowing, ventriloquism, mental magic, ancient magic, automata, curious toys, stage effects, photographic tricks, and the projection of moving photographs are all well described and illustrated.
By A. A. HOPKINS. 568 pages, 420 illus. Price \$2.50

A Complete Electrical Library

By **Prof. T. O'CONNOR SLOANE**

An inexpensive library of the best books on Electricity. Put up in a neat folding box. For the student, the amateur, the workshop, the electrical engineer schools and colleges, comprising five books, as follows:
Arithmetic of Electricity, 138 pages, \$1.00
Electric Toy Making, 340 pages, 1.00
How to Become a Successful Electrician, 189 pages, 1.00
Standard Electrical Dictionary, 682 pages, 3.00
Electricity Simplified, 158 pages, 1.00
Five volumes, 1,300 pages and over 450 illustrations.
A valuable and indispensable addition to every library.

OUR GREAT SPECIAL OFFER.—We will send prepaid the above five volumes, handsomely bound in blue cloth with silver lettering, and inclosed in a neat folding box, at the **Special Reduced Price of \$5.00** for the complete set. The regular price of the five volumes is \$7.00.

The New Agriculture

By **T. BYARD COLLINS**

12mo, 374 Pages, 160 Illustrations
Cloth. Price, \$2.00


This valuable work sets forth the changes which have taken place in American agricultural methods which are transforming farm life, formerly so hard, into the most independent, peaceful, and agreeable existence. Farm life to-day offers more inducements than at any previous period in the world's history, and it is calling millions from the desk. The present work is one of the most practical treatises on the subject which has ever been issued.

The latest and best book on the subject. Contents: I. The New Call to the Farm.—II. The New Soil.—III. Irrigation.—IV. The New Fertilization.—V. The New Transportation.—VI. New Interests.—VII. New Creations.—VIII. New Varieties.—IX. New Practice.—X. New Machinery.—XI. The New Inspiration.

Special circular of contents of these volumes sent free.
MUNN & CO., 361 Broadway, New York

Gas producers, poker mechanism for, S. B. Sheldon	886,655
Gases, apparatus for producing electric discharges through, A. Schneller	886,874
Gate, W. B. Morgan	886,533
Gate, J. W. Robinson	886,867
Gear casing, transmission, A. Tedeschi	886,738
Gear, change speed, F. Hesselius	886,701
Gear for cycles and the like, gradually variable speed, F. H. De Veuille	886,356
Gear, variable speed, W. Wolter	886,911
Gearing, machine for cutting toothed, G. Nardin	886,398
Gearing, speed change, E. J. McClellan	887,010
Glass articles, apparatus for drawing hollow, J. H. Lubbers	886,618
Glass, ornamenting, J. M. Conroy, reissue	12,789
Glassware finishing, automatic snap for, J. E. Crawford	886,351
Grader, road, Haynes & Webb	886,802
Graft wrapping machine, W. H. Bell	886,923
Grain cover, S. B. Brier	886,477
Grain heater, Klementis & Sebastian	886,518
Grain treating apparatus, C. D. Stephens	886,887
Grate, J. W. Wolcott	886,453
Grate, movable, A. B. Reck	886,727
Grinding machine, cutlery, Bastian & Gratz	886,754
Grindstone for grinding or smoothing lithographic stones, O. Reuchlin	886,640
Gums of certain sapotaceae, substance produced from the, M. M. Dessau	886,482
Gun, J. Becker	886,576
Gun sight, Bassell & Blenkner	886,752
Gun with recuperator spring, recoil, H. K. nonenberg	886,611
Gun with screw elevating mechanism and adjustable sight device, O. Graubering	886,598
Guns, apparatus for adjusting elevation of, G. A. Schoeller	886,648
Guns, breech-closing device for, Bobbert & Zeller	886,929
Guns, fluid brake for recoil, Lauber & Koch	887,045
Guns, pneumatic recuperator for recoil, Lauber & Koch	886,615
Handle, See Knife handle	
Harness, W. B. Hilton	886,504
Harvester, G. W. Ingersoll	886,703
Hay gatherer and stacker, E. M. Orton	886,725
Hay press, E. W. Kelsey	886,986
Hay rack standard, B. C. Speer	886,549
Hay racks, load binder for, C. H. Cline	886,479
Heat coil and protector unit, W. Kaisling	886,374
Heating and ventilating system, J. E. Moore	886,391
Heating, art of, E. H. Gold	886,969
Hectograph composition, W. Doctor	886,771
Heel locking device, adjustable, C. S. Shute	887,020
Hides for the manufacture of leather, preparation of, O. Rohm	886,411
Hinge seat cutting tool, G. M. White	886,750
Hinge, spring, F. Brucker	886,474
Hitching block, portable, J. B. Barnett	887,026
Hog hoist, Schmidt & Pfum	886,417
Holder, combination, F. Haase	886,495
Horse blankets, lap robes, etc., safety attachment for, J. E. Hunter	886,511
Horseshoe, J. G. Burns	886,939
Horseshoe, nailless, W. Dettmann	886,957
Hydrocarbon engine, Packard & Hatcher	887,013
Injector, W. R. Park	886,849
Ink well, J. C. Piers	886,859
Inkstand, B. O. Roberts	886,865
Insecticide, M. Bean	886,340
Internal combustion engine, J. B. Knickerbocker	886,519
Internal combustion engine, J. Sulzer	886,662
Iron, treating, P. Wilks	886,968
Ironing board, F. R. Fiecke	886,361
Jar closure, F. W. Bedford	886,342
Jar cover fastening, fruit, W. A. Bostwick	886,930
Key action, J. C. Wahl	886,447
Kitchen rack, O. Rothengatter	886,413
Knife cleaning and polishing machine, H. F. Hambruch	886,602
Knife handle, W. W. Howell	886,809
Knit fabric and making same, R. J. Steiner	886,886
Lace fastener, shoe, R. Gayton	886,792
Ladder, R. R. Jones	886,514
Ladder, extension step, A. C. Taylor	886,737
Lamp, White & Stover	886,749
Lamp, electric incandescent, H. Kuzel	886,821
Lamp, miner's, S. J. Thompson	886,441
Lamp, vapor electric, R. Kuch	886,706
Lantern, W. S. Hamm	886,973
Latch mechanism, door, Pool & Elliott	886,635
Lathe, P. Murray	886,719
Lens grinding machine, toric, Wall & Saile, reissue	12,790
Lenses, manufacturing bifocal, J. L. Borsch, Jr.	887,028
Leveling staff, W. F. Darling	886,354
Lifting pack, Collier & Rigg	886,766
Limekiln, R. H. Moler	886,837
Linotype machine, A. Dow	886,584 to 886,587
Linotype machine, W. H. Schaff	886,646
Linotype machine matrix, A. Dow	887,034
Linotype machine spacer or justifier, A. Dow	887,035
Liquid applying instrument, Boyajeau & Craddock	886,932
Liquid holder, dispensing, H. P. Gorman	886,596
Loading apparatus, P. Bissen	886,344
Loading apparatus, N. Madson	887,000
Loading apparatus for wagons and the like, L. Kniffen	886,705
Log turner, S. D. Arthur	886,918
Loom, automatic filling replenishing, U. Hebert	886,700
Loom picker check, A. S. Cowan	886,952
Loom warp stop motion, J. B. Derfinak	886,769
Looms, automatic weft replenishing apparatus for, Rostrom & Worman	886,542
Looms, reversing mechanism for the take-up mechanism of, E. H. Ryon	886,871
Lubricator, C. B. & F. W. Hodges	886,368
Mail bag catcher and deliverer, G. J. Meier	886,832
Mail bag catching and delivering apparatus, J. C. Dayton	886,955
Mail delivery apparatus, A. K. Landis	886,995
Mailing device, J. R. McClellan	886,843
Map holder, A. J. Nystrom	886,723
Marking device, R. L. Herman	886,804
Massaging device, K. C. Jopling	886,984
Match box and other receptacle, B. vom Eigen	886,688
Measure, tape, S. D. Jordan	886,814
Measuring the refraction of the eye, lens system for, H. L. De Zeng	886,770
Mechanical movement, H. Brammer	886,758
Metal cutting and shaping machine, J. R. Main	886,382
Metal drawing apparatus, J. T. S. & W. Moltrup	886,717
Metal heating furnace, J. R. George	886,492
Metal wheel, Williams & Grant	886,565
Metal working machine, S. Zietarski	886,572
Metals, electrolytic process of producing, Price & Herry	886,857
Metals, extracting, D. R. Robertson	886,866
Metallic fender and mud guard, W. C. Groehn	886,494
Metallic tie and rail fastener, L. McFarlane	886,841
Micrometer gage, C. A. Kelley	886,817
Millstone dressing machine, R. C. Helms	886,502
Mining dredge, T. P. Rochford	886,728
Mirror attachment for table implements, E. Walter	886,746
Mixer, See Concrete mixer	
Mixing machine, C. W. Upright	886,899
Molding machine, J. P. & J. F. J. Costigan	886,951
Motors, fuel sprayer for internal combustion, H. A. Johnston	886,513
Music sheets, machine for making perforated, P. L. Wood	886,455
Music turner and holder, automatic sheet, H. F. Shipley	886,425
Musical instruments, pedal mechanism for, A. F. Larson	886,377
Musical key instruments, playing attachment for, A. T. Chester	886,348
Nail, W. Horner	886,980
Nails, machine for making roofing, J. E. Dobson et al.	886,960
Necktie support, N. D. Nelson	886,399
Needle threader, A. P. Koon	886,376
Nut lock, J. W. Shawver	886,424

Dissect My Razor The "GILLETTE"



Observe its convenience—its perfection in every detail.

Figure out how much time and money you can save by adopting the "Gillette" habit.

You will then know why over two million men are proclaiming the superiority of the "Gillette."

BECAUSE it gives you a clean, comfortable, safe shave in three to five minutes—no matter how inexperienced you are.

BECAUSE the hardest beard, though on the tenderest skin, willingly yields to the soft, easy action of the keen "Gillette" blade.

No Stropping No Honing

BECAUSE the holder lasts a lifetime.

BECAUSE its blades are so inexpensive that when dull you throw them away as you would an old pen.

King Gillette

The Gillette Safety Razor Set consists of a triple silver-plated holder, 12 double-edged flexible blades—24 keen edges, packed in a velvet lined leather case, and the price is \$5.00.

Combination Sets from \$6.50 to \$50.00.

Ask your dealer for the "Gillette" to-day. If substitutes are offered, refuse them, and write us at once for our booklet and free trial offer.

GILLETTE SALES COMPANY

207 Times Bldg. New York 207 Kimball Bldg. BOSTON 207 Stock Exchange Bldg. Chicago



Mullins Steel Boats Can't Sink
—the fastest and safest boats built. Made of pressed steel plates, with air chambers in each end like a life boat, they are absolutely safe. Faster, lighter and more buoyant than wooden boats—practically indestructible—they don't leak, crack, dry out or wear out, and every boat is absolutely guaranteed. The ideal boats for pleasure, summer resorts, boat liversies, etc.
Send for catalog of Motor Boats—Marine Engines—Row Boats—Hunting and Fishing Boats.
THE W. H. MULLINS COMPANY, 118 Franklin St., Salem, Ohio.

Engineering News

(ILLUSTRATED)

214 Broadway, New York

The leading weekly Engineering paper of the world, devoted to the interests of Civil, Mechanical, Mining, and Electrical Engineers. 100 to 125 pages weekly. Send for free sample copy.


Simple Filtration Does Not Kill Typhoid Germs

Electrical Filtration Does!

As Proved by City Water Expert and Other
Prominent Authorities

Descriptive Booklet sent upon request

ELECTRIC WATER PURIFYING AND REFRIGERATING COMPANY
111 BROADWAY, NEW YORK CITY



Scientific American Index of Manufacturers


NEWLY REVISED EDITION of 1908
64 PAGES, 2500 ENTRIES, FREE

SOME ten years ago the publishers of the SCIENTIFIC AMERICAN issued an index of leading manufacturers. This book has proved so popular that the demand has warranted an entire new edition. This invaluable list tells where to buy almost any article, and buyers who fail to find the information they desire can have their wants specially looked up without charge, and if necessary we will advertise their wants in our inquiry column without expense. The first edition of this index is only 15,000 copies, so that early application is necessary.



MUNN & CO., Publishers Scientific American
Office 361 Broadway, New York

Proven Permanent Profits



The Original Vacuum Cleaning Machine

The above wagon will prove a mint to you. Making money at the rate of \$40.00 per day.

It cleans Residences, Stores, Hotels, Halls, Clubs, Theaters, Schools, without wear and tear on persons or places.

Reliable, durable and most efficient Portable Plant in the world. On a small investment you can realize \$3,000 to \$5,000 a year in Proven Permanent Profits.

Free bulletins and catalogues to all that are in earnest.


A full line of Stationary Vacuum Cleaning Plants are also made by us.

Send for illustrated booklets.

Gen'l Compressed Air & Vacuum Machinery Co.

4479 Olive Street, Dept. "D," ST. LOUIS, MO.

PERFECTION 1908 MARINE MOTORS



Simplest, swiftest, most efficient and best finished engine sold.

Our 3 1/2 H. P. is light enough for canoe or rowboat, and powerful enough for 22 foot launch.

2 1/2 H.P. \$55

Clean and easy to operate; starts with quarter-turn of fly-wheel; every part accessible; no vibration; almost noiseless. Built from finest material; the best finished engine sold. We guarantee satisfaction, or free replacement. 2, 2 1/2, 3, 5, 6 to 12 H. P. Write for Catalogue.

The Caille Perfection Motor Co., 1343 2d Ave., Detroit, Mich.



Roads are Smoothest with a MERKEL SPRING FRAME MOTORCYCLE

The 1908 MERKEL spins along with an easy spring that makes motorcycling a pleasure. The Spring Frame and extra long Wheel Base overcome jolts and jars; the Double Grip Control insures safety; and the Ball Bearing Motor, which may be had with Magneto Ignition, gives the greatest efficiency with the least cost.

Send for this: The Merkel Booklet tells the story of the Merkel's success—it is free.

MERKEL MOTOR CO.

1128 26th Ave., Milwaukee, Wis.

BARCAINS IN

AUTOMOBILES, NEW AND SECOND-HAND. Largest dealers in the world.

All makes, guaranteed, at saving of 30 to 75 per cent. Send for latest complete list of new and second-hand Autos, on hand. Big saving on tires, apparel and supplies. Send for our new catalogue No. 129, just issued, it will save you money.


TIMES SQUARE AUTOMOBILE CO. 1599 B'way, N. Y. City. 1332 Michigan Ave., Chicago, Ill.



A MOTOR-CYCLE OR LAUNCH at Small Cost

By using one of our Attachable outfits. Will fit any bicycle. A complete line of Finished Motors and Rough Castings from 1 1/2 to 10 H. P. for Bicycle, Auto, Marine or Stationary. Send stamps for catalogue.

STEEFFY MFG. CO., 2941 West Girard Ave., Phila., Pa.



Motors

for airships and other purposes where light and powerful engines are required. 1 to 40 H. P. Air Cooled. 50 & 100 H. P. Water Cooled.

Adopted by War Department. Send for catalogue B. G. H. CURTISS MANUFACTURING CO. Hammondsport, N. Y.




Little Giant GASOLINE MOTORS

Reliable, Reversible, Two Cycle. Two and Three Port. Guaranteed for one year. Simple and easy to operate. Our Free Catalogue A3 is worth your having.

Send 10 cents in stamps for our book entitled "Ignition, Vaporization, Installation and Operation of a Gasoline Motor."

UNITED MFG. CO., - - Detroit, Mich.

BETTER THAN BATTERIES




alone for sparking your auto, boat or gas engine is a set of storage batteries kept charged by our

Apple Battery Charger

a dynamo run by the flywheel of your engine that provides the best current for ignition purposes; always ready for any emergency. Eliminate ignition uncertainties by writing for our catalogue.

The Dayton Electrical Mfg. Co., 94 St. Clair St., Dayton, Ohio



Palmer Motors

Two and Four Cycle. One, Two and Four Cylinder. Stationary and Marine. One to Twenty H. P. Catalogue FREE.

PALMER BROS., Cos Cob, Conn.

New York: 30 East 30th Street

Philadelphia: The Bourse

Boston: 85 Union Street


Portland, Me.: Portland Pier

Seattle, Wash.: Colman Dock

Nut lock, R. H. Fisher	886,787
Oil burning plant, system of regulation for, Atchison & Weymouth	886,466
Oil treating apparatus, waste, P. E. Mook	886,718
Oils, apparatus for treating waste, H. E. Haller	886,696
Oiling device, valve, B. Alkman	886,461
Ophthalmoscope, H. L. De Zeug	887,032
Ordinance sighting apparatus, K. Voller	887,023
Ore crusher, C. O. Michaelsen	887,003
Ore previous to cyaniding or the like, means for treating crushed, H. L. Templer	886,892
Ores, balling together of pulverulent or dusty, H. Dicke	886,683
Overflow alarm, Andersen & Hansen	886,336
Package tie, W. E. Fricke	886,592
Package tie, P. L. Wilkerson	886,751
Packing case wall, G. F. Bishopric	886,926
Pants and drawers supporter, W. F. Craig	886,679
Paper board container, J. W. Low	886,710
Paper board, machine for making combination, O. H. Moore	887,007
Paper feed mechanism, F. L. Wood	886,454
Pattern, G. M. Laub	886,378
Peanut gleaner, H. L. Phippen	887,015
Penholder, W. A. Caldwell	886,346
Perambulator, V. Baup	886,922
Photographic and other purposes, manufacture of films for, J. H. Smith	886,883
Photographic film for daylight loading, G. Bianchi	886,673
Photographic objective, P. Rudolph	886,416
Photographic ray filter, P. J. Dukelow	886,684
Piano action, upright, M. Beckwith	886,341
Piano, autoneumatic music playing, F. C. White	886,908
Piano or organ players, governing mechanism for pneumatic, J. H. Chase	886,347
Picture and producing the same, multiple, G. Holmsten	886,606
Picture apparatus, life motion, J. Bianchi	886,674
Picture supporter, E. F. Bradt	886,935
Pictures, machine for making and displaying, W. N. Selig	886,654
Pigment, J. C. Heckman	887,042
Pin, F. J. Kristofek	887,043
Pipe nipple holder, J. Yule	886,571
Pistons, cushioning device for, O. S. Pike	886,402
Plaiting and braiding machines, switch for, B. Lepperhoff	886,825
Planing machine, J. R. Thomas	887,021
Planter, C. B. Rozliar	886,415
Planters, covering attachment for seed, E. Taylor	886,665
Plastering material, D. R. Jones	886,813
Plow, G. Ross	886,412
Plug driver, C. E. Glidden	886,364
Pocket safety attachment, H. Erickson	886,964
Powder can or box, sifter top, J. M. Hothersall	886,702
Powder distributor, C. D. Holt	886,979
Power motor, W. Snee	886,548
Power transmitting mechanism, R. H. Dunlap	886,778
Pressure controller, A. Michelin	886,834
Printing and other purposes, cylinder for, W. Love	886,998
Printing machine, two-color, T. Brock	886,936
Printing press, Harris & Smith	886,367
Printing, ruling, and like machines, feeding mechanism of, F. W. Vickery	886,901
Propeller, fish-tail, F. S. Merrow	886,389
Propulsion of vessels, G. Pertot	886,850
Protractor, J. A. Grenier	886,895
Pulley, W. Mayer	886,831
Pulverizer, Lewis & Stecher	887,047
Pump, H. G. Riebenack	886,893
Pump, J. W. Andersen	886,916
Pump, air, J. Darling	886,353
Pump, automatic hydraulic, L. A. Laursen	886,379
Pump, duplex air, J. Shourek	886,428
Pump for pumping liquids, steam, J. K. Sweeney	886,440
Pumping apparatus, wave power, F. E. Bosworth	886,931
Punching machine, W. T. Sears	886,876
Purse puzzle, T. P. Reid	886,540
Puzzle, D. D. Lowery	886,999
Rack, J. Boyle	886,933
Radiator, J. T. Stokes	886,550
Radiator attachment, J. M. Dungan	886,777
Rail, E. R. Robinson	886,541
Rail joint, J. C. Hafford	886,972
Railway, amusement, J. H. Dewey	886,958
Railway block signal, Coker & Scarbrough	886,947
Railway cattle guard, Brown & Shelbourne	886,937
Railway frog, G. H. Trisch	886,897
Railway gate, W. H. Kaur	886,816
Railway gate, electric, R. M. Moore	886,842
Railway rails, manufacture of, W. H. Connel	886,349
Railway road crossing, metal, R. Faries	886,487
Railway signal, automatic, J. P. Norwood	886,847
Railway signal, electric, A. Kuzel	886,993
Railway signaling apparatus, electric, P. J. Matter	886,620
Railway switch, automatic, I. A. Call	886,941
Railways, automatic electric signal system for, J. P. Buchanan	886,676
Rake, See Rotary rake	
Rake, W. C. Rarig	886,406
Rake, B. H. Ellis	886,689
Rake cleaner, J. E. Lucas	886,711
Ratchet wrench, socket, W. A. Burnop	886,476
Razor, M. Schutze	886,875
Reamer, C. L. Martin	886,830
Receptacle closure, F. Lalau	886,994
Receptacle closure, detachable, H. P. McMillan	886,397
Refrigerator overflow tanks, alarm device for, H. T. Dumas	886,776
Relay for signaling apparatus, L. H. Thullen	886,740
Retinoscope, ophthalmoscope, and the like, Inskeep & Gowll	886,512
Rock drill, hydrocarbon, J. V. Rice, Jr.	886,407
Rolls or drums, means for attaching flexible material to, T. H. Davies	886,582
Rotary engine, W. J. Chance	886,765
Rotary engine, T. Ashley	886,919
Rotary explosive engine, S. L. Robbins	886,641
Rotary rake, side delivery, J. Dain	886,681
Rotary screen, D. P. Findley	886,996
Sad iron, N. Streeter	886,728
Saddle, J. Wittner	886,670
Salt trough, A. R. Hoffmann	886,806
Sample holder, I. J. Kornik	886,521
Sander, automatic, Williams & Isaacs	886,910
Sap collector, J. F. O'Connor	887,012
Sash weight, F. C. Schwedtmann	886,653
Saw gage and jointer, Wheelock & Pence	886,450
Scale, computing, J. J. Duffie	886,775
Score board, J. M. Hamilton	886,697
Sealing cap, bottle, Betts & Vandenberg	886,925
Seaming and corrugating pipes, machine for, J. J. Meggy	886,975
Section press and foundation setting mechanism, C. E. Cox	886,581
Self closing lock, A. Nathan	886,533
Sewer trap, F. A. Radcliffe	886,405
Sewing machine angle sewing attachment, W. Wilson	886,568
Sewing machine binding attachment, W. Wilson	886,567
Sewing machine, button, B. T. Leveque	886,826
Sewing machine shuttle, C. F. & M. T. Goforth	887,069
Sewing machine take-up, W. M. Ammerman	886,574
Shade fixture, window, A. L. Crim	886,953
Shade roller, E. E. Palmer	886,409
Shaft bending machine, P. P. Dyke	886,359
Shifting device, E. C. Smith	886,431
Shingle for roofs and gable ends of houses, composition, Young & Burruss	886,912
Shipping and display box, F. G. Merritt	886,388
Shirt, G. G. Rockwood	886,410
Shirt holder, laundried, N. J. Goodman	886,795
Shock absorber, G. L. Harvey	886,501
Shoe, P. G. Mayhew	886,716
Shoe, J. M. Quinn	886,860
Shoe fastening, W. A. Dunstan	886,779
Shoe finishing machine, J. S. Hansen	886,604
Shutter operator, R. C. Spencer, Jr.	886,658
Sifter, ash, G. W. Child	887,031
Sifter top can or box, sheet metal, J. M. Hothersall	886,509
Sight feed lubricator, F. W. Edwards	887,036
Signaling system, J. Shepherd	886,879

BIGGEST ENGINE BARGAIN

See Who Offers Them, Then Consider the Prices



Here is the biggest real bargain in Gasoline Marine Engines you ever saw. A new Three-Horse-Power Engine for \$44! Or a new Six-Horse-Power Engine for \$80! Only a limited number. The stock won't last long at these prices. It's the chance of a lifetime. Write to-day for full information.

The Special Reasons for These Low Prices

A little over a year ago The Ferro Machine & Foundry Company purchased the entire interests of the Detroit Auto Marine Co. The Ferro Machine & Foundry Company immediately utilized their entire manufacturing facilities for turning out FERRO Motors, and the result was that a quantity of partially finished Detroit Auto Marine parts were left on hand.

These parts were principally of the three and six-horse-power sizes. As these parts of Detroit Auto Marine Motors were of no use to the Ferro Machine & Foundry Company nor to anyone else in this partially completed state, it was recently decided to finish and assemble these parts and place these three-horse-power and six-horse-power engines thus built on the market at less than cost, so as to clear up this extra stock at once.

These parts were crank shafts, connecting rods, carburetors, commutators, and the balance of the motors, including all castings, have been just recently manufactured. They are made of the best material throughout and finished perfectly. It's the biggest bargain ever offered to the boat builder or the boat owner who wants to put an engine in his boat or replace his old engine.

Read What Users Say

Detroit Auto Marine Co.—Your engines are the talk of the town. They run so steadily and propel the boats so fast. I have 4 boats to put engines into. I will have 10 or 15 more sold before the coming season.

C. H. SABIN, St. Albans, Vt.

Detroit Auto Marine Engine Co.—After a run of over 800 miles (60 miles on ocean) with 3 h. p. engine in my 30-ft. house boat, at an average of 4 1/2 miles per hour, I want to say the little "Auto Marine" is as good and reliable as ever built at any price.


W. M. SMITH, Miami, Fla.

Remember, these engines are tested at the factory to develop their full rated horse-power. We will always have all parts on hand for repairs.

We will furnish you with price list so you can get any part of these engines any time promptly and at low price direct from our factory.

Write today—NOW—and we will send you full illustration and description of these engines and the various outfits that go with them.

The Ferro Machine & Foundry Company, Cleveland, O. Eastern Branch: Dept. 1, 44 Cortlandt St. 2d Fl., New York



\$200.00 in Six Months from 20 Hens

TO the average poultryman that would seem impossible, and when we tell you that we have actually done a \$500.00 Poultry business with 20 hens on a corner in the city garden 30 feet wide by 40 feet long we are simply stating facts. It would not be possible to get such returns by any one of the systems of poultry keeping recommended and practiced by the American people, still it is an easy matter when the new PHILO SYSTEM is adopted.

The Philo System Is Unlike All Other Ways of Keeping Poultry.

and in many respects is just the reverse, accomplishing things in poultry work that have always been considered impossible, and getting unheard of results that are hard to believe without seeing; however, the facts remain the same and we can prove to you every word of the above statement.

The New System Covers All Branches of the Work Necessary for Success.

from selecting the breeders to marketing the product. It tells how to get eggs that will hatch, how to hatch nearly every egg and how to raise nearly all the chicks hatched. It gives complete plans in detail how to make everything necessary to run the business and at less than half the cost required to handle the poultry business in any other manner. There is nothing complicated about the work, and any man or woman that can handle a saw and hammer can do the work.

Two Pound Broilers in Eight Weeks

are raised in a space of less than a square foot to the broiler without any loss and the broilers are of the very best quality, bringing here, three cents per pound above the highest market price.

Our Six Months Old Pullets are Laying at the Rate of 24 Eggs Each per Month

in a space of two square feet for each bird. No green cut bone of any description is fed, and the food used is inexpensive as compared with food others are using.

Our new book, the Philo System of Progressive Poultry Keeping, gives full particulars regarding these wonderful discoveries with simple, easy to understand directions that are right to the point, and 15 pages of illustrations showing all branches of the work from start to finish.

Don't Let the Chicks Die in the Shell.

One of our secrets of success is to save all the chicks that are fully developed at hatching time, whether they can crack the shell or not. It is a simple trick and believed to be the secret of the Ancient Egyptians and Chinese which enabled them to sell the chicks at 10 cents a dozen.

Chicken Feed at 15 Cents a Bushel.

Our book tells how to make the best green food with but little trouble and have a good supply any day in the year, winter or summer. It is just as impossible to get a large egg yield without green food as it is to keep a cow without hay or fodder.

Our New Brooder Saves Two Cents on Each Chicken.

No lamp required. No danger of chilling, overheating or burning of the chickens as with brooders using lamps or any kind of fire. They also keep all lice off the chickens automatically or kill any that may be on when placed in the brooder. Our book gives full plans and the right to make and use them. One can be easily made in an hour at a cost of 25 to 50 cents.

A FEW TESTIMONIALS.

Your system of poultry keeping should appeal to all poultrymen. The advantages of your system are many, and the quality of the large flock of poultry you have raised on your city lot is the best evidence of its success.

Geo. L. Harding, Binghamton, N. Y.

Valley Falls, N. Y., Sept. 5, 1907. It was my privilege to spend a week in Elmira during August, during which time I saw the practical working of the Philo System of Poultry Keeping, and was surprised at the results accomplished in a small corner of a city yard. "Seeing is believing," they say, and if I had not seen it, it would have been hard to believe that such results could have followed so small an outlay of space, time and money.

(Rev.) W. W. Cox.

Windsor, Vt. March 8, 1908. I consider the one dollar I invested in the Philo System, Poultry Review and American Poultry Advocate the best investment for the money I ever made.

Robert L. Patrick.

Jacobs Creek, Pa. I received the Philo System Book mailed to my home address, Beechtree, Pa. I am highly pleased with it, and am anxious to spread the good news as far as I can. I am a preacher of the gospel engaged by the Baptist Association to do Evangelistic work. I am on the road all the time, have about 14 days in each town. I am very much interested in the book and will do all I can to help the other fellow to know how, and to spread the good tidings received in the Philo System.

(Rev.) F. B. Williams.

SPECIAL INTRODUCTION OFFER

By special arrangement we are able to give for only \$1.00 the book, with the right to use all plans.

One year's subscription to Poultry Review. A monthly paper for utility breeders. One year's subscription to the American Poultry Advocate.

Upon receipt of \$1.00 you will get the book by return mail and your subscriptions will start at once.

Copy of the Philo System book and a year's subscription to Poultry Review and the American Poultry Advocate, all for \$1.

AMERICAN POULTRY ADVOCATE, 306 Hogan Block, SYRACUSE, N. Y.

Classified Advertisements

Advertising in this column is 75 cents a line. No less than four nor more than ten lines accepted. Count seven words to the line. All orders must be accompanied by a remittance. Further information sent on request.

READ THIS COLUMN CAREFULLY.—You will find inquiries for certain classes of articles numbered in consecutive order. If you manufacture these goods write us at once and we will send you the name and address of the party desiring the information. There is no charge for this service. In every case it is necessary to give the number of the inquiry. Where manufacturers do not respond promptly the inquiry may be repeated.

MUNN & CO.

BUSINESS OPPORTUNITIES.

VENDING MACHINES FOR GUM AND SWEETS. Send for descriptive circular. Foreign rights for sale. For full particulars address S-D Machine Company 463 Greenwich Street, New York City.

Inquiry No. 8594.—Wanted spring suitable for spring motor.

WANTED.—Useful Novelties, practical tools, labor saving devices for use in shipping and packing departments. Any good articles which will facilitate shipping, packing or branding goods. Address B. & S. Co., Box 173, New York City.

Inquiry No. 8596.—Wanted to buy printed pillow tops for sofa pillows.

MACHINES TO FEED PAPER to ruling, folding, etc., machines. Cheapest and best. New patent. Limited territory. Sale or license to right party. Zimmerman, 1000 Tribune Bldg., Chicago.

Inquiry No. 8597.—Wanted to buy an alcohol furnace to heat a hot water system.

WE HAVE A LARGE FACTORY and are looking for something to manufacture. Prefer to buy an established business at a reasonable price. Louis Rastetter & Sons, Fort Wayne, Ind.

Inquiry No. 8598.—Wanted to buy waterturbines.

HELP WANTED.

POSITIONS OPEN.—Salaries \$600 to \$5,000. Write today for "Brain Brokers" telling how we have placed 5,000 men. For full particulars address Hapgood, 363 Broadway, New York.

Inquiry No. 8599.—Wanted to buy a 13-inch copier cylinder head.

BOOKS AND MAGAZINES.

WIRELESS TELEGRAPHY.—Send 10 cents for special number of *Electrician and Mechanic*, devoted to this subject. Articles on how to make a 4-inch induction coil, magnetic detector, independent interrupter, indoor wireless, adjustment of detectors on tuned circuits, wireless telephony, storage batteries. Also hall seat, 16-foot launch, model engine, telephone installation, mechanical drawing, etc. List of electrical and mechanical books free. Sampson Publishing Company, 1151 Beacon Building, Boston, Mass.

Inquiry No. 8601.—Wanted an incandescent lamp burner for kerosene lamps.

GRE-SOLVENT.

GRE-SOLVENT instantly dissolves Machine-grease, Paint, Ink, from hands. Beneficial to skin. Sells like wildfire to every mechanic. Agents wanted. Big profits. Free sample. Do it now. Utility Co., 646 W. 44th St., N. Y. City.

Inquiry No. 8602.—Wanted to buy machinery and materials for incandescent gas mantle manufacture.

HOUSEHOLD NEEDS.

BUTCHER'S BOSTON POLISH is the best finish made for floors and interior woodwork. Not brittle; will not scratch or deface like shellac or varnish. Send for free booklet. For sale by dealers in Paints, Hardware and House Furnishings. The Butcher Polish Co., 356 Atlantic Avenue, Boston, Mass.

Inquiry No. 8606.—Wanted to buy a cutting and winding machine for narrow fabric bias binding.

DEAFNESS.

TO THOSE HARD OF HEARING.—An efficient aid sent for trial, no expense, no risk, no contract, no money unless device be kept. For full particulars address A. O. Tiemann & Company, 107 Park Row, New York.

Inquiry No. 8607.—Wanted to buy an electric incubator.

BUNGALOWS.

THE MAY NUMBER of *American Homes and Gardens* contains photographs and plans of big and little, costly and inexpensive bungalows, as well as articles on the furnishing of bungalows. Double number. Price, 50 cents. Order from your newsdealer or from Munn & Co., 361 Broadway, New York City.

Inquiry No. 8608.—Wanted to buy Broom machinery, Broom corn, Broom handles.

Inquiry No. 8610.—Wanted addresses of manufacturers of collapsible tube machinery.

Inquiry No. 8611.—Wanted to buy springs for light power purposes.

Inquiry No. 8612.—Wanted to secure locomotives propelled by vapor engines.

Inquiry No. 8613.—Wanted to buy smoke consumers for house heaters.

Inquiry No. 8614.—Wanted to buy pearl button machinery.

Inquiry No. 8615.—Wanted to buy a machine for breaking the hull of the almond nut without breaking the fruit.

Inquiry No. 8616.—Wanted to buy for export to Porto Rico perforated metal shelving.

Inquiry No. 8617.—Wanted to buy for export to Porto Rico complete baking plant for 1,000 loaves daily.

Inquiry No. 8618.—Wanted to buy for export to Porto Rico refrigerating machine, cooling rooms, 10x12, 1x16, bar cooling box. Wanted complete with motor.

Inquiry No. 8620.—Wanted to buy aluminum cans.

Inquiry No. 8621.—Wanted to purchase coal briquetting machinery.

Inquiry No. 8622.—Wanted to buy automobile engines and supplies.

Inquiry No. 8623.—Wanted to buy electric cooking stoves with battery attached.

Inquiry No. 8624.—Wanted to buy portable rivet heaters.

Inquiry No. 8625.—Wanted to buy small sized channel iron, also leaf springs for experimental work.

Inquiry No. 8626.—Wanted to buy lacquered and plain sheet steel for sign making, also paraffining outfit for signs, presses for wood signs and sheet rubber.

Inquiry No. 8627.—Wanted to buy an alternating current generator of 2 K. W. capacity, or smaller.

Inquiry No. 8628.—Wanted to buy paving block machines for use with partly fluid substances.

Inquiry No. 8629.—Wanted to buy rubber specialties and coiled brass springs.

Inquiry No. 8630.—Wanted addresses of leading novelty manufacturers.

Inquiry No. 8631.—Wanted to buy fruit evaporators.

Inquiry No. 8632.—Wanted to buy machine for perforating music rolls.

Inquiry No. 8633.—Wanted to buy show cases.

Inquiry No. 8634.—Wanted to buy brass, bronze and china novelties.

Inquiry No. 8635.—Wanted to buy mica chimneys and smoke tops.

Inquiry No. 8636.—Wanted to buy household brushes.

Inquiry No. 8637.—Wanted to buy lawn mower grinders.

Inquiry No. 8638.—Wanted to purchase mica or porcelain insulation.

Inquiry No. 8639.—Wants stencils for decorative borders such as are used around half tones.

Inquiry No. 8640.—Wanted to buy alcohol lamps for lighting purposes.

Inquiry No. 8641.—Wanted to buy a self-lighting gas burner.

Inquiry No. 8642.—Wanted to buy a gasoline motor inspection car standard gage.

Inquiry No. 8643.—Wanted to buy concrete post machines.

Inquiry No. 8644.—Wanted address of glass tube manufacturer who does bending.

Inquiry No. 8645.—Wanted to buy parts for curling irons.

Inquiry No. 8646.—Wanted to buy cheap small motor from 1/4 to 1 horse power, single phase 60 cycle, 110 volts.

Inquiry No. 8647.—Wanted to buy steel hat pins 8 inches pointed at both ends.

Inquiry No. 8648.—Wanted to buy small steam saw mill using lumber waste for fuel. Western manufacturer preferred to save freight.

Inquiry No. 8649.—Wanted to buy non-inflammable celluloid.

Inquiry No. 8650.—Wanted to buy file cutting machinery.

Inquiry No. 8651.—Wanted to buy apparatus for making gas from oil.

Inquiry No. 8652.—Wanted address of manufacturers of drop forged wrenches.

Inquiry No. 8653.—Wanted addresses of dealers in sheet steel, New York City preferred.

Inquiry No. 8654.—Wanted addresses of case-hardeners in New York.

Inquiry No. 8655.—Wanted to buy leather for motor cycle mud guards.

Inquiry No. 8656.—Wanted to buy parts of models and gear wheels.

Inquiry No. 8657.—Wanted to buy a small water motor.

Inquiry No. 8658.—Wanted to buy cooking stoves and lamps using denatured alcohol as fuel.

Inquiry No. 8659.—Wanted to buy ground corn cobs in large quantities.

Inquiry No. 8660.—Wanted to buy creosote making machinery.

Inquiry No. 8661.—Wanted to buy machinery for making cutlery.

Inquiry No. 8662.—Wanted to buy small machine for drawing thread from cotton and machine for making lozenges.

Inquiry No. 8663.—Wanted to buy file cutting machines.

Inquiry No. 8664.—Wanted to buy game boards.

Inquiry No. 8665.—Wanted to buy comb making machinery.

Inquiry No. 8666.—Wanted to buy screw making machinery.

Inquiry No. 8667.—Wanted to buy needle, pin and pen machinery.

Inquiry No. 8668.—Wanted to buy water power washing machine.

Inquiry No. 8669.—Wanted to buy machinery for making rifle barrels.

Inquiry No. 8670.—Wanted to buy a low-cost or second-hand lathe to be operated by foot power.

Inquiry No. 8671.—Wanted to buy welding and machinery for making same.

Inquiry No. 8672.—Wanted to buy 2,500-pound gasoline traveling crane.

Inquiry No. 8673.—Wanted to buy folding umbrellas.

Inquiry No. 8674.—Wanted to buy machinery for cultivating rice and making Yuca starch.

Inquiry No. 8675.—Wanted to buy machinery for making sawdust into bricks for fuel.

Inquiry No. 8676.—Wanted to buy flat irons heated by denatured alcohol.

Inquiry No. 8677.—Wanted to buy model safety razors.

Inquiry No. 8678.—Wanted to buy cheap sewing machines.

Inquiry No. 8679.—Wanted to buy cheap guns.

Inquiry No. 8680.—Wanted to buy cheap watches.

Inquiry No. 8681.—Wanted to buy envelope making machines.

How to Build a 5 H.P. Gas Engine at Home

In SCIENTIFIC AMERICAN SUPPLEMENTS 1641 and 1642, E. F. Lake describes simply and thoroughly how a five horse power gas engine can be built at home. Complete working drawings are published, with exact dimensions of each part. Price by mail for the two Supplements, 20 cents. Order from your newsdealer or from

MUNN & COMPANY
Publishers
361 Broadway, New York

Silicon dioxide, making, H. N. Potter.....	886,637
Silicon monoxide, making, H. N. Potter.....	886,636
Sleigh runner, detachable, B. White.....	886,563
Slimes treatment, C. E. D. Usher.....	886,900
Smoke and soot arrester for stacks, J. F. Miles.....	887,004
Snag fastener, G. A. Holmes.....	886,808
Soap anchor, G. W. Gaines.....	886,791
Sod cutting and removing device, J. A. Musgrove, Jr.....	887,009
Soda fountain, H. K. Smith.....	886,881
Sodium formaldehyde sulfoxylate, Seifert & Meves.....	887,050
Soldering machine, can-vent, C. A. Crandall.....	886,767
Sole, cushion shoe, E. E. Harmon.....	886,801
Speculum, mouth, N. W. Kyle.....	886,522
Spindle, C. S. Foster.....	886,789
Spoke socket, N. W. May.....	886,715
Spring bridge, G. A. Bader.....	886,467
Sprocket, friction, E. F. Hafelfinger.....	886,601
Square, bevel, M. Renner.....	886,639
Square, attaching means for, J. A. Toomey.....	886,894
Stamp, ore, W. B. Easton.....	886,686
Stand, See Display stand.....	
Steam generator junction box, J. C. Parker.....	886,631
Steering gear, A. P. Brush.....	886,938
Stenciling machine, E. F. Kunath.....	886,902
Stirrup, W. D. Miller.....	887,005
Stitching machines, thread laying device for book, F. Kugler.....	886,820
Stove and furnace, W. R. Penery.....	886,965
Stovepipe, extension, H. K. Hansen.....	886,366
Street sweeper, C. O. Smith.....	886,430
Street sweeper, E. E. Hall.....	887,040
Sulfur burner, J. F. Conrad.....	886,948
Sulkies and gang plows, attachment for, J. T. Toland.....	886,895
Swing, W. T. Green.....	886,799
Swing, M. Hathaway.....	886,974
Swing, lawn, W. S. Tohill.....	886,444
Syrup dispensing apparatus, McCloskey & Gray.....	886,720
Table top, removable, N. C. Merrill.....	886,623
Target trap, H. E. Winans.....	886,669
Telegraph, duplex, J. J. Ghegan.....	887,038
Telegraph instrument, Bellows & Behner.....	886,755
Telegraph, printing, J. C. Barclay.....	886,338
Telegraph transmitter, automobile, J. C. Barclay.....	886,339
Telephone local toll or pay stations, system and apparatus for, J. Harrison.....	886,497
Telephone selector and lock-out, party line, H. D. Williams.....	886,909
Telephone service, system for measured, J. Harrison.....	886,498
Telephone toll box, J. Harrison.....	886,499
Telescope, E. Neumayer.....	886,722
Telescope, binocular, R. Straubel.....	886,435
Telescope, double, Straubel & Heckel.....	886,436
Telescope, sighting, M. da S. Netto.....	886,628
Telescope, sighting, F. Schleth.....	886,647
Tent, F. W. Burch.....	887,029
Thill coupling, C. C. Bradley.....	886,578
Thread guide mechanism, J. E. Prest.....	886,638
Threshing machine, F. F. Landis.....	886,707
Threshing machine, J. Sanders.....	886,872
Threshing machine, Anderson & Quessnell.....	887,024
Ticket issuing and recording machine, H. Tyler.....	886,743
Ticket separating and counting machine, W. A. Gibbs.....	886,793
Time indicating device, C. E. Getz.....	886,603
Time recorder, workman's, W. A. Wood.....	886,456
Tires, means for attaching pneumatic, A. C. Miller.....	886,835
Tongs, crushing, M. B. Pickett.....	886,401
Tool, combination, J. M. Kiehle.....	886,987
Tool, electric driven, A. F. Carver.....	886,678
Tool operating machine, G. P. Thomas.....	886,551
Top holder, M. Glascock.....	886,595
Towel rack and holder, combined, O. E. Myers.....	886,534
Toy, W. Hizer.....	886,505
Traction wheel, motor vehicle, C. H. Schmidt.....	886,873
Train controller, automatic, G. Toft.....	886,741
Transporting system, H. G. Brown.....	886,472
Transmission mechanism, L. E. Mahout.....	887,001
Tray or truck, portable, A. C. McNeiven.....	886,537
Trench brace, De France & Read.....	886,956
Trolley, J. Shepherd.....	886,880
Trolley guard, J. E. Saucier.....	886,645
Trolley harp, H. W. Kimes.....	886,517
Trolley line clamp, A. Caron.....	886,942
Trousers holder, E. Rohde.....	886,442
Truck, log, J. W. Germany.....	886,493
Truss, J. Habenicht.....	886,509
Tubes, automatic shut off for pneumatic, E. Flint.....	886,489
Turbine, A. Jude.....	886,515
Twine or cord hanger, H. Allers.....	886,915
Twisting machine, P. Hardman.....	886,698
Typesetting and line casting machines, spacer for, H. Degener.....	886,583
Typewriter ribbon attachment, C. A. Joerissen.....	886,609
Typewriters and the like, copy holder for, W. L. Wood.....	886,457
Typewriting machine, C. A. Morey.....	886,392
Typewriting machine, F. Volker.....	886,557
Typewriting machine, F. A. Young.....	886,570
Typewriting machine, B. C. Stickney.....	886,660
Typewriting machine, A. T. Brown.....	886,759
Typewriting machine line spacer, J. S. Southerden.....	886,432
Umbrella, T. A. Stombaugh.....	886,890
Umbrella, folding, G. C. Shivers.....	886,426
Umbrella, folding, N. Spanick.....	886,885
Unloading and transferring apparatus, G. M. Bennett.....	886,468
Valve, W. Plate.....	886,633
Valve actuating mechanism, W. D. Sweetman.....	886,663
Valve, combined wet and dry pipe, A. S. Nicol.....	886,629
Valve for air brakes, quick action triple, W. T. Richards.....	886,409
Valve for steam boilers, safety, E. J. Clarke.....	886,945
Valve, hydraulic, C. E. Gillette.....	886,946
Valve lifter, Rohen & Porton.....	886,868
Valve, puppet, J. H. Dickinson.....	886,357
Valve, relief, J. L. Doherty.....	887,033
Vault lock, grave, Myers & Tuttle.....	886,396
Vehicle brake, D. T. Lohmes.....	886,828
Vehicle, canopy top, J. H. Sprague.....	886,659
Vehicle, motor, W. L. Marr.....	886,528
Vehicle shock absorbing apparatus, R. M. Lovejoy.....	886,617
Vehicle shock weakening device, H. Sans.....	886,643
Vehicle spring, F. R. Skidmore.....	886,429
Vehicle spring, A. Fortner.....	886,967
Ventilator, See Window ventilator.....	
Ventilator, G. Kabureck.....	886,610
Vessel, transport, O. Mehrens.....	886,621
Veterinary obstetrical instrument, C. Gabel.....	886,363
Veterinary operating table, I. L. Smith.....	886,656
Veterinary remedy, C. A. Coe, Jr.....	886,946
Vibrator, E. M. Tormin.....	886,443
Wagon dumps, automatic controller for, L. J. McMillin.....	886,536
Wagon or truck, A. Smith.....	886,734
Wall register, C. J. Andrae.....	886,463
Wall tie, Schirra & Weber.....	887,018
Walls, manufacture of intermediate, H. Hansen.....	887,041
Washboard, G. B. Lutoms.....	886,829
Washing machine, C. Vieman.....	886,745
Washing machine, A. T. Newman.....	886,845
Washing machine gearing, A. F. Victor.....	887,022
Watch barrel, W. B. Mehl.....	886,387
Water governor, centrifugal, W. L. Waters.....	886,500
Water motor, R. D. Tittle.....	886,442
Water tank, cement, J. J. Daniel.....	886,481
Weather strip, A. S. Aiman.....	886,573
Weather strip, A. R. Thomas.....	886,893
Weather and cultivator, O. J. Gonzalez.....	886,970
Well drill, H. B. King.....	886,704
Well pulling machine, Kraft & Feter.....	886,989
Wheel flange pressures, apparatus for testing, G. L. Fowler.....	886,691
Wind strip, J. S. Sewell.....	886,878
Winding machines, manufacture of paper cones for yarn, W. F. Smith.....	886,884
Window, M. Levin.....	887,046
Window lock, W. E. Poulson.....	886,853
Window operating mechanism, C. P. Pond.....	886,851
Window rest and escape ladder, combined, J. J. Hersche.....	886,605

Needraw
BOSTON GARTER
DESIGNED TO BE WORN WITH KNEE DRAWERS
NON-ELASTIC TUBULAR KNIT LEG BAND
ELASTIC ADJUSTABLE PENDANT
NO METAL TOUCHES THE LEG
Made with the Celebrated **Velvet Grip**
CUSHION RUBBER BUTTON CLASP
Of your haberdasher or sample pair on receipt of 25c.
GEO. FROST CO.
Sole Makers, Boston
GOOD ALL THE YEAR ROUND

KEROSENE MARINE MOTORS

This motor uses kerosene, vaporizing it by an entirely new method from heat of exhaust pipe, and does not draw charge into base of engine. Uses 20 per cent. Less Fuel than on Gasoline, and gives 10 per cent. More Power. Uses regular jump spark ignition. Write for catalog. A motor that will save you money. Specially adapted to work boats. Un



BUILD YOUR OWN BOAT

BY THE BROOKS SYSTEM

I can sell you a boat for one-fourth of what a factory would charge. 100 cents of actual value and results for 25 cents. Is it worth considering? Anyone can build a boat by using my exact size printed paper patterns and illustrated instruction sheets. My boat catalogue shows all kinds of boats. Send for it—right now, today. It's free. Patterns from \$1.50 up.


KNOCK-DOWN BOAT FRAMES



A Set-up Frame

I can in many cases supply knock-down frames all ready to put together at a lower price than you would pay for suitable raw material. Every piece is accurately shaped and machined ready to put together. All patterns and illustrated instructions needed to finish the boat—sent free with knock-down frames.

TWO SPECIAL OFFERS



Length 22 ft. Beam 56 in. K. D. frame and patterns \$24.00. Brooks 6 H. P. Type D motor, complete equipment \$95.00. Both the above \$108. Complete boat with 6 H. P. motor, ready to run, as illustrated \$230.

BROOKS SPECIAL TYPE E 3 H. P. MOTOR

Complete with Electrical and Marine Equipment.

Write me personally for my boat or engine catalogue. C. C. BROOKS, President. BROOKS BOAT MFG. CO. (Originators of the pattern system of boat building.) 405 Ship Street, Saginaw, Mich., U. S. A.



AUTOMOBILISTS

and men in all walks of life should know the merits of LITHOLIN WATERPROOFED LINEN COLLARS and CUFFS

No matter how soiled, they are cleaned instantly with a damp cloth, and made white as new. Absolutely waterproof, they hold their shape under all conditions. Being linen they look like the real thing. Wear indefinitely, and don't wilt, fray or crack. Every fashionable style in all sizes.

Collars 25c. Cuffs 50c.

If not at your dealer's, send, giving styles, size, number wanted, with remittance, and we will mail, postpaid. Booklet of styles free on request. THE FIBERLOID CO., Dept. 22, 7 Waverly Place, N.Y.



GAS ENGINE DETAILS.—A VALUABLE and fully illustrated article on this subject is contained in SUPPLEMENT No. 1292. Price 10 cents. For sale by Munn & Co. and all newsdealers.




Paint or White-Wash Your Buildings

Save two-thirds the labor cost. This Auto-Spray will do it better and quicker than 5 men with brushes. Capacity 8 gals. Easily carried from place to place. Sprays reaches all crevices—brushes do not. The AUTO-SPRAY MACHINE

Sprays Trees, Vegetables, etc., as well as it handles white-wash and cold-water paint. Pressure enough for tallest trees, suitable for all purposes. Low in price, satisfaction guaranteed. We make all styles and sizes of sprayers. Write today for particulars. THE E. C. BROWN CO., 23 Jay St., Rochester, N.Y.

THE EUREKA CLIP

The most useful article ever invented for the purpose. Indispensable to Lawyers, Editors, Students, Bankers, Insurance Companies and business men generally. Book marker and paper clip. Does not mutilate the paper. Can be used repeatedly. In boxes of 100 for 25c. To be had of all booksellers, stationers and notion dealers, or by mail on receipt of price. Sample card, by mail, free. Manufactured by consolidated Safety Pin Co., Box 121, Bloomfield, N. J.



Window ventilator, J. L. Mallory.....	886,714
Wire stretcher, C. C. Atkinson.....	886,920
Wire tie, H. A. Drew.....	886,775
Wrench, H. A. Sturges.....	886,437
Wrench, J. E. Wakefield.....	886,448
Wrench, H. C. Moore.....	887,006
Writing machine, W. A. Schmidt.....	886,418

DESIGNS.

Bottle, F. U. Bowers.....	39,292
Collar, shirt, D. R. Griffith.....	39,298
Jar, D. R. Brown.....	39,291
Oil cloth, A. Hunsicker.....	39,296
Paper, decorative, C. L. Mead.....	39,295
Shade or globe for artificial lights, G. F. Weber.....	39,293, 39,294

TRADE MARKS.

Alcohol burners, Thos. W. Houchin Co.....	68,937
Alcohol, denatured, G. L. Marion Mfg. Co.....	68,897
Ale, beer, half-and-half, porter, etc., West End Brewing Co.....	68,880
Baking powder, J. C. Grant Chemical Co.....	68,908
Bareges, E. L. Waldo.....	68,895
Beer, Bienville Brewery.....	68,899
Bottles, heat and cold insulated, J. G. Lyman.....	68,930
Brushes, paint, C. W. Snow & Co.....	68,891
Candies, Stern & Saalberg Co.....	68,878
Canned fish and oysters, J. Oppenheimer & Co.....	68,883
Canned salmon, Griffith-Durney Co.....	68,871, 68,872
Canned vegetables, W. W. Boyer & Co.....	68,921
Chemicals, certain, New York Quinine & Chemical Works.....	68,898
Chocolate, Suchard Societe Anonyme.....	68,884
Cigars, Rodriguez y Hno.....	68,865
Cigars, S. S. Pierce Co.....	68,866
Cigars, J. W. Roberts & Son.....	68,877
Clocks, Seth Thomas Clock Co.....	68,894
Coffee and tea, Ridenour-Baker Grocery Co.....	68,876
Conductors, armored, Sprague Electric Co.....	68,936
Current transformers, alternating, General Electric Co.....	68,926
Cutlery and tools, certain, Whiton Hardware Co.....	68,868
Dyes, Rainbow Dye Co.....	68,901
Edge tools, certain, Stanley Rule & Level Co.....	68,897
Felt roofing, Buck Roofing Co.....	68,890
Flour, wheat, Duluth-Superior Milling Co.....	68,915
Flour, wheat, Higginsville Milling Co.....	68,916
Flour, wheat, J. O. Norris.....	68,917
Flour, wheat, W. H. Stokes Milling Co.....	68,919
Foods, certain, Holbrook Limited.....	68,928
Furniture polish, Standard Furniture Co.....	68,914
Fuses and blasting caps, Ladin & Rand Powder Co.....	68,892
Gloves, leather, Strawbridge & Clothier.....	68,879
Hair tonic, F. J. Pieper.....	68,900
Hair tonic, toilet water and cream, Oza Co.....	68,911
Hammocks, I. E. Palmer Co.....	68,861
Hardware, certain, Covert Manufacturing Co.....	68,857, 68,858
Harness, certain, Covert Manufacturing Co.....	68,922, 68,924
Harness, saddles, collars, whips and lap robes, Harris Saddlery Company.....	68,927
Hat trimmings, certain, Aitken, Son & Co.....	68,854
Heating apparatus, certain, Reliance Heater & Supply Co.....	68,932
Ice cream cones and popcorn, E. E. McCoy.....	68,882
Insulating composition, C. V. Frye.....	68,939
Jewelry and precious metal ware, certain, A. L. Bailhache.....	68,856
Laboratory apparatus, certain, J. P. Remington, Jr.....	68,933
Magazine or periodical, S. J. Hopper.....	68,929
Medicinal preparations, certain, W. H. Gale.....	68,906
Medicinal roots, barks, herbs, gums, etc., J. L. Hopkins & Co.....	68,910
Medicines, certain, F. A. Richter.....	68,934, 68,935
Milk, Marshall Milk Condensing Co.....	68,875
Milk flour and desiccated milk, Standard Milk Flour Co.....	68,918
Oil, lubricating, Galena-Signal Oil Co.....	68,859, 68,870
Paper, crape, Dennison Manufacturing Co.....	68,912
Perfumes and perfumed toilet powders, E. Palmer.....	68,912, 68,913
Planters, attachments therefor, etc., potato, Potato Implement Co.....	68,931
Remedies, certain, H. M. O'Neil.....	68,899
Remedies for kidney, bladder and liver troubles, E. C. De Witt & Co.....	68,905
Remedies for seasickness, M. Heim.....	68,907
Remedy, certain, L. S. Sorber.....	68,902
Remedy for scalp diseases, J. W. Black.....	68,896
Screw and slotting machines, National Acme Mfg. Co.....	68,864
Silk piece goods, J. Kridel Sons & Co.....	68,873
Soap, J. Biechele.....	68,903
Soap, medicated, J. Biechele.....	68,904
Soda, bicarbonate of, J. C. Grant Chemical Co.....	68,909
Stoves, ranges, furnaces, and radiators, Union Stove Works.....	68,938
Tarts, I. Weltman.....	68,920
Tea, Tangs Lashley Co.....	68,887
Thread, spool and sewing cotton, American Thread Co.....	68,855
Tomato and beef extract, A. H. Landsberger.....	68,874
Tops, Milton Bradley Co.....	68,863
Trousers, Washington Woolen Mills.....	68,888
Twines, Overman & Schrader Cordage Co.....	68,893
Underwear and corsets, muslin, Younker Bros.....	68,889
Vehicles and boats, certain road, Daimler-Motoren-Gesellschaft.....	68,925

LABELS.

"A Barker's Guarantee," for carpets, A. Barker.....	14,182
"Canadian Process Whiskey," for whiskey, Old Kentucky Whiskey Co.....	14,174
"Fairskin," for creams and lotions, M. Lowe.....	14,178
"4 Queens Brand of Evaporated Product of Apples," for an evaporated product of apples, J. W. Teasdale & Co.....	14,177
"Kaiser's Corn Root," for a medical preparation for the removing of corns from human feet, F. Kaiser.....	14,180
"Polly's Imported Furniture Cream," for a dressing for furniture, leather, or metals, G. B. Wilkins.....	14,181
"Queen Alexandrias of Judea Sweet-Violet Bath," for a bath powder, J. L. De Zeabault.....	14,179
"Red Rock," for aerated water, Red Rock Spring Water Co.....	14,175
"Stafo-life," for uncooked wheat bread, J. P. Thomas.....	14,176

PRINTS.

"Male apparel," for male apparel, Becker, Mayer & Co.....	2,270
"Rivets, washers, eyelets and sheet metal specialties," for rivets, washers, eyelets, and metal specialties, Edwin B. Stimpson Company.....	2,271

A printed copy of the specification and drawing of any patent in the foregoing list, or any patent in print issued since 1863, will be furnished from this office for 10 cents, provided the name and number of the patent desired and the date be given. Address Munn & Co., 361 Broadway, New York.

Canadian patents may now be obtained by the inventors for any of the inventions named in the foregoing list. For terms and further particulars address Munn & Co., 361 Broadway, New York.

LOOK FOR THIS LABEL

TRADE MARK

DESIGN PATENTED 1905

TRADE MARK

REG. U.S. PAT. OFF.

“Porosknit”

TRADE MARK

REG. U.S. PAT. OFF.

The Only Logical Summer Underwear For Men

¶ The cool comfort—the easy fit—the real satisfaction to be had by wearing “Porosknit” underwear makes the summer heat bearable. Close woven fabrics smother the body, but “Porosknit” (the open-work underwear) “lets the body breathe”—allows free circulation of air to the pores of the skin.

¶ One very vital thing to remember is the “Porosknit” label—it’s sewed on the neck band and drawer band of every genuine “Porosknit” garment. It’s important because there are very disappointing imitations of “Porosknit” that you want to avoid. There is only one “Porosknit.”

¶ “Porosknit” underwear comes in long sleeve, short sleeve and athletic shirts and ankle length and knee length drawers—50 cents the garment.

¶ “Porosknit” Union Suits for Men—\$1.00. If you can’t find “Porosknit,” write for our booklet “Inside Information.”

CHALMERS KNITTING COMPANY, 21 Washington St., Amsterdam, N.Y.

Shirts or 50¢ the Drawers 50¢ the Garment

LET US BE YOUR FACTORY
STAMPINGS, MODELS, EXPERT WORK
THE GLOBE MACHINE AND STAMPING CO.
970 Hamilton St., Cleveland, O.

ICE MACHINES Corliss Engines, Brewers' and Bottlers' Machinery, THE VILBER MFG. CO., 899 Clinton St., Milwaukee, Wis.

MODELS & EXPERIMENTAL WORK. Inventions developed. Special Machinery. E. V. BAILLARD. 24 Frankfort Street, New York.

RUBBER Expert Manufacturers Fine Jobbing Work
PARKER, STEARNS & CO., 228-229 South Street, New York

Experimental & Model Work
Civ. & advice free. Wm. Gardam & Son, 231 Fulton St., N.Y.

ELECTRIC GOODS.—Big Cat. 3 cts. Want Agents. Ohio Electric Works, Cleveland, O.

MANUFACTURING CAPITAL WANTED
Large European firm has now perfected a patent process which will entirely revolutionize every industry where painting, enameling, etc., is required. The process will save about 50 per cent. of labor, time and material and will by reason of its increase of efficiency and reduction in cost from the old process, give rise to many new industries. The invention is fully protected by patents all over the world and the firm is desirous of disposing of the patent, manufacturing and selling rights in the United States. Representative in this country is prepared to negotiate with interested parties having sufficient capital, the process can be seen in operation in New York City or in the European factories. Agents or brokers need apply, will deal with principals only or their Attorneys. For interview, address by letter only, RAPID, care of McMullen Co., 5th Ave. & 33d St., New York

MODELS & CHICAGO MODEL WORKS
ESTABLISHED 1867 179 E. MADISON ST. CHICAGO, ILL.
WRITE FOR CATALOGUE OF MODEL SUPPLIES

DIE WORK SPECIAL TOOLS MODELS NOVELTIES
Experimental Work for Inventors
H. TURNER TOOL CO., 215 E. Clinton St., Chicago

MASON'S NEW PAT. WHIP HOISTS
save expense and liability incident to Elevators. Adopted by principal storehouses in New York & Boston. Made by VOLNEY W. MASON & CO., Inc. Providence, R. I., U. S. A.

NOVELTIES & PATENTED ARTICLES
MANUFACTURED BY CONTRACT. PUNCHING DIES, SPECIAL MACHINERY. E. KONIGSLOW STAMPING & TOOL WORKS, CLEVELAND, O.

Magical Apparatus.
Grand Book Catalogue. Over 700 engravings 25c. Parlor Tricks Catalogue, free. MARTINKA & CO., Mfrs., 436 Sixth Ave., New York

THE SCHWERTLITZ STAMP CO.
STEEL STAMPS, LETTERS & FIGURES. BRIDGEPORT, CONN.

INVENTORS We manufacture METAL SPECIALTIES of all kinds, to order; largest equipment; lowest prices. Send perfect sample for low estimate and best expert advice. **FREE** THE EAGLE TOOL CO., Dept. A, Cincinnati, O.

LEARN PLUMBING
A trade that will make you independent for life. Hours shorter—Pay bigger—Demand greater than any other trade. You need no previous experience. Our practical methods enable you in a few months to hold position as skilled plumber or conduct your own business. Catalog sent free.
St. Louis Trades School
4428 Olive St. St. Louis, Mo.

LEARN WATCHMAKING
We teach it thoroughly in as many months as it formerly took years. Does away with tedious apprenticeship. Money earned while studying. Positions secured. Easy terms. Send for catalog.
ST. LOUIS WATCHMAKING SCHOOL, St. Louis, Mo.

FREE Squab Book
Mated pair kissing. — From eggs to squabs in 4 weeks. How to make money breeding Squabs
PLYMOUTH ROCK SQUAB CO., 361 Howard St., Melrose, Mass

VENTRILOQUISM
Learned by any Man or Boy at home. Small cost. Send to-day 2-cent stamp for particulars and proof.
O. A. Smith, Room 147, 2040 Knoxville Ave., Peoria, Ill

CEMENT BOOKS. How to Use Portland Cement 50c; Cement Sidewalk Construction, \$2.50; Hollow Concrete Block Building Construction, 50c. Sent postpaid.
CEMENT AND ENGINEERING NEWS, Chicago, Ill.

DIE MODELS SPECIAL WORK TOOLS MACHINERY
If made in metal, we can make it.
NATIONAL STAMPING AND ELECTRIC WORKS
158-159 S. Jefferson Street, Chicago, Ill.

INVENTORS, MANUFACTURERS SPECIAL TOOLS—DIES—LET US FIGURE METAL NOVELTY WORKS CO. 85-91 W. LAKE ST. CHICAGO

A VALUABLE INVENTION. Ellipsograph For Sale—Patented in United States, Canada and England. This patent is sure to make a fortune for some one; there is nothing like it in the world. Will sell rights for United States and Canada. Address R. KAATZ & CO., 301 Tacoma Bldg., Chicago.

MECHANICAL SPECIALTIES
for universal and exclusive introduction in European markets. Send lowest offers or samples to
Arthystie Co., Berlin W. S., Leipziger Str. 112

60 YEARS' EXPERIENCE

PATENTS

TRADE MARKS DESIGNS COPYRIGHTS & C.

Anyone sending a sketch and description may quickly ascertain our opinion free whether an invention is probably patentable. Communications strictly confidential. **HANDBOOK** on Patents sent free. Oldest agency for securing patents. Patents taken through Munn & Co. receive special notice, without charge, in the

Scientific American.

A handsomely illustrated weekly. Largest circulation of any scientific journal. Terms, \$3 a year; four months, \$1. Sold by all newsdealers.

MUNN & Co., 361 Broadway, New York
Branch Office, 625 F St., Washington, D. C.

DON'T BUY GASOLINE ENGINES UNTIL YOU INVESTIGATE "THE MASTER WORKMAN," a two-cylinder gasoline, kerosene or alcohol engine, superior to any one-cylinder engine; revolutionizing power. Its weight and bulk are half that of single cylinder engines, with greater durability. Costs Less to Buy—Less to Run. Quickly, easily started. Vibration practically overcome. Cheaply mounted on any wagon. It is a combination portable, stationary or traction engine. SEND FOR CATALOGUE. **THE TEMPLE PUMP CO., Mrs. Meagher and 15th St., Chicago.** THIS IS OUR FIFTY-FIFTH YEAR.


Garden Hose Rubber Belting Steam Packing Rubber Specialties

N. Y. BELTING & PACKING CO.
LIMITED

91 and 93 Chambers Street
NEW YORK

WRITE FOR CATALOGUE

The Only Pipe that Gives the Natural Tobacco Flavor. TURCO-AMERICAN GLASS PIPE



It has two bowls. An inner one of fine meerschaum, from which the smoke is drawn into an outer one of tough, annealed non-absorbent glass, through vents B-B. When tobacco burns to this point, vents B-B are closed by turning inner bowl A and the smoke is then drawn through vents C. This prevents steaming the tobacco and every grain burns to a white ash. All the nicotine is retained in the non absorbent glass bowl D. That's why only cool, clean smoke reaches the mouth—why the pipe never bites. No wet residue to throw away. No offensive smell in rooms or clothes. Easily cleaned. "Push" stem ferrule. Smoke it a week and if not satisfied money will be refunded. Pipe with case, \$2.00. Without case, \$1.50. Postpaid. State preference for straight or curved stem. Send for FREE Booklet, "History of Smoking."

TURCO-AMERICAN PIPE CO., 349 South Ave., Rochester, N. Y.

Scales All varieties at lowest prices. Best Railroad Track and Wagon or Stock Scales made. Also 1000 useful articles, including Saws, Sewing Machines, Bicycles, Tools, etc. Save Money. Lists Free. CHICAGO SCALE CO., Chicago, Ill.

LEARN TO BE A WATCHMAKER
Bradley Polytechnic Institute
Horological Department
Peoria, Illinois
Formerly Parsons Horological Inst.
Largest and Best Watch School in America
We teach Watch Work, Jewelry, Engraving, Clock Work, Optics. Tuition reasonable. Board and rooms near school at moderate rates. Send for Catalog of Information.

CRUDE ASBESTOS
DIRECT FROM MINES
PREPARED ASBESTOS FIBRE for Manufacturers use
R. H. MARTIN,
OFFICE, ST. PAUL BUILDING
220 B'way, New York.

City Conveniences in Country Homes
All the comforts of hot and cold water in the house, and running water at the barn, now possible for country residents and farmers. The
Niagara Hydraulic Ram
will pump water from any stream just where you want it. Cheaper than a gasoline engine or windmill. Write for booklet AA and guaranteed estimate. We furnish towers and tanks.
NIAGARA HYDRAULIC ENGINE CO.
110 Nassau St., N. Y. Factory, Chester, Pa.


GIANT STEAM SHOVELS
Toledo 125 Ohio, U.S.A. Vulcan Place
The Vulcan Iron Works Co.

Build Your Own Small Engine
We sell sets of castings up to 2 horse power. Also boilers, locomotives, gas engines, etc. 32-page catalogue for 10c. in stamps. This amount refunded on order amounting to \$1.00 or over. Contractors for light machinery of every description.
SIPP ELECTRIC AND MACHINE CO.
Keene St., Paterson, N. J.

A HANDY LITTLE TOOL
is our Rule Clamp No. 299 used to clamp two steel rules together—end to end—in extension. Rules may be of same or different widths up to 1 3/4 inches. Of special value to mechanics having tool chests smaller than 12 inches.
Price 50c. a pair
Send for 232 page catalog No. 18-B.
THE L. S. STARRETT CO., Athol, Mass., U. S. A.

LUBRICATES ANYTHING
SEND FOR SAMPLE
15-21 S. CLINTON ST.
CHESLEY & CO. FINEST USA

For Real Economy Get a CADILLAC



Repair Cost, 50 Cents a Week—Over 18 Miles per Gallon of Gasoline

Actual figures are the strongest argument for economy. Here they are—averages obtained from the sworn reports of a large number of single-cylinder Cadillac owners, taken at random from all over the United States, covering all imaginable road conditions—mountains, hills, sand, snow, mud. The story they tell is of vital interest to every prospective purchaser. Read it in

"The Truth About the Automobile and What it Costs to Maintain One"


sent free on request for Booklet No. 47.

These figures—by disinterested people—conclusively prove Cadillac economy. The cars themselves prove their service and durability. You see these sturdy, rugged little machines everywhere—always thoroughly alive to any test or requirement—always going. There are 16,000 in daily use; many of them in their sixth season, yet they are just as smooth, powerful and reliable as ever, with never even a suggestion of failing.


Capable of thirty miles an hour; offers the fullest complement of that pleasure, convenience and recreation which only a car like the Cadillac can afford. Described in catalog T47.

Prices include pair dash oil lamps, tail lamp and horn.

CADILLAC MOTOR CAR CO., Detroit, Mich.
Member A. L. A. M.



\$850



The Howard Watch

Hundreds of men are waiting for a thin watch they know something about—that they are sure is reliable and free from watch troubles.

Here at last is the king of flat watches—the New Howard extra-thin model about as flat as two silver dollars and a thoroughly accurate timepiece; a practical watch made in America. Each watch tested and timed in its case at the factory and accompanied by a certificate of guarantee—not only as a time-keeper but the HOWARD kind of a time keeper.

The thin model occupies less room; is easier to take out or

replace; does not drag down the waist-coat or bulge out when worn in the fob pocket.

Any Howard jeweler will be glad to show it to you whether you are ready to buy now or are merely interested in it as a triumph of American workmanship.

The price of each HOWARD watch is fixed at the factory and a printed ticket attached. Its value is the same everywhere and always. 17-jewel thin model, 25-year guaranteed filled case, \$37.50, up to 19-jewel, 14-K solid gold case, \$90.

If your jeweler cannot supply you, write to us for the name of one who will.

Eibert Hubbard visited the home of the HOWARD Watch and wrote a book about it. If you'd like to read this little journey drop us a postal card—Dept. P—we'll be glad to send it to you. Also a little catalogue and price list, with illustrations actual size—of great value to the watch buyer.

E. HOWARD WATCH COMPANY, Boston, Mass.

Cook Without Fire 75% of the Family Food—Save 75% on Fuel Bills—Save 75% Time and Trouble
—Food 75% Better Cooked

YOU can do all this—and keep COOL while doing it—with the CHATHAM FIRE-LESS COOKER—proved most successful by two years' experience—the greatest labor-saving—fuel-saving—and trouble-saving device known. Take any one of a hundred different Foods that are boiled—steamed or stewed. Heat them thoroughly on the range a few minutes—then put them into the

CHATHAM
Fireless Cooker


—and they will continue to cook until thoroughly done, without time—trouble—or fuel. No danger of burning or boiling dry. 125 recipes of things to be cooked in the Chatham Fireless Cooker sent with every Cooker. The genuine Chatham Fireless Cooker is sold by responsible dealers everywhere. If not on sale at your dealer's write me direct for free booklet and I will see that you are promptly supplied. Manson Campbell, President.

THE MANSON CAMPBELL COMPANY, Ltd.
Factory: 806 Wesson Ave., Detroit, Mich.
Branch Houses: 82 E. 3rd St., St. Paul, Minn. 1308 W. 11th St., Kansas City, Mo.
Address nearest office. Canadian trade can be supplied from Chatham Factories at Chatham, Ont. Canadians, please address me for booklet and other printed matter.



The Latest and Best A. W. FABER "CASTELL" DRAWING PENCILS
They take the finest point obtainable of any lead pencil, are least liable to wear, therefore more lasting than any others.
Sold by all stationers and dealers in artists' materials. Sample sent to all parties interested on receipt of 10 cents in postage stamps.
A. W. FABER, 49 Dickerson Street, Newark, New Jersey

THE RACING MACHINE SPARK PLUG
The "CENTERFIRE" Plug—Power increased 10 per cent. each explosion. Ignition in center of compression. Soot proof, quick action, perfect combustion. Agents Wanted. Sample Plugs, \$1 each. Give name of car and year. Write
GENERAL ACCUMULATOR & BATTERY CO., 128 Second St., Milwaukee, Wis.



The Actual Worth

Of an adding and listing machine is in what it does, how it does it, and how long it will do it. The Universal Adding and Listing Machine will produce the maximum of nice, clean, clear-cut, accurate work with the least effort, and it will last longer under any kind of use than any other adding and listing machine ever built.

The Universal always adds what it prints and prints what it adds—it prints in just as perfect alignment after years of hard use as the day it left the factory.

The key action is light; the handle pull is smooth and easy; the adding register is in plain view, just above the keyboard; items to be added are printed in black, blue or purple, and the totals and sub-totals are always printed in red, right next to the last item. No blank stroke of the handle is necessary before taking a total.


There are so many other important features on the Universal that are advantageous for you on your work that you ought to write and tell us about your class of work and learn what the Universal will do for you, and how it will do it easier and faster than you are doing it at present.

There is no charge or obligation attached to your getting all this information. Can you afford not to write us now?

Universal

Adding Machine
Company

3835 Laclede Avenue
ST. LOUIS



PIERCE MOTOR BOATS
\$150.00 and up
PIERCE MOTORS
\$37.50 and up

Send stamps for catalog.
Satisfaction guaranteed or money refunded.
PIERCE ENGINE CO., 24 West Street, Racine, Wis.
1421 Michigan Avenue, Chicago
Siegel-Cooper, New York City Butler Motor Car Co., Boston

Everything for the Automobile

SUPPLIES AND PARTS AT LOWEST PRICES
Our 1908 Catalog just out—200 Pages, 1,000 illustrations, 5,000 descriptive prices. Sent Free
NEUSTADT AUTOMOBILE AND SUPPLY COMPANY
3932 Olive Street, St. Louis, Mo.

ARE YOUR EYES NORMAL?

If not, it will be very much to your interest to send for our Illustrated Treatise **The Eyes, Their Ills and Their Care.** It gives very valuable detailed information on eye-weaknesses and their results; also how they may be prevented. The regular price of this Treatise is 25 cents but we will send it for a limited time on receipt of 10 Cents in stamps or currency. There may be information therein which will be especially valuable to you, so we suggest that you write for it today.
THE IDEAL CO., Dept. 45, 321 Fifth Ave., NEW YORK

GOES LIKE SIXTY SELLS LIKE SIXTY \$60
GILSON GASOLINE ENGINE
For Pumping, Cream Separators, Churns, Wash Machines, etc. FREE TRIAL. Ask for catalog—all sizes.
GILSON MFG. CO. 308 Park St. Fort Washington, Wis.

A MONEY MAKER
Hollow Concrete Building Blocks Best, Fastest, Simplest, Cheapest Machine. Fully guaranteed.
THE PETTYJOHN CO.
615 N. 6th Street, Terre Haute, Ind.

Second-Hand Bargains

Automobiles of every standard make at half their values. Runabouts \$100 to \$350; Touring Cars \$250 to \$1500; Limousines \$500 to \$2500; Roadsters \$750 to \$1500. All makes and models including '08 cars. Packard, Peerless, Pierce, Pope-Toledo, Rambler, Ford, Reo, Cadillac and many other makes. Every car guaranteed. Shipped on approval. Special proposition to good agents. Complete Catalog on request.
MISSISSIPPI VALLEY AUTO CO., Dept. B St. Louis, Mo.

MENNEN'S BORATED TALCUM TOILET POWDER for After Shaving.
Insist that your barber uses Mennen's Toilet Powder after he shaves you. It is Antiseptic, and will prevent any of the many skin diseases often contracted. A positive relief for Prickly Heat, Chafing and Sunburn, and all afflictions of the skin. Removes all odor of perspiration. Get Mennen's—the original. Sold everywhere, or mailed for 25 cents. Sample Free.
GERHARD MENNEN CO., Newark, N. J.

MILLIONS for TEN THOUSAND DOLLARS
Will sell patent for Land and Water Vehicles; latest improvements; safer, swifter, lighter than automobile on land and rapid boat on the water. Investigate
JOYCE MFG. CO., Macdonald, Sask., Canada